ARCTIC WASTE DISPOSAL

SOME PROBLEMS OF SOLID AND LIQUID

WASTE DISPOSAL IN THE NORTHERN ENVIRONMENT

A series of 8 reports by

Technical Branch,

Environment Protection Service,

Department of the Environment

Northwest Region

and

Professor G. Heinke,

Department of Civil Engineering,

University of Toronto

for the

Environmental-Social Program

Northern Pipelines

July 1974

The data for these reports were obtained as a result of investigations carried out under the Environmental-Social Program, Northern Pipelines, of the Task Force on Northern Oil Development, Government of Canada. While the studies and investigations were initiated to provide information necessary for the assessment of pipeline proposals, the knowledge gained is also useful in planning and assessing highways and other development projects.

The research was carried out and the report was prepared under contract for the Arctic Land Use Research Program, Northern Natural Resources and Environment Branch, Department of Indian Affairs and Northern Development. The views, conclusions and recommendations expressed herein are those of the authors and not necessarily those of the Department.

CONTENTS

REFUSE SACK COLLECTION
SYSTEM STUDY

by

K. R. Heuchert

Technical Branch
Environmental Protection Service
Northwest Region
Environment Canada

March 1974

TABLE OF CONTENTS

LIST OF FIGURES

1. SUMMARY

This investigation was concerned with determining the acceptability of the refuse sack collection system for use in the North. The study was carried out at Aklavik and Wrigley, N.W.T.

A number of difficulties were encountered during the study, resulting in Aklavik abandoning the project almost immediately after start-up and Wrigley discontinuing the use of the sack system approximately four months after start-up.

One of the main reasons for the project abandonments was that the residents of the two settlements could see no advantage to the refuse sack collection system over the previous collection methods. The two communities had well-managed collection systems before the refuse sack project was initiated.

2.   INTRODUCTION

The collection of domestic refuse is probably the most difficult phase of the solid waste problem in the Canadian North.

Costs that might be incurred in northern communities, compared to southern communities, are probably much higher. This can be partially attributed to the harshly adverse winter conditions in the North which make the pick-up and transportation of refuse very difficult.

At present, in most communities, domestic refuse is deposited in garbage cans or 45-gallon drums prior to pick-up. During winter months refuse tends to freeze to these containers, making the work of the collection personnel all the more difficult. There is also a tendency for these containers to become the focal point for congregations of dogs and ravens, thus resulting in the refuse being scattered over relatively large areas and adding to the already difficult problem of collection.

A health hazard may also be created, in particular, when sewage bags are a part of domestic refuse, as is the case in many northern communities.

At most northern work camps, refuse is stored in large garbage cans, lined with plastic bags. When these containers become full, the plastic bags are removed and new ones inserted. These bags, containing the refuse, are then incinerated. There can be a problem if the refuse is stored outdoors prior to incineration. During winter the plastic becomes brittle and easily ruptured.

The refuse sack collection system offers a feasible alternative to those methods being employed at present. Its potential for use in the overall waste management program at a pipeline construction camp was discussed in the report "Management of Waste from Arctic and Sub-Arctic Work Camps" by Grainge et al (1973).

In order to evaluate the usefulness of large paper sacks in replacing garbage cans and barrels, a small project was set up in two communities, Aklavik and Wrigley, N.W.T. Holders for the refuse sacks were attached to approximately twenty homes in each of the two communities.

The main objective of the study was to determine the overall acceptability of replacing metal containers with wet strength paper refuse sacks in northern Canada. The acceptability was related to:

        (a) handling,
        (b) aesthetics,
        (c) personal preference.

It was anticipated that this study would be very useful
in determining the acceptability of the refuse sack
system for northern work camps. Pipeline work camps in the
Mackenzie Valley are expected to have populations of up to
and possibly greater than 600 people. This is the
approximate size of Aklavik, N.W.T.

These small industrial communities will require a sound
solid waste management program, part of which will be an
acceptable in-house storage and collection procedure. The
paper refuse sack collection system is one alternative which
should be considered.

3.   CURRENT STATE OF KNOWLEDGE

Large paper refuse sacks are commonly used for domestic refuse in such places as Greenland, Denmark, Norway, Sweden, Finland and England. Grainge (1969, 1974) has indicated that this method of in-house storage works very well and is totally acceptable.

These refuse sacks are approximately 1/3 cubic metres in size and are either hung from holders attached to the exterior of the homes or fitted into compartments accessible from both inside and outside the residence. Figures 1 to 3 show typical holder and bag set-ups in Greenland.

Domestic refuse is generally hauled in open trucks in Green-land, which is the same as that method used in northern Canada.

An extensive study was carried out for the City of Inglewood, California, by Stone and Company Inc. (1972). The results of that study indicated a general acceptability of the refuse sack collection system.

Refuse sack collection systems of this type have not previously been used in northern Canada.

Figure 1

Figure 2

Standard plastic-impregnated, double thickness, paper garbage bags, which will withstand rain. In the best arrangement, the bag fits into compartment of house which is accessible by air-tight trap from inside and by door from outside. (after Grainge, 1969)

Figure 3

Typical Cleanup at Residence
(Note garbage container with
metal lid.) (after Grainge, 1969)

4. STUDY AREAS

Through the assistance of the Department of Local Government,
Government of the Northwest Territories, Department of
National Health & Welfare, Yellowknife, N.W.T. and
Department of Public Works, Government of the Northwest
Territories, two communities were chosen for the pilot
project. One of the conditions in choosing the sites was
that the settlement managers have a genuine interest in the
project. With this in mind, the two communities, Wrigley
and Aklavik, were chosen. Approximately twenty homes in
each community participated in the study.

Wrigley is a settlement located along the east bank of the
Mackenzie River approximately 114 air miles north of Fort
Simpson at 63°13'N latitude and 123°23'W longitude. The
population of Wrigley is approximately 200. Hunting,
trapping and fishing are the basis of the economy of the
settlement. The community also has a small saw mill.

The residents of Wrigley were using 45 gallon drums for refuse
storage and burning prior to pickup. The refuse disposal
area is a small dump site, just outside the town. Pit
privies are common, resulting in no sewage bags being
disposed of with the refuse.

The study was initiated at Wrigley in July, 1973.

Aklavik, the second community chosen for the study, has
an approximate population of 600 and is located 35 air
miles west and south of Inuvik on the west shore of the
Peel Channel at 68°12' N latitude and 135°00' W longitude.
Fur production and manufacture of fur garments and handicrafts
are the main economic base of the settlement.

Sewage bags and domestic refuse are picked up and hauled on
a contract basis to a dump site.

The refuse sack study was initiated at Aklavik in August,
1973.

Two types of refuse sacks were used at the two settlements
for this investigation.

1. Galvanized holders with 2-holed bracket for
    securing to the sides of houses or backyard fences
    (11 1/2" wide x 16" long). Jaw type clamp for
    securing paper bag to holder.

2. Bag Types: (i)   26" x 42 3/4" pasted open mouth
                      2/60 wet strength paper.

                (ii) 26" x 42 3/4" x 10" pasted open mouth
                      2/60 wet strength paper with 1 1/2
                      mil free film liner 26" x 49"
                      inserted and cut flush with bag
                      length.

3. Printing: Refuse Sack System. Pilot Project by
               Department of Local Government, N.W.T.
               and Environment Canada, Environmental
               Protection Service, Northwest Region.

The refuse sacks were purchased from Consolidated Bathurst
Packaging Ltd., Calgary, Alberta.

Figure 4 is a schematic diagram of the holder and refuse sack
arrangement. Figures 5 and 6 are photographs of holders and
sacks installed at Aklavik, N.W.T.

REFUSE SACK HOLDER

30 cm

40 cm

REFUSE SACK SYSTEM

FIGURE 4

Figure 5 - Holders and bags attached to homes in Aklavik, N.W.T.

Figure 6 - Holders and bags attached to homes in Aklavik, N.W.T.

5. METHODS AND SOURCES OF DATA

The pilot study results were strictly subjective. The most valuable information was obtained from the settlement managers since they are in charge of the operations of the settlements. The views of the refuse collection personnel were also of great importance, for obvious reasons.

The settlement manager, settlement secretary, collection personnel and study participants in Wrigley were contacted approximately two months after the study was initiated. An Environmental Protection Service employee also visited the community during March, 1974. The Aklavik settlement manager, settlement secretary, settlement chairman, councillors, collection personnel and members of some of the participating families were contacted during February, 1974. Earlier contacts with the settlement manager during 1973 had also been made.

6.   RESULTS

6.1 Aklavik

Shortly after the study was initiated at Aklavik the project was abandoned by the settlement.

The reasons given for discontinuing the use of the refuse sack collection system were as follows:

1.   There was a conflict of interest between the refuse and sewage hauling contractors. (An attempt had been made to combine the two collection activities.) The solid waste hauling contractor would not collect refuse sacks containing sewage bags and likewise with the sewage hauling contractor because the refuse sacks containing sewage bags also contained dry garbage. This led to a stalemate and as a result several bags were still full, six months later, hanging from the holders.

2.   The residents did not like the holders attached to the sides of the homes. They thought it would be better to have the bags in containers at the edge of the street. There were also complaints that the holders were placed too high for easy access, or were not fastened properly and therefore did not remain attached to the homes. The latter was probably due to children hanging on them, in the opinion of the settlement manager.

3.   The settlement felt the project had been forced upon them.

6.2 Wrigley

On September 28, 1973, two months after the study initiation, a questionnaire was prepared. These were filled out individually by a representative of the Environmental Protection Service during personal interviews at each of the residences.

The Wrigley residents had the opportunity of using both types of bags. The bags were replaced by the collection personnel so the type of bag used depended solely on what the collection men distributed.

The following is a brief summary of the pertinent questions asked and the answers received during the September visit.

Question 1.   Do you prefer this method of collection over the method used before?

Pro: 50%
Con: 50%
Comment: Most who wished to continue this
          type of garbage collection, provided
          no reason to support their opinion.

Question 2.   Comment on the size of bags.

a)   much too large   0%
b)   too large   0%
c)   right size   40%
d)   too small   60%
e)   much too small   0%
Comment: 85% of the people who wanted to dis-
          continue the paper bag study said the
          bags were too small for their purposes.
          70% of the people who wanted to
          continue using the paper bags said
          the bags were the right size.

Question 3.   Are the bags strong enough?

Only one person out of fourteen was dissatisfied
with the strength of the bag whether it be wet
strength or polyethylene lined.

Question 4.   Approximately how many bags have been damaged
               or broken?

35% of the total people interviewed reported
no damaged or torn bags.
The remaining participants stated that they
had experienced one or two incidents of torn
bags.

Question 5.   What difficulties have you experienced with using
               refuse bags for storage and collection?

a)   Children play with the bags and tear them.
b)   Contradictory comments on dogs tearing
     the bags but no actual occurrences.
     There were some comments on dogs not being
     able to smell through plastic.
c)   One interviewed person simply said he
     did not like the paper bag.
d)   Difficult to dispose of cardboard boxes
     and bulky items of this nature.
e)   Placing the holders higher from the ground
     would place the bags out of reach of the
     dogs; however, the bags would then be
     inaccessible to the user.

Summary of the Settlement Manager and Refuse Collectors, both sharing the same opinion:

The frequency of collection (twice per week) had not changed with the introduction of the new system. Cleanliness of the yards had not improved or degenerated as a result of the paper bag system. The streets were aesthetically more appealing as a result of the removal of the 45 gallon barrels. Space requirements for the landfill site had not changed as the new system was introduced. Ease of handling of the garbage had improved.

During November, 1973, the settlement council decided to discontinue the use of the refuse sack system. Their reasons for ending the investigation were as follows:

1. The bags were being torn by dogs resulting in refuse being strewn around the yards. The end condition was more objectionable than when the 45 gallon drums were being used.

2. The bag system was not necessary because Wrigley has always been a tidy community and garbage collection and disposal was not a problem.

The observations of the Environmental Protection Service employee who visited Wrigley in March 1974 were that the barrel system of storage and pickup was working very well. The barrels were along the roadside away from the homes. The yards were very clean and there did not appear to be any problem with refuse being scattered around.

7. DISCUSSION

The abandonment of the pilot project at Aklavik indicates that the approach taken for evaluating this system was unacceptable. It is the opinion of the author that there were two basic reasons for the project termination:

1. The residents did not feel that they were involved in the study.

2. It is very difficult to propose changes to existing ways of life and expect the people concerned to accept these changes immediately.

The Wrigley study did prove that the system will work. They did not have any major difficulties until approximately four months after the study initiation.

Unfortunately, when the use of the refuse sack system was abandoned in both Aklavik and Wrigley, no one within the Environmental Protection Service was notified of the difficulties the communities were experiencing. Perhaps the problems could have been overcome. The author is confident that if the Territorial Government had been responsible for the investigation, the project would not have terminated in the manner in which it did. A better response would probably be obtained if the Territorial Government was responsible for the project, relying only on the Environmental Protection Service for advisory support.

The residents of Aklavik and Wrigley have decided that they would rather use the 45 gallon drums instead of the bag system. It is therefore impossible to reinstate the project in either of these communities.

The author believes that the refuse sack collection system, if implemented in the North, would be a great improvement over the collection systems presently being used in most communities. The greatest problem is trying to overcome an established practice. Serious consideration should be given to implementing in-house refuse sack storage systems when designing new northern homes.

The introduction of the refuse sack system into a pipeline construction camp would be relatively simple as compared to instating it in an established community. Pipeline camps would require careful planning concerning waste management and servicing. Because these communities will be constructed anew, it would be very simple to include the refuse sack system in the overall program of solid waste handling.

8. CONCLUSIONS

1. There must be a genuine interest on the part of the users of the refuse sack system in order for it to work.

2. The Aklavik and Wrigley residents could see no advantage in the refuse sack system over the existing systems.

3. The problems encountered to date in the settlements are unlikely to exist at northern work camps.

4. Bulky items such as cartons should be placed separately beside the garbage as is common in most of Canada. For example, an empty carton could be filled with garbage and placed beside the bag.

5. The Government of the Northwest Territories should be responsible for future refuse sack studies at northern communities, relying on Environmental Protection Service staff for technical support only.

9. IMPLICATIONS AND RECOMMENDATIONS

In designing and constructing new residences and services for pipeline construction camps, in-house facilities to accommodate the use of the refuse sack system should be considered as a part of the overall waste management program.

10. NEED FOR FURTHER STUDY

The refuse sack system should be evaluated at a northern work camp.

11. REFERENCES

Grainge, J.W., 1974, Personal communications.

Grainge, J.W., Edwards, R., Heuchert, K.R., and Shaw, J.W.,
    1973, Management of Waste from Arctic and Sub-Arctic
    Work Camps; Report No. 73-19 for the Environmental
    Social Committee, Northern Pipeline, Task Force on
    Northern Oil Development.

Grainge, J.W., November 12, 1969, Study of Environmental
    Engineering in Greenland and Iceland; Manuscript Report
    No. NR-69-5, sponsored by the World Health Organization.

Stone and Company Inc., 1972, The Use of Bags for Solid
    Waste Storage and Collection, prepared for Environmental
    Protection Agency, distributed by National Technical
    Information Service, U.S. Department of Commerce, 5285
    Port Royal Road, Springfield, Va.   22151.

WORK CAMPS SEWAGE DISPOSAL
WASHCAR - INCINERATION COMPLEX

by

A. CAM EDWARDS
RICHARD FAHLMAN

Technology Programs Section

Technical Branch

Northwest Region

Environmental Protection Service

Environment Canada

March, 1974

CONTENTS

APPENDIX I*

LIST OF FIGURES

LIST OF TABLES

1. SUMMARY

The workcamp sewage disposal study outlined in this report investigates an alternative to conventional methods of sewage collection and disposal for northern camps. This method of sewage treatment will be of primary importance in areas where water supplies are limited or in areas such as high ice content permafrost zones, where the construction of sewage lagoons is undesireable.

The complete system is composed of two portable trailer units connected by a utilidor. The first trailer is a washcar containing vacuum and chemical recirculating toilets, urinals, washbasins, showers, clothes washers, driers, a sauna, and ancillary equipment. The second trailer houses the sewage holding tank, incinerator and associated equipment. Liquid wastes are collected by the vacuum and recirculating toilet systems and pumped to a holding tank in concentrated form. Contents of the holding tank are then discharged to the incinerator for high temperature combustion.

Results of the study to date show the water consumption of the vacuum toilets to be approximately 1.5 litre/flush, considerably less than the 15-25 litres used in conventional units. It was found that the vacuum and chemical recirculating toilets saved approximately 22,500 litres of water per month, and limited the total monthly water consumption to 51,500 litres for the period under study. However, the showers and washing machines consumed most of the total water supply and future studies are required to investigate methods for further water conservation in these areas.

Certain drawbacks are inherent in the system, such as the high cost of self-sufficiency involved with electrical power generation and requirements for supervisory personnel for maintenance, repair and sewage incineration.

From the initial stages of the study, it is thought that the system is a feasible alternative to conventional means of sewage treatment, and further studies are required to determine user response and equipment capabilities over an extended time period. Also, tests concerning incinerator operating efficiency and stack emissions have not yet been concluded.

2. INTRODUCTION

2.1 Nature and scope of study

At present, the methods of wastewater collection and
disposal used for construction camps in the N.W.T. are
basically of two types, sewage lagoons and trucked systems
for holding tank wastes. There are inherent drawbacks to
both of these methods. The applicability of a sewage
lagoon is dependent upon specific site conditions. Such
factors as availability of fill material for berm construc-
tion, drainage patterns, depth of the water table and soil
permeability, must be suitable for lagoon construction. In
areas of permafrost, lagooning may be further complicated by
the presence of ice wedges or high ice content soils, and
by the problem of thermokarst development. The disposal of
effluents may also be a problem and the reclamation of
abandoned lagoons can be difficult and expensive. The trucked
system for holding tank wastes is primarily a method of collec-
tion and does not involve treatment processes. Sewage and
kitchen wastes are piped into a large holding tank which is
periodically pumped to a tank truck and removed for disposal.
This method of disposal usually involves the discharge of the
waste water directly to land. From an environmental and
public health standpoint, such a method is undesirable.

This study involves an assessment of the operational cha-
racteristics of a washcar-incinerator complex and determining
whether such a unit is a feasible alternative to the above
methods for the collection and disposal of fecal wastes in
northern construction camps. The complex is composed of two
mobile trailers; an incinerator, and a washcar which contains
two types of vacuum toilets (Vacusan, 2 units and Vacu-Flush,
1 unit) and 2 chemical recirculating toilets (Jet-O-Matic),
as well as regular washbasins, urinals, showers, clothes
washers, driers and a sauna. (Fig. 1-3).

Feces, from the flush toilets, are drained by vacuum into a
holding tank situated in the washcar. When the tank is full
the vacuum is released and the contents are pumped via a
utilidor into a holding tank in the incinerator trailer where
the sewage is macerated then pumped into the incinerator for
combustion. The chemical recirculating toilets, when full,
are also pumped into the holding tank in the incinerator car.
Figure 4 gives the plumbing system for the washcar.

2.2 Specific Objectives

2.2.1 To assess the general performance and user preferences
for the 3 types of toilet units and to determine their
water conservation capabilities.

2.2.2   To assess the performance of the incinerator in
        terms of power and fuel requirements, combustion
        efficiency and stack emissions.

2.2.3   To determine, from the above and other related
        information, the economic and operational
        feasibility of this type of unit as a method
        of waste disposal for northern camps.

2.3   Relation to proposed pipeline development

If construction of a pipeline through the Mackenzie Valley
is undertaken, a proliferation of transient construction
camps would be anticipated along the proposed route. It
would be beneficial for construction contractors and super-
visory personnel to have available rugged sewage collection
and disposal systems which are portable, consume minimal
amounts of water, and which keep discharges of wastes to
the environment at a minimum. The prototype washcar-
incinerator complex involved in this study could possibly
meet these requirements.

Fig. 1   Interior of washcar,
         sauna entrance in background

Fig. 3   Feces incinerator
         furnace

Fig. 2   Exterior of incinerator
         trailer

PLUMBING SYSTEM FLOWPLAN – FOR WASHCAR   FIGURE 4

3. CURRENT STATE OF KNOWLEDGE

The use of vacuum toilets and liquid waste incinerators is
still a relatively new field in sanitary engineering. Their
viability in northern climates as an alternative to
conventional methods of collection and disposal of sewage
is still unproven, except in isolated case studies (Averill
and Heinke, 1973; Miholits, 1961; Baribo, 1957). This study
will provide information gathered on a long-term basis,
under actual camp conditions, as to the feasibility of such
a disposal method.

4. LOCATION OF STUDY

The washcar trailer and incinerator complex is presently
situated at DPW Workcamp #1, Ft. Simpson, N.W.T. It
is planned to move the trailers to another, larger
workcamp to allow the unit to be observed operating at
full capacity and, also, to supply information as to the
general mobility of the trailers and requirements for
re-installation after transport.

5.   METHODS AND SOURCES OF DATA

5.1   Water, Power and Fuel Consumption

Meters were installed to monitor the following:

  a) total washcar water consumption

  b) shower and laundry water consumption
     (two meters, hot and cold)

  c) urinal and lavatory consumption was
     calculated from the above i.e. a-b=c

  d) vacuum toilet water consumption. Wash water is
     recycled, through a water meter, from a holding
     tank below the hand basins to the vacuum toilets.

  e) electrical power consumption for both the washcar
     trailer and the incinerator trailer.

The chemical toilets were charged with a known quantity of
water. Fuel oil consumption for heating the washcar trailer
and for incinerator fuel was not metered, but consumption
rates could be derived from the known fuel tank sizes and
records of the volumes purchased.

5.2   Maintenance

Records of repairs and maintenance requirements are kept for
all equipment. In particular, these records will be useful
for comparing the durability and performance of the two types
of vacuum toilets and the chemical recirculating toilets.

5.3   Operator Requirements

From daily observations of the washcar-incinerator operations,
a set of recommendations regarding operator duties and responsi-
bilities will be formulated.

5.4   Analysis of User Preferences

Preferences of the workcamp members for the various types
and makes of toilet units will be determined quantitatively
by the use of flush counters which are installed in the
toilet units and which record the number of times each was
used. A subjective assessment of the attitudes of the workmen
towards the toilet units and the sauna will be made through
conversations with the men.

5.5 Incinerator Operation

Operating characteristics of the incinerator unit with regards to furnace temperature, oil feed rate, air supply pressure, efficiency of organics destruction, and stack emissions will be determined.

6.   RESULTS

6.1   Water, Power and Fuel Consumption

Table 1 gives the weekly and month end summary of the
water consumption and power requirements for the washcar.
The total water requirements for the month (28 days) was
51,300 litres or 100 lpcd. The vacuum toilets consumed
940 litres of water through the last 3 weeks of operation,
at an average of 1.5 litres/flush. The chemical toilets
required less water, 65 litres/charge, each charge lasting
100 flushes, under the present infrequent use. The amount
of water used in the chemical toilets for the first month
of operation was approximately 157 litres. Thus, the total
toilet water consumption for the first month can be estimated
to be in the range of 1350 to 1515 litres.

The washcar consumed approximately 80 kwh/day of electrical
power, regardless of the camp size. Extended use of the
sauna, which is rated at 9 kW, may eventually raise this
figure. Fuel consumption of both the washcar and incinerator
has not been investigated to date.

6.2   Maintenance

All of the equipment in the washcar was found to perform
satisfactorily but daily checks are required to ensure their
continued operation. The Vacu-Flush toilet system was initially
plugging due to insufficient vacuum but this problem has been
rectified.

When sewage is being pumped from the toilet holding tanks to
the incinerator car, care must be taken to ensure that the
macerating pumps do not run "dry". They must be shut-off
immediately upon completion of pumping or pump seizures will
develop.

6.3   Operator Requirements

To ensure proper performance of the units, the operator should:

1.   Ensure the safety, security, cleanliness and habitability
        of the units.

2.   Maintain adequate supplies of fuel oil and water.

3.   Ensure all equipment including pumps, motors, valves,
        toilets, etc. are operating correctly and effectively.

4.   Incinerate sewage when necessary; the operator must pump
        the stored sewage from the washcar to the incinerator
        car holding tank thence to the incinerator.

TABLE 1

UTILITIES CONSUMPTION

WEEKLY AND MONTH-END SUMMARY

| | Water Consumption (litres) | | | | Elect Power kwh | Camp Attendance |
	Meter #1 Total Water	laundry & showers Meter #2 Cold	Meter #3 Hot	Meter #4 Toilet		
Week #1						
Total	15048	6500	4780	650	–	175
Daily Avg.	2149	928	680	93	–	25.0
Week #2						
Total	13815	4666	4585	420	530	152
Daily Avg.	1973	666	655	60	75.7	21.7
Week #3						
Total	3630	5540	4300	300	601	110
Daily Avg.	1947	790	610	43	85.9	15.7
Week #4						
Total	8833	3325	2240	220	556	88
Daily Avg.	1261	475	320	31	79.4	12.6
4 Week Total	51327	20034	15903	1590	1,687✫	525
Weekly Average	12831	5008	3975	400	562.3✫	131.3
Daily Average	1833	715	567	56	80.3✫	18.8

✫ Three weeks used as basis for calculation
✫✫ 30 gal/mo. required to charge the chemical toilets not included in data

5. Ensure all freeze-up prevention equipment including furnaces, heat tape, insulation, etc. are operating effectively.

6.4   User Preference

A summary of the weekly toilet flush counts is given in Table 2. As shown in the table, the vacuum toilets received a much greater usage than the chemical (Jet-O-Matic) recirculating toilets. The vacuum toilets were preferred by the patrons because they most resemble conventional flush toilets. The chemical toilets emit an inoffensive chemical odor and the user must ascend a large step before use. They are slower acting in the flush cycle and comparatively quiet in flush operation, giving the user a feeling that they are under-designed.

The comments made by the washcar patrons included humorous anecodotes about the drawing power of vacuum if the toilet was flushed while the user was seated. Various names such as "Atomic Toilet" have been tagged to the washcar-incinerator complex. The noise emanating from the vacuum toilets greatly exceeds that of standard flush toilets.

6.5   Incinerator Operation

Study has not been completed as yet. Table 3 gives some data on the results of a trial incineration conducted on September 24, 1973.

TABLE 3

INCINERATION - SEPT. 24/73

Time	Inc.[1] Temp (^{o}F)	Waste Liquid[2] Pump Setting (Revolutions)	Air Temp[3] (^{o}F)
10:45 a.m.	-	-	52
11:08	1460	3	58
11:31	1420	8	65
11:40	1400+	13	68
11:50	1380+	17	71
12:00 noon	1360+	17	73
STOP INCINERATION SEQUENCE			
START INCINERATION SEQUENCE			
2:20 p.m.	560	-	70
2:35	1460	3	71
2:53	1440	8	-
2:56	1420+	13	76
3:06	1400+	17	78
3:56	1460	24	89
4:16	1400+	28	91
4:25	1400+	28	91
4:31	1400+	28	92
4:41	1400+	28	92
4:52	1410+	28	93
5:00	1410	28	94
5:01	1410	28	-
5:05	1200	-	95
5:08	1500	-	95
5:10	1440	28	96
5:15	1420	28	95
5:25	1420+	28	95
5:30	1440	28	94
5:32	1440	28	94

(1) Temperature inside incinerator.
(2) Worm gear revolutions

    0 rev. setting = no flow rate
   28 rev. setting = max. flow rate at max. gear setting
   (approx. 135 gal./hr.)
(3) Temp. within incinerator trailer, close to power
    supply panel.

Notes
10:45 a.m. - 12:00   Waste water incineration rate 54   imp gal/hr
  4:31 - 5:00 p.m.   "   "   "   " 130 "   "   "
  5:08 - 5:32 p.m.   "   "   "   " 144 "   "   "

TABLE 2

WEEKLY TOILET FLUSH COUNTS

Toilet	Week #1	Week #2	Week #3	Week #4	Total 4 Weeks
#1 Vacusan	103	106	94	84	387
#2 Vacusan	106	79	57	34	276
#3 Vacu-Flush	not recorded	87	34	30	151
#4 Jet-O-Matic	42	35	25	19	121
#5 Jet-O-Matic	flush counter removed		–	–	–
Camp attendance (man days)	25.0	21.7	15.7	12.6	18.8

Note: – The term "man days" refers to the average daily camp
attendance for each seven-day period.

– The flush counter installed on toilet #5 was removed
after the first week, and relocated on toilet #3.
Toilet #5 was getting very little use and toilet
#3 was installed by the manufacturer without a flush
counter.

7. DISCUSSION

Average water consumption in construction camps has been rated by Fair et al (1966) at 45 lpcd (U.S.), but this includes kitchen consumption, drinking water, etc. A breakdown, by the above authors, of domestic (urban) water consumption apportions the uses as follows:

    a) 41% to flushing toilets
    b) 37% to washing and bathing
    c) 6% to kitchen use
    d) 5% to drinking
    e) 4% to washing clothes
    f) 3% to household cleaning
    g) 4% to miscellaneous activities

Thus, the washcar requires approximately 85% of the total camp water. Based on the above construction camp rating, the washcar patrons, using conventional flush toilets would consume

    143 lpcd. (45 US galls x .85 x 3.8)= 143

The following calculations give two separate estimates of the volume of water saved during the first month of operation:

I. (143 - 98) litres x 28 days x 18.8 man days

    = 23790 litres

II. 1156* flushes x 22.5 litres/flush (conventional toilets)

    = 2600 litres

From the above calculations it can be assumed that the washcar installed toilets saved the camp in excess of 21,100 litres for the period under study. Much greater savings would be realized with a larger camp size. Discussion of the other aspects of this study, as well as further comment on water consumption, will be dealt with at a later date when more data are available.

*Note: The first week flush count for the Vacu-flush toilet was estimated to be similar to the Vacusan units (approx. 100). Usage of the #5 Jet-O-Matic toilet was assumed to be the same as the #4 toilet.

8. RECOMMENDATIONS

Although toilet water consumption has been reduced, further attempts should be made to further curtail the overall water usage. This could possibly be achieved through the use of shower water timers and washing machines with low water requirements. Meters to measure kitchen and laundry water use should be installed to provide further information on total consumption.

At capacity, the washcar is designed to handle 40 patrons. With an average daily consumption of approximately 90 litres/person the 4500 litre holding tank is underdesigned. At present, the operator has difficulty maintaining adequate water supplies, especially over holiday and week-end periods of maximum usage. The future water storage capacity for washcar trailers maintaining camp sizes of this nature should be in excess of 9000 litres.

Future designs should possibly consider a third trailer which would contain:

1. Electrical generator
2. Large volume water storage
3. Fuel oil storage
4. Spare parts and supplies

Such a unit should be portable and connectable to the other units.

9. REFERENCES

Averill, D.W., and G. W. Heinke, 1973, Vacuum Sewer Systems, Dept. of Civil Engineering, University of Toronto.

Baribo, L.E., 1957, Field Testing of Ground Type Incinerator Toilets under Arctic Conditions, Tech. Note AAL-TN-57-6, USAF, Arctic Aeromedical Lab.

Fair, G.M., J.C. Geyer, and D.A. Okun, 1966, <u>Water and Wastewater Engineering</u>, Vol. 1, John Wiley and Sons Inc., New York.

Miholits, E.M., 1961, Research and Development of a New Method of Waste Disposal for Isolated Sites in the Arctic, Tech. Rep. 61-9, USAF, Arctic Aeromedical Lab.

THERMAL EXPANSION COMPENSATION

IN ABOVE GROUND WATER PIPING

SYSTEMS FOR LOW TEMPERATURE

ENVIRONMENTS

by

R. R. Gilpin
M. G. Faulkner

Dept. of Mechanical Engineering
The University of Alberta

under contract to:

Technical Branch
Environmental Protection Service
Northwest Region
Environment Canada

March 1974

CONTENTS

LIST OF TABLES

LIST OF FIGURES

1. SUMMARY

Because of the significant number of unexplained expansion joint failures in situations where these joints are subjected to freezing water, an investigation of the behaviour of various types and makes of expansion joints was done in the laboratory. As many of the reported failures have occurred in water lines after they had been drained, the study concerned itself with joints which were frozen with only a small amount of water remaining in them.

Four different steel piping expansion joints were treated under freeze-thaw conditions simulated in low temperature environmental chambers. Neither of the two slip-type joints proved to be satisfactory. The packed-slip joint was not suitable due to excessive maintenance and alignment requirements. The Dresser coupling became too stiff at low temperatures and would probably cause buckling of the pipe under certain conditions. Of the other two joints tested, the internally-supported bellows proved unsatisfactory as ice tended to be trapped and hindered the normal operation. The free-flexing bellows was the best of the types tested. With ice frozen inside it, the joint performed adequately provided the amount of contraction was limited to 50% of its rated amount.

While the joints tested in this study were for 2 and 3 inch diameter lines, it is believed that the results would be applicable to other, larger sizes of water piping joints.

2. INTRODUCTION

If development of a proposed Mackenzie Valley gas pipline is undertaken, a large number of construction camps will be necessary. Life-support systems, including sewage and water distribution, will be a requirement for any camps located along the proposed route. The failure of expansion joints in water and sewage lines, due to the severe freeze-thaw conditions experienced in Canada's north, have been previously encountered. It was therefore proposed to study the behaviour of a number of types of expansion joints used in steel piping systems under low temperature (sub-freezing) conditions. In particular their ability to expand and contract both with and without water frozen inside them was to be investigated in the laboratory. The primary objective was to find expansion joints which will perform satisfactorily in northern climates.

3. CURRENT STATE OF KNOWLEDGE

Normally the temperature in the piping of an above ground water distri-
bution system is maintained at a relatively constant value equal to
that of the water circulating in it (approximately 40°F). However
such systems may occasionally have to be shut down and the lines
drained in which case the pipe may be subjected to the full range of
air temperatures. This temperature range may be as large as 160°F.
For steel pipe this range of temperature would produce approximately
1-1/4" of length change per 100' of pipe.

The three common techniques available for absorbing this length change
are:

    (1) a "snaked" or "zig-zag" line
    (2) expansion loops
    (3) an "in-line" expansion joint.

Each has specific advantages and limitations.

The "snaked" or "zig-zag" line has perhaps some advantages as far as
simplicity is concerned. It does, however, require more lateral space
than the "in-line" expansion joint. For example with anchor points at
100' intervals a "snaked" line would have to be offset some 3' from a
straight line. This means that the "snaked line" cannot be used in a
utilidor although it may be acceptable when laying pipe over an open
area. Less lateral offset is required if the anchor points are more
closely spaced. For example with anchor points every 20' the offset
is only half a foot. The radius of curvature of the pipe bends between
anchor points however is too small for the large diameter pipes.

Expansion loops may be built into the line, however these tend to be
expensive to install as well as substantially increasing the pressure
drop in the line. The Federal Department of Public Works has tried
a rather simple expansion loop constructed with ball and socket joints.
These joints however failed under low temperature conditions.

The most feasible type of expansion device for a utilidor would be an
"in-line" type of joint. The normal procedure of designing for expan-
sion and contraction using this type of joint is given by Wilbur (1967).
The types of "in-line" joints tested were:

    (1) Dresser type coupling
    (2) Packed-slip type
    (3) Internally-supported bellows
    (4) Free-flexing bellows

Sketches of these joints are shown in Figures 1 through 4.

The Dresser type coupling is not designed as an expansion joint; how-
ever, it will take about 1/4" of movement under normal conditions.
Thus if they are spaced at 20' intervals they normally will suffice as
expansion compensators.

The packed slip type is a much more sophisticated expansion compensator designed primarily for industrial plant use. A single unit can accomodate the large expansions, up to 12", that occur in high temperature lines. They have the disadvantages that they require routine maintenance and accurate alignment of the pipes to be joined.

The internally-supported bellows and the free-flexing bellows both employ a corrugated metal bellows to compensate for the expansion. They differ in the way the bellows are physically arranged in the joint as shown in Figures 3 and 4.

Operation experience with in-line type expansion joints has shown that failures frequently occur if the pipe must be shut-down and drained during the winter. The Federal Department of Public Works has experienced some failures of an internally-supported bellows joints (a type of which was tested in this study). Environment Canada's Technical Branch, Edmonton, also reports that "Dresser" type couplings, which at normal operating temperatures provide for some expansion and contraction, fail to do so under freezing conditions (Grainge, Pers. Comm.)*. From these observations it was surmised that the expansion joints were failing because either the joints were becoming stiffer at the cold temperatures or ice formed from the water left in the joint was preventing the normal operation of the expansion joint. These conditions were simulated in the laboratory.

* Grainge, J.W., Senior Project Engineer, Technology Program,
            Environmental Protection Service,
            Edmonton, Alberta.

METHODS

Four different types of "in-line" expansion joints were tested. These
are the Dresser coupling, packed-slip type, internally-supported bel-
lows and free-flexing bellows. The particular joints tested and appro-
ximate prices are listed in Table I.

In the first series of tests the joints indicated in 1, 2, 3 and 4(b)
of Table I were subjected to six different tests each. In all these
tests the joints were expanded or contracted in a hydraulic testing
machine with the objective of determining what force would be required
to produce a deformation in the joint of 0.25".

The six tests on each joint consisted of three tension and three com-
pression tests. These tension and compression tests were conducted
at room temperature (70°), at -20°F and at -20°F with water frozen in-
side the joint. In this last test with the joint and connecting pipes
in the horizontal position, water was put into the joint until it be-
gan running out of the ends of the pipe. The water was then frozen
and the entire assembly transferred to the environmental chamber in
the testing machine, cooled to -20°F and tested in tension. After the
tension test the ice was melted and refrozen before the compression
test was started.

A further sequence of tests were conducted to determine the effects of
larger amounts of ice in the joints, as well as greater deformations
of each joint. These tests were concentrated on the packed-slip and
free-flexing type of joint since the first series of tests had shown
them to be superior to the others.

Finally a series of tests were done on free-flexing joints of different
lengths (numbers 4(a) and 4(c) Table I). These tests were designed to
determine the maximum compression that the free-flexing joints with
ice in them could take without suffering permanent deformations.

TABLE I

Type of Joint	Price (f.o.b. Edmonton)
1. Dresser Coupling, 2" nominal pipe.	$ 13.00
2. Packed-slip expansion joint 2" nominal pipe.	224.00
3. Internally supported bellows, 2" nominal pipe.	69.00
4. Free-flexing expansion joint 3" nominal pipe	
(a) one with 4 corrugations	144.00
(b) one with 6 corrugations	159.00
(c) one with 8 corrugations	175.00

5.   RESULTS

The results for the first series of tests were summarized in Table II. Shown are the loads required for a 0.25 inch compression or expansion of the joint. In some instances the load reached a maximum value before a 0.25 inch displacement was obtained and then the load fell off with further displacement. In these cases the maximum load is recorded.

The free-flexing bellows were observed to suffer permanent deformation if they were compressed excessively with ice trapped in the bellows. For example, Figure 7 shows the result of compressing the six corrugation, free-flexing bellows joint one inch. Several sizes of joints were tested to determine the maximum compression that could be tolerated without permanent deformation. These results along with the specified maximum axial traverse are shown in Table III. It will be observed that the maximum safe traverse with ice frozen in the bellows is about 50% of the normally specified traverse.

TABLE II

Forces Required to Displace Various Expansion
Joints 0.25" under Normal and Freezing Conditions

	Tension (lb)			Compression		
	Room Temp.	-20°F	-20°F with Ice	Temp.	-20°F	-20°F with Ice
1. Dresser Coupling 2" nominal pipe	2100*	5000*	6350*	3700	6100	9700
2. Packed-slip type 2" nominal pipe	400*	900*	600*	500*	380*	2700*
3. Free-flexing bellows 3" nominal pipe	125	125	125	125	125	150
4. Internally-supported bellows 2" nominal pipe	100	100	2400	70	120	3600*

* maximum force occurred before a displacement of 0.25" was reached

TABLE III

Maximum Joints Traverse of Free-Flexing Bellows

No. of Corrugations on Joint	Specified Maximum Axial Traverse	Maximum Safe Traverse with Ice Frozen in Bellows	% of Specified Traverse
4	1"	1/2"	50
6	1-1/2"	3/4"	50
8	2"	1"	50

TABLE IV

Free-Flexing Expansion Joint Costs

	No. of Corrugations	Quoted Price f.o.b. (Edmonton)	Allowable Traverse (inch)	Required Joint Spacing (ft.)	Cost per foot f.o.b. (Edmonton)
3" nominal pipe	4	$144	0.5	40	$3.60/ft
	6	159	0.75	60	2.65/ft
	8	175	1.0	80	2.19/ft
	10	190	1.25	100	1.90/ft
6" nominal pipe	6	248	1.12	90	2.75/ft
	8	271	1.5	120	2.25/ft
	10	294	1.88	150	1.96/ft

6. DISCUSSION AND CONCLUSIONS

Of particular interest in the results is the change in the force required to operate the joints that occurs when they are cold and when they have ice in them. Also of interest is the maximum force required for compression of the joint. For the two-and three-inch diameter joints tested it is estimated that the pipe between supports spaced 20 feet apart would buckle if the force in the pipe exceeds three or four thousand pounds. This will happen instead of the joint compressing.

The force required to operate the "Dresser" coupling, which was high at room temperatures, increased to 5000 or 6000 pounds when the joint was cooled to -20°F without any ice in it. The force increased even further when ice was frozen in it. It is therefore probable that such a joint would provide no expansion compensation under freezing conditions.

The internally-supported bellows, which required forces of about 100 pounds at room temperature and at -20°F, required forces of the order of 3000 pounds when ice was frozen in them. These high forces were due to the design of the bellows structure (Figure 3) which traps the ice formed. This is primarily why internally-supported bellows joints have failed during a shut-down cycle.

The forces required to operate the two remaining joints, the packed-slip type and the free-flexing bellows, were acceptable, the free-flexing bellows showing the least adverse effect from having ice frozen in it.

If the amount of ice frozen in the joint was increased the force required increased considerably. For example for the packed-slip type half full of ice the force required was 5000 pounds whereas with a very small amount of ice in it the force was 2700 pounds. One could conclude that any piping system must be designed so that the expansion joints will drain to the greatest extent possible.

In tests where the amount of compression was increased from 0.25 inches to one inch it was found that the maximum force required for the packed-slip type was 3400 pounds while that for the free-flexing bellows was 1000 pounds. (The specified maximum expansion for these joints are 4" and 1-1/2" respectively.) The higher force required for the packed-slip joints, along with the fact that they require maintenance and accurate alignment, would tend to rule them out for expansion compensation under freezing conditions. This leaves the free-flexing bellows as the most acceptable expansion joint from a technical point of view.

7. RECOMMENDATIONS

7.1 Type of installation recommended.

It is recommended, that in future installations of above-ground water piping systems, the free-flexing bellows joint be tried. A record of its performance as well as that of other types of joints should be kept in order to relate the field experience to the findings of this study.

7.2 Method of installation and cost.

Installation and Cost of the Bellows Expansion Joints

For installation of bellows joints, it is essential that the manufacturer's specifications be followed. For proper behaviour of the joints it is of particular importance that the proper pipe anchors, pipe guides, and expansion joint pre-compression are used in the piping installation. We would recommend that for the case where ice may become frozen in the bellows the maximum axial traverse should be only 50% of the specified maximum for a given type of joint.

The costs of a number of sizes of free-flexing expansion joint as quoted in December 1973 are listed in Table IV. Also shown in Table IV are the allowable expansion for each joint (one half of the specified value), the required expansion joint spacing and the cost per foot this would add to the pipe. Note that this last column does not include the cost of pipe anchors, pipe guides, and associated installation costs.

In each case the most economical joints are the ones that take the most displacement per joint; that is, the one with the largest number of corrugations. The minimum cost for both the 3" and 6" pipe sizes, using ten corrugation joints, is around $2 per foot of pipe.

It should be remembered that the free-flexing bellows with 10 corrugations will not have very much lateral stiffness and the proper installation of alignment guides is particularly critical.

8. NEEDS FOR FURTHER STUDY.

No further requirements for the study of expansion joints are anticipated at this time.

FIGURE 2 PACKED-SLIP TYPE

PACKING SEALS

LUBRICANT

SLIDING SURFACE

DRAIN PLUG

FIGURE 4 FREE-FLEXING BELLOWS

FLANGE

BELLOWS

FIGURE 1 DRESSER COUPLING

RUBBER SEALS

PIPE

FIGURE 3 INTERNALLY-SUPPORTED BELLOWS

BELLOWS

PIPE

Figure 5   Permanent Deformation due to Over Compression
of a Free-Flexing Bellows Joint

9.   REFERENCE

Wilbur, E.R. 1967. Handling Expansion and Contraction in Piping Systems.
    Dom. Eng. Vol. 210, No. 5.   pp. 50-53 and 70-74.

EFFLUENT CRITERIA

THE FATE OF ALGAE IN ALGAE-RICH EFFLUENTS

by

R. EDWARDS

Technology Programs

Technical Branch
Environmental Protection Service
Northwest Region
Environment Canada

March 1974

TABLE OF CONTENTS

* Available on application to Manager, A.L.U.R. Program,
Northern Natural Resources and Environment Branch,
Department of Indian and Northern Affairs,
Ottawa, Ontario. K1A 0H4

LIST OF FIGURES

LIST OF TABLES

1.   SUMMARY

Sewage oxidation ponds will probably be used by construction
camps in northern areas to treat their wastewater. The
treated effluent from these oxidation ponds could be
discharged to small streams and water bodies.

During the summer months, algae (phytoplankton) in the
oxidation ponds multiply rapidly and reach high concentra-
tions. These algae are carried in the effluent and are
continually discharged from the oxidation pond into the
receiving water during the summer. Since the physical and
chemical quality of the receiving water is vastly different
from that of the effluent, the algae are suddenly placed
in a different environment which will affect their
physiological activity. It was thought that the change of
environment might be sufficiently severe to cause a down-
stream die-off of the effluent-borne algae.

Studies of two oxidation ponds and their respective receiving
waters in Alberta have indicated that although high levels
of algae, principally *Scenedesmus quadricauda, S. falcata*
and *Actinastrum* spp. are discharged to receiving waters,
they remain alive and in apparent good condition for
considerable distances downstream of their release point.
Since they remained alive, they did not impose an oxygen
demand on the receiving water and did not reduce dissolved
oxygen levels. It therefore appears that, in respect of
oxygen demand, effluent-borne algae do not have a deleterious
effect on a receiving water during the summer.

2.   INTRODUCTION

The Mackenzie Valley Corridor has been suggested as a
possible route through which the significant finds of
natural gas in the western arctic may be brought to
southern markets. The construction of a pipeline to
transport this gas could take several years to accomplish
and will require the development of a large number of
construction camps.

Construction camps will generage large quantities of waste-
water which must be treated to an acceptable level before
it is discharged to the environment. The use of sewage
oxidation ponds has been suggested (Grainge et al, 1973)
as a suitable method of wastewater treatment for these
construction camps.

In an oxidation pond, degradation of organic material takes
place through bacterial oxidation which releases carbon
dioxide to the wastewater. During the summer, algae in the
oxidation pond reuse the carbon dioxide to form algal
biomass. By this means a large concentration of algae can
develop in an oxidation pond by the end of the summer. The
effluent which is discharged from an oxidation pond will
therefore contain large numbers of algae. Under certain
circumstances, the effluent-borne algae, which have
developed in the warm and nutrient-rich waters of an
oxidation pond, may be discharged to a cold and oligotrophic
receiving water. Discharged algae can be expected to affect
the downstream receiving waters in various ways.

If the algae are unable to survive in their new environment
a sudden die-off would impose a heavy oxygen demand on the
receiving water, resulting in decreased levels of dissolved
oxygen. Alternatively, the algae may remain alive, but
their growth rate would fall to a low level. In this case,
they would not exert an oxygen demand on the receiving
water.

The project was divided into two phases, the first being
to determine the fate of algae released from oxidation
ponds and the second to develop alternative tests for
algae-rich effluents which will accurately assess the
efficiency of oxidation pond treatment of effluents. The
first phase of this study is reported here.

3.   CURRENT STATE OF KNOWLEDGE

Sewage oxidation ponds serving settlements in arctic and
sub-arctic areas have been in existence for some time.
The oxidation pond at Inuvik, for example, which was built
in 1959, has been extensively studied by Dawson et al, (1973),
who reported that the oxidation pond produced an 85%
reduction in BOD_5 from the raw sewage to effluent in summer
and 41% reduction in winter.

The effects of sewage effluent on receiving water quality
in Banff National Park have been studied by Robinson (1972)
and by Krishnaswami and Slupsky (1970). They concentrated
on water chemistry, invertebrate communities and phytoplankton,
but did not consider in depth, the algal fraction of the
oxidation pond effluent and its fate in the receiving water.

Oxidation ponds produce high concentration of algae during
the summer and the fact that there is little information
on the fate of algae discharged into receiving waters has
been pointed out by Caldwell and Parker (1973). These workers
suggest that under certain conditions, discharged algae
can constitute a BOD_5 load on the receiving water and
decrease the dissolved oxygen level. This is only likely
to occur if the algae are discharged to an environment
unfavourable for their maintenance or growth and they decay.

The standard tests which are applied to determine the
efficiency of an oxidation pond or wastewater treatment
plant include the determination of biochemical oxygen
demand (BOD_5) and suspended solids (SS). In the BOD_5 test,
a sample of water or effluent of known oxygen level is
incubated for 5 days in the dark at $20^{\circ}C$ after which the
oxygen level is again determined. The difference between
the initial and final oxygen concentration is calculated in
terms of oxygen utilized per litre of wastewater over the
test period. If the test water contains significant
quantities of algae, then, under 5 days of continuous dark
conditions, these algae will respire and use their stored
food products, and in so doing they will utilize dissolved
oxygen from the water. Conversely, if the test were run
under well-lighted conditions, the algae would be producing
oxygen through the process of photosynthesis and consequently
the oxygen level in the water would rise. In fact, tests
have demonstrated that when BOD_5 bottles containing an algae-
rich effluent are submerged in a receiving stream under
natural conditions, the level of dissolved oxygen in the
bottles increases, indicating a negative BOD_5 whereas
running the test in the dark indicates a high BOD_5.

The BOD_5 test is intended to indicate the amount of oxygen
required to oxidize organic material in the water sample
through bacterial action. Living algae cells will not be

decomposed by bacteria under natural conditions. It is
only when the algae cells have died that they can be
decomposed by bacteria and an oxygen demand on the water
is exerted. The BOD_5 test, therefore, is unsuitable for
algae-rich effluents.

The suspended solids consist of organic and inorganic
material which is held in suspension in the water. The
algae fraction constitutes suspended solids and is included
in the test result. A high concentration of algae in the
effluent will result in a high SS reading.

There is a fundamental difference between the processes
involved in the operation of an oxidation pond and those
involved in the operation of an activated sludge plant for
example.

In an oxidation pond, non-living organic material which
enters the pond in the influent is broken down and oxidized
by bacterial action. This oxidation process releases
energy, which the bacteria utilize for growth and metabolism,
and carbon dioxide, which is released into the surrounding
water, and may escape into the atmosphere. The bacteria,
therefore, require oxygen to degrade the organic material
and this oxygen is supplied to some extent by gas exchange
at the air-water interface, but mostly by algal photo-
synthesis. In the process of photosynthesis, algal cells
remove carbon dioxide from the water and build it into
algal biomass, using the energy from sunlight to do so. To
summarize, most of the organic material in the influent is
oxidized to carbon dioxide by bacterial action, but much of
the carbon dioxide is reconverted into organic material as
algal biomass. The net result therefore, in general terms,
is that the non-living organic matter entering the pond is
converted into living organic matter and comparatively
little carbon is lost from the system.

In an activated sludge treatment plant, bacteria break down
the incoming organic material, but the oxygen they use in
this process is provided by forced aeration of the waste-
water. The carbon dioxide generated through bacterial
action is partly lost to the atmosphere and is partly lost
by being carried out of the plant in the effluent. By this
process, much of the organic material entering the plant is
converted into carbon dioxide. The bacterial biomass which
is synthesized within the plant is settled out and returned
to the influent line, thus producing an effluent of good
quality.

Since the biological processes which take place in enclosed
mechanical treatment plants and oxidation ponds are very
different, it is unreasonable to apply the same measuring

stick to both types to determine their efficiency.
Obviously, an algal-laden effluent will always show a high
BOD_5 when tested under dark conditions. If it were tested
under well-lighted conditions, a negative BOD_5 could well
be indicated. Generally speaking, algal productivity is
directly proportional to light intensity. Under high light
conditions, productivity will be high because the production
of biomass by photosynthesis is greater than the breakdown
of biomass due to respiration. As light intensity falls,
the photosynthetic production of biomass decreases until at
a certain light intensity, the photosynthetic production of
biomass is approximately equivalent to the breakdown of
biomass through respiration. At this light intensity, there
will be neither a net gain nor a net loss of algal biomass.
If a BOD_5 test were run under light conditions such that
there were no change in algal biomass, then, within limits,
a reduction of oxygen level in the BOD bottles would be
caused by bacterial respiration and oxidation of non-living
organic materials.

It has been suggested that the algal fraction of a waste-
water sample may be removed by filtration and a BOD_5 test
on the filtrate will give a better indication of the
quality of the effluent. However, it should be noted that
some of the non-living organic material in the effluent is
in suspension and will therefore be removed by filtration,
along with the algae and some of the bacteria. A BOD_5
test on this filtrate will give an indication of the amount
of dissolved organic material in solution. A filtered
test is therefore of limited value and is therefore not
recognized as a Standard Method.

4. STUDY AREA

4.1 Location of Study

To fulfil the objectives of the study, it was necessary to select a stream which would allow the recovery of algae discharged from an oxidation pond. The receiving water should therefore be a relatively small, flowing stream readily accessible for some distance downstream from the effluent discharge point. There are a number of sewage oxidation ponds in the Mackenzie Valley Corridor, but these were considered unsuitable for field investigation since they discharge into the vast Mackenzie River where any discharged material would quickly become diluted to the point that it was unrecoverable. An ideal receiving water is one where rapid mixing of the effluent with receiving water takes place so that errors in downstream sampling will not arise through poor mixing of the effluent and the receiving water.

These constraints coupled with the necessity for such logistic support as laboratory facilities resulted in the selection of two sites in Alberta.

The two selected sites were Louise Creek, Banff National Park, which receives effluent from a sewage oxidation pond serving Upper Lake Louise, and Battle River, Ponoka which receives effluent from an oxidation pond complex which serves the town of Ponoka. Emphasis was placed on the Louise Creek study.

The oxidation pond serving Upper Lake Louise is a single cell measuring 145 m by 80 m. At a working depth of 1.5 m, it has an estimated surface area of 10,200 m^2 and an estimated volume of 14,200 m^3. At an average flowrate of 0.01 $m^3 s^{-1}$, this oxidation pond will have an estimated retention time of 15 days, which is reduced to 5.8 days at the peak flow of 0.03 $m^3 s^{-1}$.

The lagoon complex at Ponoka consists of 4 anaerobic cells, each of 2100 m^3 capacity at 3 m depth, one intermediate lagoon of 3,000 m^3 capacity at 2.4 m depth, and an aerobic lagoon of 50,000 m^2 extent with a capacity of 93,000 m^3 at 1.8 m depth. The lagoon complex is believed to have been built in 1960 and total containment is practised during the winter months.

The streams chosen for study are very different in character. Louise Creek is a small turbulent to torrential mountain stream (Fig. 1) which drains a glacial melt lake. The creek runs for approximately 3000 m before joining the Bow River. The effluent from the oxidation pond enters the creek approximately 1,100 m downstream from the creek origin.

Figure 1. Louise Creek, midway between sample points B and C.

Figure 2. The effluent outfall which flows into Louise Creek, sample point B.

The water of Louise Creek is consequently cold and oligo-
trophic. Conversely, the Battle River at Ponoka is a slow-
flowing, meandering stream which is passing through an
agricultural area. It originates from a small lake approxi-
mately 50 km upstream from Ponoka and it eventually joins
the North Saskatchewan River in Saskatchewan. It is
relatively high in nutrients which are derived from run-off
from agricultural land and from seepage from feed lots and
farm yards along its course.

4.2 Sample Collection Points

Four sample collection points, designated A,B,C & D were
selected along Louise Creek. The location of these points
is given below.

Sample Point	Location on Louise Creek
A	Approximately 12 m upstream from the effluent outfall.
B	Outfall of the effluent from the lagoon pipe (Fig. 2).
C	Approximately 1,100 m downstream from the effluent outfall, at the lower road crossing of the creek.
D	Just upstream of the confluence with the Bow River, approximately 1,800 m downstream from the effluent outfall.

On the Battle River, six points were initially selected
for sampling, with two additional points selected at a
later stage. The location of these points is given below.

Sample Point	Location on Battle River at Ponoka
A	90 m upstream from the effluent outfall.
B	The effluent outfall.
C	60 m downstream from the effluent outfall.
D	230 m downstream from the effluent outfall.
E	800 m downstream from the effluent outfall.
F	1,600 m downstream from the effluent outfall.
G	3,200 m downstream from the effluent outfall.
H	6,400 m downstream from the effluent outfall.

Field investigations were carried out at 2-3 week intervals
from 25th June 1973 until 21st September 1973 in both study
areas.

5. METHODS AND SOURCES OF DATA

5.1 Flow Measurements

Water flow in Louise Creek was measured where the creek flows through a culvert at the lower exit from the Upper Lake Louise parking lot. The culvert is elliptical and measures 2.4 m wide by 1.8 m high. The depth of water in the culvert was taken and the velocity of the flow through was measured with a Gurley flow meter. The flow could then be calculated. The outflow from the Louise Creek oxidation pond was measured by constructing a small channel along which the effluent flowed. The depth of effluent in the channel and the channel width were noted and the effluent velocity was measured.

The Gurley flow meter was also used to determine the velocity of the effluent leaving the Ponoka lagoon by placing it inside the 25 cm diameter outflow pipe. The depth of effluent in the pipe was noted at the time the flow measurements were taken.

The depth of water in the Battle River prevented measurements of flow rate from being made in early summer. As the flow dropped in late summer, measurements were made at a point where the river flows over a concrete ford. Here, the flow was measured and the cross-sectional area of the stream was estimated.

5.2 Phytoplankton Collection, Preservation and Analysis

Samples of phytoplankton were collected from each of the sampling points. The samples were kept cool during transportation. The samples from Louise Creek were taken to the Canadian Wildlife Service Field Laboratory, Banff, where they were concentrated according to Welch's (1948) method. Formalin was added as a preservative at 5% final concentration.

Due to the abundance of phytoplankton in the effluent samples, these were not concentrated. Formalin was added at the same concentration.

Samples from the Battle River were taken to the Environmental Protection Service Chemical Laboratory, Edmonton, where they were concentrated and preserved in the same manner as those from Louise Creek.

Samples collected during the early summer were counted using a Sedgwick-Rafter counting cell on a compound microscope fitted with a Whipple ocular micrometer, (Welch, 1948). Later samples were counted by sedimenting 1 ml or 2 ml aliquots and using an inverted compound microscope.

Test samples counted by both methods gave comparable
results. The drop method outlined by Edmondson (1969) was
also tried and found to give comparable results, but it
was not used significantly in this study.

Identification of phytoplankton was done with the aid of
taxonomic keys (Smith,1950; Prescott,1970; and Ward and
Whipple,1959). Only abundant species were identified and
counted, since those species which occurred in low numbers
could be expected to have little effect on the receiving
waters. Counts were of organisms/ml, each coenobium was
counted as unity.

5.3   Bacteriological Sample Collection

Standard bacteriological bottles containing a small amount
of sodium thiosulphate were provided by the Provincial
Public Health Laboratory, Edmonton. These were used to
collect water samples for bacteriological analysis and
were delivered to the Provincial Public Health Laboratory
for analysis on the day of collection.

5.4   Water Quality, Chemical and Physical Parameters

At the time of collection of the phytoplankton samples,
measurements of dissolved oxygen and temperature were made
with a YSI portable oxygen meter. 4.5 l samples of water
and effluent were collected from selected sampling locations
and delivered to the Environmental Protection Service
Chemical Laboratory, Edmonton, for analysis by the
"Standard Methods". Measurements of the total chlorine
in the effluent from the Louise Creek oxidation pond were
made using the orthotolidine method provided by a Hach DR/2
Field Test Kit.

6. RESULTS

6.1 Flow Measurements

The estimates of flow for Louise Creek and for the two
oxidation pond effluents are given in Table 1.

Table 1. Flow Data

DATE	LOUISE CREEK AREA			PONOKA AREA	
1973	Louise Creek A	Oxidation Pond B	Dilution Ratio $\frac{A}{B}$	Battle River	Oxidation Pond
25-26 June	$3.7 \ m^3s^{-1}$	$0.012 \ m^3s^{-1}$	314	-	-
9-10 July	1.61	0.028	57	-	$0.024 \ m^3s^{-1}$
23-24 July	2.46	0.013	189	-	-
13-14 Aug.	2.77	0.007	396	-	0.010
28-30 Aug.	1.33	0.005	266	$2.83 \ m^3s^{-1}$	0.014
10-12 Sept.	1.70	0.006	283	0.35	0.014
21 Sept.	0.51	0.005	102	-	-

TOTAL PHYTOPLANKTON POPULATION — Louise Creek Area

SAMPLE DATE — (1973)

FIG. 3

SCENEDESMUS POPULATION — LOUISE CREEK AREA

SAMPLE DATE — (1973)

FIG. 4

ACTINASTRUM POPULATION   Louise Creek Area

FIG. 5

CHLAMYDOMONAS POPULATION   Louise Creek Area

FIG. 6

CHLORELLA POPULATION — Louise Creek Area

FIG. 7

DIATOM POPULATION — LOUISE CREEK AREA

FIG. 8

TOTAL PHYTOPLANKTON POPULATION — Battle River Area

FIG. 9

SCENEDESMUS POPULATION — Battle River Area

FIG. 10

CHLORELLA POPULATION   Battle River Area

FIG. 11

DIATOM POPULATION   Battle River Area

FIG. 12

The flow of Louise Creek declined throughout the study period from a high of 3.77 m^3s^{-1} to a low of 0.51 m^3s^{-1}. The flow of the Louise Creek oxidation pond was greatest on 9th July, and thereafter declined to a low of 0.005 m^3s^{-1}. The dilution of the Louise Creek effluent is also included in Table 1. The least dilutution occurred when the effluent flow was greatest, on 9 July, when the dilution ratio was 57:1. Greatest dilution occurred on 13 August when the dilution ratio was 396:1. The greatest flow from the Ponoka oxidation pond also occurred on 9 July, but over much of the study period, it was relatively consistent at 0.014 m^3s^{-1}. The Battle River at Ponoka dropped steadily throughout the study period to a low of 0.35 m^3s^{-1} on 12 Sept. At that time the dilution ratio of the effluent was 25:1.

6.2   Phytoplankton Populations

The results of the phytoplankton counts are shown in Figures 3-12. The curve designations correspond with the sampling point locations previously given. Complete data are given in Appendix I and II.* The total phytoplankton population for the Louise Creek effluent (Fig. 3) increased steadily throughout the study period, reaching a high of 848,000 organisms/ml. The phytoplankton population in Louise Creek above the effluent outfall averaged approximately 100 organisms/ml with lesser numbers during the mid part of the study period. Below the effluent outfall, there was an average of approximately 1,000 organisms/ml throughout most of the study period.

The most common organism in the effluent from the Louise Creek oxidation pond was *Scenedesmus quadricauda*. *S. falcata* was also present and was included in the counts given in Fig.4. *Scenedesmus* reached a peak of 144,000 organisms/ml in late July and thereafter declined to 14,000 organisms/ml by late September. *Scenedesmus* was not observed in the water of Louise Creek above the effluent outfall. In the creek below the outfall an average of 775 organisms/ml was counted.

Organisms of the genus *Actinastrum* were not found in Louise Creek above the outfall, but were present in the oxidation pond effluent (Fig. 5). They steadily increased in the effluent during the study period, to a high of 798,000 organisms/ml. In the creek below the outfall, *Actinastrum* steadily increased throughout the study period to approximately 3,000 organisms/ml.

---

* Appendices available on application to Manager, ALUR Program, Northern Natural Resources and Environment Branch, Dept. Indian Affairs and Northern Development, OTTAWA, K1A OH4

Populations of *Chlamydomonas* were present in the Louise Creek effluent at the beginning and end of the study period, but disappeared during the month of August.

Populations of a species of *Chlorella* were not present in Louise Creek above the effluent outfall, but averaged approximately 10,000 organisms/ml in the effluent (Fig. 7). Lower down in the creek these organisms ranged from 100-1000 organisms/ml over much of the study period.

Diatoms were present throughout Louise Creek where they averaged about 100 organisms/ml throughout the study period (Fig. 8). They were also initially observed in the Louise Creek effluent, but were not observed at this sampling point later than June.

In the Battle River, the total phytoplankton population increased during the study period, both above and below the oxidation pond outfall (Fig. 9). It reached a peak of over 9,000 organisms/ml upstream of the outfall during September. The effluent increased slightly in total population of phytoplankton during the study period to a high of over 70,000 organisms/ml.

The most common phytoplankton organism found in the Battle River study was *Scenedesmus quadricauda*. *S. falcata* is also present and is included in the data in Figure 10. *Scenedesmus* organisms were present upstream of the effluent outfall where they averaged about 20 organisms/ml over most of the study period. In the effluent, *Scenedesmus* averaged about 44,000 organisms/ml. Downstream from the outfall, *Scenedesmus* increased from 100 to 1300 organisms/ml during the study period.

Chlorella appeared in early July and tended to increase during the summer, both above and below the Battle River outfall and in the effluent itself (Fig. 11). Diatoms were present in the Battle River, above and below the outfall, where they ranged from about 100-1000 organisms/ml (Fig. 12).

6.3   Bacteriological Data

The bacteriological data for the Louise Creek area and for the Battle River area are given in Table 2 and 3 respectively. Although not a direct part of this study they are included to give an indication of the possible downstream levels of bacteria. Fecal coliform organisms were recorded upstream of the Louise Creek effluent outfall on one occasion. Chlorination of the Louise Creek effluent resulted in the absence of fecal coliform organisms from the effluent during the latter part of the study period.

Table 2

BACTERIOLOGICAL DATA   LOUISE CREEK AREA

SAMPLE DATE	TOTAL COLIFORM				TOTAL COLIFORM				STANDARD PLATE COUNT X 1000			
	A	B	C	D	A	B	C	D	A	B	C	D
10/7/73	0	38	8.2	3.6	0	2.0	1.8	0	100	320	140	900
24/7/73	170	1800	1600	29	6.8	4.5	4.0	3.7	1.5	64	2.5	1.2
14/8/73	0	1800	39	93	0	0	0	0	3.0	1,750	3.0	3.0
29/8/73	0	0	15.0	0	0	0	0	0	3.0	2,440	3.0	3.0
12/9/73	3.6	460	3.0	-	0	0	0	-	0.04	3.0	0.4	-
23/9/73	0	2.0	4.5	-	0	0	0	-	0.12	3.3	0.6	-

Table 3

BACTEROLOGICAL DATA   BATTLE RIVER AREA

SAMPLE DATE	TOTAL COLIFORM						FECAL COLIFORM						STANDARD PLATE COUNT X 1000					
	A	B	C	D	E	F	A	B	C	D	E	F	A	B	C	D	E	F
10/7/73	540	1800	540	540	350	540	17.0	350	14.0	12.0	14.0	21.0	1.3	36	0.6	1.0	1.5	800
24/7/73	540	1800	240	350	350	350	20.0	52	33	40	40	4.0	1.2	30	1.3	2.5	0.5	1.5
14/8/73	49	-	240	110	95	130	4.5	-	4.5	4.0	3.6	4.0	3	-	15	14.5	3	11.5
30/8/73	27	280	40	920	350	110	0	0	0	6.8	2.0	0	1.3	12.9	2.3	3.1	1.3	1.8
12/9/73	220	32	110	-	-	-	4.5	0	2.0	-	-	-	0.4	77	3	-	-	-

Table 4

LOUISE CREEK WATER QUALITY DATA

Sample Date	June 25, 1973				July 9, 1973				July 23, 1973			
Sample Point	A	B	C	D	A	B	C	D	A	B	C	D
Dissolved Oxygen (mg/1)	10.0	8.0	9.5	9.5	9.3	9.0	9.3	9.2	9.0	10.0	9.0	9.0
Temperature °C	6.1	16.7	6.1	6.1	12.1	19.0	12.5	12.5	12.2	18.9	12.2	12.2
B.O.D.$_5$ (mg/1)	1	4	1	-	2	32	2	-	1	21	1	-
C.O.D. (mg/1)	4	69	1	-	1	107	1	-	1	120	1	-
Suspended Solids (mg/1)	17	19	14	-	8	35	5.5	-	2	40	8	-
Volatile Susp. Solids (mg/1)	1	13	1	-	1	31	1	-	1	35	1	-
Total Residue (mg/1)	95	180	90	-	96	240	90	-	92	198	-	-
Fixed Residue (mg/1)	60	95	85	-	60	106	84	-	78	88	-	-
pH	8.0	7.7	8.0	-	8.2	7.3	8.2	-	8.2	7.3	8.2	-
Alkalinity as CaCo$_3$ (mg/1)	70	115	70	-	71	113	71	-	72	110	71	-
Ammonia Nitrogen (mg/1)	0.1	4.0	0.1	-	0.1	7	0.1	-	0.1	5.2	0.1	-
Nitrate Nitrogen (mg/1)	0.1	0.19	0.1	-	0.11	0.1	0.16	-	0.1	0.1	0.13	-
Nitrite Nitrogen (mg/1)	0.01	0.019	0.01	-	0.01	0.02	0.01	-	0.01	0.01	0.02	-
Organic Nitrogen (mg/1)	-	-	-	-	-	-	-	-	-	-	-	-
Total Phosphate (mg/1)	0.04	1.3	0.05	-	0.01	2.10	0.03	-	0.03	2.2	0.12	-
Turbidity (j.t.u.)	3.8	7.4	3.7	-	1	11	1	-	6	14	4	-
Total Hardness (mg/1)	75	95	95	-	76	86	78	-	72	88	77	-
Chloride (mg/1)	4	14	2	-	5	14	5	-	4	24	4	-
Total Carbon (mg/1)	21	50	22	-	18	63	24	0	20	69	21	-
Inorganic Carbon (mg/1)	20	31	21	-	18	34	21	-	19	34	20	-
Organic Carbon (mg/1)	1	19	1	-	1	29	3	-	1	38	2	-
Sulphate (mg/1)	-	-	-	-	5	7	6	-	5	5	6	-
Total Chlorine (mg/1)	-	1.8	-	-	-	0.02	-	-	-	1.3	-	-

Table 4 (Cont'd)

LOUISE CREEK WATER QUALITY DATA

Sample Date	Aug. 13, 1973				Aug. 28, 1974				Sept. 10, 1973			
Sample Point	A	B	C	D	A	B	C	D	A	B	C	D
Dissolved Oxygen (mg/l)	9.5	11.5	9.3	9.3	9.6	9.6	9.5	9.6	8.5	11.8	8.7	8.7
Temperature °C	11.1	21.0	11.0	11.0	9.0	18.0	8.0	8.0	12.0	20.0	12.5	12.5
B.O.D.$_5$ (mg/l)	1	21	1	-	2	17	2	-	2	11	2	-
C.O.D. (mg/l)	1	128	-	-	1	135	1	-	1	113	2	-
Suspended Solids (mg/l)	2	40	8	-	3	36	6	-	2	32	2	-
Volatile Susp. Solids (mg/l)	1	35	1	-	1	34	2	-	1	28	1	-
Total Residue (mg/l)	78	232	90	-	92	218	90	-	84	212	86	-
Fixed Residue (mg/l)	72	108	46	-	80	142	72	-	56	88	70	-
pH	7.9	7.4	8.2	-	8.1	7.1	8.1	-	7.4	7.1	7.9	-
Alkalinity as CaCo$_3$ (mg/l)	66	108	71	-	71	110	74	-	74	94	69	-
Ammonia Nitrogen (mg/l)	-	-	-	-	0.1	8.0	0.1	-	0.1	3.5	0.1	-
Nitrate Nitrogen (mg/l)	-	-	-	-	0.1	0.1	0.13	-	0.1	0.1	0.1	-
Nitrite Nitrogen (mg/l)	-	-	-	-	0.01	0.01	0.01	-	0.01	0.01	0.01	-
Organic Nitrogen (mg/l)	-	-	-	-	0.11	0.83	0.16	-	0.4	7.9	0.6	-
Total Phosphate (mg/l)	0.1	1.9	0.1	-	0.1	2.3	0.1	-	0.10	2.0	0.10	-
Turbidity (j.t.u.)	2	12	6	-	5	20	5	-	6	17	5	-
Total Hardness (mg/l)	77	92	77	-	72	93	81	-	76	81	77	-
Chloride (mg/l)	10	20	14	-	4	21	5	-	1	15	9	-
Total Carbon (mg/l)	21	74	22	-	21	76	21	-	20	69	32	-
Inorganic Carbon (mg/l)	19	34	20	-	20	32	20	-	19	27	32	-
Organic Carbon (mg/l)	2	40	2	-	1	44	1	-	1	42	0	-
Sulphate (mg/l)	7	8	7	-	5	7	5	-	6	3	5	-
Total Chlorine (mg/l)	-	2	-	-	-	1.6	-	-	-	2.4	-	-

Table 4 (Cont'd)

LOUISE CREEK WATER QUALITY DATA

Sample Date	Sept. 21, 1973												
Sample Point	A	B	C	D	A	B	C	D	A	B	C	D
Dissolved Oxygen (mg/1)	9.5	9.7	9.3	9.6								
Temperature °C	7.5	11.0	8.0	8.0								
B.O.D.5 (mg/1)	1	15	1	–								
C.O.D. (mg/1)	1	110	1	–								
Suspended Solids (mg/1)	2	32	2	–								
Volatile Susp. Solids (mg/1)	2	31	2	–								
Total Residue (mg/1)	56	204	68	–								
Fixed Residue (mg/1)	36	92	64	–								
pH	8.0	7.2	8.0	–								
Alkalinity as CaCO3 (mg/1)	71	90	71	–								
Ammonia Nitrogen (mg/1)	0.1	0.1	1.5	–								
Nitrate Nitrogen (mg/1)	0.1	0.1	0.13	–								
Nitrite Nitrogen (mg/1)	0.01	0.03	0.01	–								
Organic Nitrogen (mg/1)	0.13	0.20	4.0	–								
Total Phosphate (mg/1)	0.1	1.42	0.1	–								
Turbidity (j.t.u.)	1.5	14	3	–								
Total Hardness (mg/1)	114	112	114	–								
Chloride (mg/1)	12	29	13	–								
Total Carbon (mg/1)	21	65	21	–								
Inorganic Carbon (mg/1)	20	25	20	–								
Organic Carbon (mg/1)	1	40	1	–								
Sulphate (mg/1)	5	5	5	–								
Total Chlorine (mg/1)	–	3.0	–	–								

Table 5

BATTLE RIVER WATER QUALITY DATA

Sample Date	June 26, 1974				July 10, 1974				July 24, 1974			
Sample Point	A	B	C	D	A	B	C	D	A	B	C	D
Dissolved Oxygen (mg/l)	–	–	–	–	6.6	6.5	6.3	6.4	8.0	7.0	9.0	8.5
Temperature °C	17	20	17	17	21	18	21	21	21	19.5	21	21
B.O.D.$_5$ (mg/l)	2	16	–	4	3	20	–	4	5	20	–	8
C.O.D. (mg/l)	56	103	–	61	51	100	–	44	44	159	–	48
Suspended Solids (mg/l)	16	15	–	18	14	44	–	11	15	53	–	11
Volatile Susp. Solids (mg/l)	2	5	–	1	1	35	–	1	3	45	–	3
Total Residue (mg/l)	415	840		405	302	826		342	286	846		514
Fixed Residue (mg/l)	265	710		310	208	676		260	214	694		362
pH	8.0	8.2	–	8.0	8.2	8.0	–	8.1	8.2	8.4	–	8.3
Alkalinity as CaCO$_3$ (mg/l)	245	550	–	245	204	518	–	206	211	501	–	212
Ammonia Nitrogen (mg/l)	0.15	15.6	–	0.20	0.1	13.8	–	0.1	0.1	9.0	–	0.1
Nitrate Nitrogen (mg/l)	0.18	0.1	–	0.16	0.1	0.12	–	0.1	0.1	0.1	–	0.1
Nitrite Nitrogen (mg/l)	0.067	0.01	–	0.01	0.02	0.02	–	0.01	0.01	3.2	–	0.1
Organic Nitrogen (mg/l)	–	–	–	–	–	–	–	–	–	–	–	–
Total Phosphate (mg/l)	0.36	7.5	–	0.36	0.51	7.55	–	0.24	0.4	5.4	–	0.3
Tubidity (j.t.u.)	4.8	11	–	6.3	1	5	–	1	4	16	–	8
Total Hardness (mg/l)	215	185	–	205	190	220	–	185	173	257	–	173
Chloride (mg/l)	18	40	–	13	6	36	–	5	19	40	–	3
Total Carbon (mg/l)	81	160	–	82	70	174	–	89	65	160	–	68
Inorganic Carbon (mg/l)	64	140	–	65	53	134	–	62	49	125	–	50
Organic Carbon (mg/l)	17	20	–	17	17	40	–	17	16	35	–	18
Sulphate (mg/l)	–	–	–	–	25	100	–	73	16	100	–	15

Table 5 (Cont'd)

BATTLE RIVER WATER QUALITY DATA

Sample Date	Aug. 14, 1973				Aug. 30, 1973				Sept. 12, 1973			
Sample Point	A	B	C	D	A	B	C	D	A	B	C	D
Disolved Oxygen (mg/1)	6.6	6.5	6.7	6.7	7.8	7.5	8.0	8.0	8.4	9.7	8.9	8.6
Temperature °C	22	17	22	22	14.5	16	14	14	15	16	15	15
B.O.D.$_5$ (mg/1)	1	24	–	1	2	18	–	2	4	30	–	8
C.O.D. (mg/1)	58	103	–	58	49	71	–	45	40	64	–	44
Suspended Solids (mg/1)	10	41	–	15	7	19	–	7	10	20	–	14
Volatile Susp. Solids (mg/1)	3	35	–	1	2	16	–	2	4	15	–	4
Total Residue (mg/1)	366	830	–	296	318	818	–	320	360	818	–	366
Fixed Residue (mg/1)	274	729	–	266	226	666	–	188	250	676	–	252
pH	7.4	8.4	–	7.1	8.1	7.9	–	8.0	8.0	7.8	–	8.0
Alkalinity as CaCO$_3$ (mg/1)	170	482	–	138	214	498	–	218	251	318	–	253
Ammonia Nitrogen (mg/1)	–	–	–	–	0.1	0.1	–	0.1	5.0	2.5	–	4.0
Nitrate Nitrogen (mg/1)	–	–	–	–	0.2	9.1	–	0.32	0.1	1.3	–	0.1
Nitrite Nitrogen (mg/1)	–	–	–	–	0.01	0.01	–	0.01	0.08	0.86	–	0.18
Organic Nitrogen (mg/1)	–	–	–	–	–	–	–	–	18.5	4.2	–	20.0
Total Phosphate (mg/1)	0.2	4.5	–	0.2	0.15	4.04	–	0.16	0.11	3.91	–	0.18
Turbidity (j.t.u.)	6	8	–	4	5	10	–	5	4	9	–	4
Total Hardness (mg/1)	197	197	–	183	192	244	–	181	208	295	–	210
Chloride (mg/1)	23	50	–	33	5	46	–	7	8	44	–	11
Total Carbon (mg/1)	71	156	–	67	71	148	–	72	80	148	–	81
Inorganic Carbon (mg/1)	48	123	–	43	54	134	–	55	62	122	–	65
Organic Carbon (mg/1)	23	33	–	24	17	14	–	17	18	26	–	16
Sulphate (mg/1)	33	134	–	32	25	180	–	23	26	103	–	27

WATER TEMPERATURE   Louise Creek Area

FIG. 13

WATER TEMPERATURE   Battle River Area

FIG. 14

6.4   Water Quality Data, Chemical and Physical
        Parameters

Water quality data are given in Table 4 and 5 for the
Louise Creek area and the Battle River area respectively.

The level of dissolved oxygen at all sampling points in the
Louise Creek area remained high throughout the study period.
Slightly lower levels were recorded in the Battle River
area.

The water temperature of Louise Creek and its contributory
effluent is expressed graphically in Fig. 13 and that of
the Battle River area in Fig. 14. The temperature of the
Louise Creek effluent was consistently higher than that of
Louise Creek itself. Conversely, the temperature of the
Battle River often exceeded that of its contributing
effluent.

Measurements of BOD_5 and suspended solids in the Louise
Creek effluent ranged from 4-32 mg/l and from 19-40 mg/l
respectively. In the Battle River effluent, BOD_5 and
suspended solids ranged from 16-30 mg/l and from 15-53 mg/l
respectively.

7.   DISCUSSION

7.1   Phytoplankton Population

The results of this study indicate that large numbers of
algae are released from sewage oxidation ponds during the
summer months. The green alga *Scenedesmus quadricauda* was
the most abundant organism in the effluent from the Louise
Creek oxidation pond in early summer. It slowly declined
in numbers throughout the summer. Conversely, a species
of *Actinastrum* was low in numbers in this effluent in early
summer, but increased considerably and continually through-
out the study period. In terms of total numbers, these two
organisms have the greatest effect on the receiving waters,
especially as neither were observed upstream of the Louise
Creek oxidation pond outfall. Below the outfall,
Scenedesmus and *Actinastrum* were observed in maximum
concentrations of 1,300 and 3,300 organisms/ml respectively.
When comparing populations of *Scenedesmus* with other single-
celled organisms such as *Actinastrum*, it should be
remembered that *Scenedesmus quadricauda* usually occurs as a
small colony of four joined cells. A concentration of
1,300 organisms/ml of *Scenedesmus quadricauda* would there-
fore contain approximately 5,200 cells/ml.

Scenedesmus quadricauda was also the most abundant organism
in the Battle River effluent, although in contrast to
Louise Creek, *Scenedesmus* was found upstream of the effluent
outfall, an indication that the Battle River is already
enriched. Downstream of the effluent outfall, *Scenedesmus*
was found in increasing concentrations reaching over 2,000
organisms/ml.

Obviously, the dilution of the effluent with the receiving
water will have an effect on the downstream concentration
of effluent borne organisms. The least dilution of the
Louise Creek effluent occurred in early July, at a time
when the total count of effluent-borne organisms was low.
At this time a peak in the total count downstream of the
effluent was noted (Fig. 3).

A similar occurrence was noted in the Battle River, when its
flow dropped to 0.35 $m^3 s^{-1}$, while the flow of the effluent
remained at 0.014 $m^3 s^{-1}$. At this time, a total count of
over 9,000 organisms/ml were recorded upstream from the
effluent outfall and over 10,000 organisms/ml downstream
of the outfall. Most of the upstream and downstream
organisms were *Chlorella*, which was almost absent from the
effluent. Under these conditions the already-enriched
Battle River was stagnating and developing an algal bloom
which was not related to the effluent.

The levels of phytoplankton recorded in Louise Creek were much higher than those previously reported by Krishnaswami and Slupsky (1970). The survey by these workers was carried out in June and July 1969 when they recorded a maximum concentration of 1163 plankton cells/litre, downstream of the effluent outfall, with only 20 cells/litre of *Scenedesmus quadricauda* being recorded in this same location. They concluded that "the waste water lagoon effluent discharged to Louise Creek affects adversely the population and variety of species of phytoplankton."

In the present study, the organisms in Louise Creek upstream of the effluent outfall were diatoms whose numbers remained relatively unchanged throughout the length of the creek on any particular sampling date. Louise Creek is, as has been noted, a torrential mountain stream which flows less than 3 km from its origin to its confluence with the Bow River. Under normal conditions a phytoplankton organism would take an hour at the most to be carried the whole length of the creek. Since the flow is torrential, mixing of the effluent with the creek water is immediate and oxygen levels are maintained in the water by constant agitation. In addition, the torrential action of the creek dislodges algae which are attached to submerged rocks, such as many species of diatoms, which will tend to increase the count of these organisms at the low end of the creek. There is no indication in this study that the standing phytoplankton population of Louise Creek is affected by the effluent. However, periphyton organisms downstream of the effluent outfall will probably be affected.

The Battle River is slow-flowing and samples collected downstream from the outfall, but on the opposite side of the river, indicated that little mixing was taking place. The effluent tended to remain on the same side of the river as it was discharged.

7.2   Physical and Chemical Parameters

There is a considerable difference in the physical and chemical parameters of the water of Louise Creek and its contributing effluent.

The effluent was consistently warmer than Louise Creek throughout the study period, although this temperature drop would have little effect on the effluent-borne phytoplankton, other than to reduce their metabolic rate. Conversely, the temperature of the Battle River often exceeded that of its contributing effluent. The maximum temperature recorded in Louise Creek was $12.5^\circ C$ which is about $5^\circ C$ less than that reported by Robinson (1972).

Ammonia nitrogen and organic nitrogen were considerably
higher in the Louise Creek effluent than in the creek
itself, although nitrate and nitrite nitrogen appeared
comparable in the effluent and creek. The same was true
of the Battle River and its effluent early in the summer,
but later ammonia nitrogen and organic nitrogen in the
river upstream of the outfall exceeded that of the effluent.

Organic carbon was considerably higher in the Louise Creek
effluent than in Louise Creek, but there was less difference
between the organic carbon in the Battle River and its
effluent.

Total phosphate was much higher in the Battle River effluent
than in the Louise Creek effluent, both being considerably
higher than their respective receiving waters.

BOD_5 levels in the Louise Creek effluent ranged up to
35 mg/l, while that of the Battle River effluent ranged to
30 mg/l. The BOD_5 of Louise Creek was less than 2 mg/l
and that of the Battle River was less than 5 mg/l. The
maximum BOD_5 of the Battle River coincided with the maximum
total count of the phytoplankton population in the river.
Similarly the maximum BOD_5 of the Battle River effluent
coincided with the peak effluent population of phytoplank-
ton, while the maximum BOD_5 of the effluent occurred during
July when the population of *Scenedesmus* was at its highest.
In this effluent, BOD_5 levels feel throughout the remaining
study period, as did the *Scenedesmus* population, but at the
same time, the population of *Actinastrum* increased.

The evidence of this study suggests that *Scenedesmus* may
have a greater effect on the BOD_5 test than *Actinastrum*,
since there is an indication of a correlation between the
level of BOD_5 and the population of *Scenedesmus* in the
receiving water.

The BOD_5 downstream of the effluent outfall appears to be
little affected by the effluent, remaining at the upstream
level in most cases.

The algae released from the Louise Creek oxidation pond
appeared at the lower end of the creek in a viable and healthy
condition. There appeared to be no mortality occurring
down the course of Louise Creek. Samples taken from up
to 25.7 km downstream of the Louise Creek and Bow River
confluence were examined and healthy specimens of
Scenedesmus and *Actinastrum* were observed. Similarly in
the Battle River, samples from 6.4 km below the outfall
indicated a slight downstream increase in the population of
Scenedesmus. There is an indication therefore, that effluent-
borne algae do not have a detrimental effect on the receiving

water.   However, it should not be construed that the
effluent itself does not have a detrimental effect on the
receiving waters, since the nutrients in the effluent will
cause an increase in the productivity of periphyton
organisms downstream from the outfall.   Periphyton
organisms were not considered in this study.

8.   CONCLUSIONS

The identification and enumeration of phytoplankton
populations above and at several points below the outfall
from two sewage oxidation ponds has been completed.

The effluents from the oxidation ponds contained high levels
of phytoplankton which ranged, in the Louise Creek effluent
for example, up to more than 800,000 organisms/ml of
effluent. Upstream from the oxidation pond outfall, the
concentration of phytoplankton did not exceed 300
organisms/ml. The maximum downstream concentration of
phytoplankton at this location was 3880 organisms/ml which
occurred when there was little dilution of the effluent.

At points further downstream, the level of phytoplankton
remained fairly constant on any given sampling date. The
quality of the effluent ranged to a maximum BOD_5 of 32 mg/l,
and a maximum SS of 53 mg/l, but through dilution in the
receiving water this was reduced to a maximum BOD_5 of
4 mg/l in Louise Creek and a maximum BOD_5 of 8 mg/l in the
Battle River. Suspended solids were similarly reduced.
Dissolved oxygen levels downstream of the effluent discharge
appeared to be little affected by the effluent.

The results of this study indicate that populations of
phytoplankton which are released from the selected
oxidation ponds remain fairly constant in the immediate
downstream section of the receiving water. The phytoplank-
ton population does not suddenly decline through die-off
of the individual organisms, thereby exerting an oxygen
demand which would be detrimental to the water quality.
Observations indicate that, under low nutrient conditions,
initial populations of phytoplankton remain constant,
although it is probable that the population level slowly
decreases with time, since the reproduction rate of the
phytoplankton is likely to be insufficient to balance the
numbers falling prey to secondary producers.

Where nutrient levels are higher, observations indicate
that populations of phytoplankton may slowly increase
downstream, although it is to be expected that there will
be a change in species composition of the phytoplankton
population, due to the varying abilities of different
species to tolerate the new conditions.

There is also an indication that *Scenedesmus* may have a
greater effect on the BOD_5 test than *Actinastrum* and may
therefore be responsible for high BOD_5 measurements.

These conclusions indicate that the algal content of
oxidation pond effluent is not necessarily deleterious to

the receiving water and underlines the need for an effluent
test which will utilize other criteria to determine the
treatment efficiency of oxidation ponds.

9. IMPLICATIONS AND RECOMMENDATIONS

The results of this project indicate that if oxidation ponds are used as sewage disposal methods by construction camps in the North, it is unlikely that the algal fraction of the effluent will be seriously detrimental to a flowing, receiving water. The most suitable receiving water is one which is constantly flowing with sufficient speed to effect good mixing of the effluent and receiving water and one which does not have a fluctuating flow which may at times become too low to be effective. There are, however, other considerations which must be taken into account.

A high level of treatment will only be achieved during the summer months when ponds are ice-free and algae can develop and provide aerobic conditions for degradation. During much of the year when ponds are covered by ice, treatment will be anaerobic and consequently poor. It may therefore be necessary to size oxidation ponds so that they have a one-year retention and can be drawn down at the end of the summer. This practice could result in extraordinarily large numbers of algae being discharged into a receiving water within a short time. It is therefore essential that the receiving water be of sufficient size and flowrate to absorb this load. Consideration must therefore be given to the selection of a suitable receiving water before deciding on the location of a camp.

A two-celled oxidation pond system would overcome the necessity to draw down at the end of the summer and would provide better than 1-year retention of the effluent. Using this system the first cell could be charged throughout the year and should be discharged to the second cell in the spring. The second cell should then be left for a year and discharged the following spring at a time when the algal population is lowest. The second cell would have a complete summer of treatment followed by a winter period when much of the algal biomass would settle out, producing an effluent of good quality for spring discharge. Each cell of a two-cell system should be of sufficient size for a one-year retention of effluent.

It is therefore recommended that, where single oxidation ponds are to be used for sewage treatment, they be sized for a one-year retention and be located so that the effluent (which should only be discharged during summer) can be discharged to a flowing water body of sufficient size and flowrate to allow no more than a 100-fold increase in the phytoplankton population. This could approximately be achieved by a 100:1 dilution of the effluent. Systems using two cells should be drawn down in spring when the algal population is low.

10.   NEED FOR FURTHER STUDY

The results of this study have indicated that the algal
fraction of algae-rich effluents may not be directly
detrimental to a receiving water during the summer.

Originally, field sampling for this study was to continue
into late fall 1973, but due to a breakdown of equipment
and other restrictions, it was necessary to terminate the
field sampling in September 1973. At the time the last
samples were taken, high levels of algae were being recorded
in the effluents from the oxidation ponds under study.
Colder temperatures and decrease in daylight with the
approach of freeze-up may adversely affect the phytoplankton
population in the oxidation ponds.   If a large percentage
of the phytoplankton died off, this might exert an increased
oxygen demand on the receiving water. There is, therefore,
a need to determine the fate of oxidation pond algae during
and after freeze-up.

The second phase of this project, which was to develop
alternative tests for assessing the treatment efficiency
of an oxidation pond, has not been started. There is an
indication, from this study, that *Scenedesmus* has a greater
effect on the BOD_5 test than does *Actinastrum*. There is,
therefore, a need to investigate this finding and to
determine the influence of various species of algae on the
BOD_5 test.

There is also a need to define the light conditions under
which little change in algal biomass takes place and to
develop standard light conditions for a BOD_5 test which
will eliminate interference by the algal fraction of the
test wastewater.

11. REFERENCES

Caldwell, D.H. and Parker, D.D., 1973. Upgrading Lagoons. U.S. Env. Protect. Agency, Technol. Transfer Program.

Dawson, R.N., Grainge, J.W., Shaw, J.W. and Greenwood, J.L., 1973. Sewage Lagoon Systems. Supplementary Report A to the report Management of Waste from Arctic and Sub-Arctic Work Camps by Grainge, J.W., Edwards, R., Heuchert, K. and Shaw, J.W., 1973.

Edmondson, W.T., 1969. A Simplified Method for Counting Phytoplankton in A Manual on Methods for Measuring Primary Production in Aquatic Environments, ed. R.A. Vollenweider. IBP Handbook No. 12. Blackwell Scientific Publications, Oxford, England.

Grainge, J.W., Edwards, R., Heuchert, K. and Shaw, J.W., 1973. Management of Waste from Arcitc and Sub-Arctic Workcamps. Report No. 73-19 for the Environmental-Social Committee, Northern Pipelines, Task Force on Northern Oil Development. Dept. Indian Aff. North. Develop. Ottawa.

Krishnaswami, S.K. and Slupsky, J.W., 1970. Bow River Pollution and Limnological Survey, Banff National Park, Alberta. Summer, 1969. Div. Public Health Eng., Dept. Nat. Health Welfare, Edmonton, mimeo.

Prescott, G.W., 1970. How to Know the Freshwater Algae. Wm. C. Brown, Dubuque, Iowa. pp. 348.

Robinson, D.J., 1972. A Survey of Water Quality and Stream Invertebrate Communities in the Vicinity of Lake Louise and Lake O'Hara During the Summer of 1971. Can. Wildlife Serv. Nat. Hist. Parks Br. Dept. Indian Aff. North. Develop., Edmonton, mimeo.

Smith, G.M., 1950. The Freshwater Algae of the United States. McGraw-Hill, Toronto, 2nd Ed., pp. 719.

Standard Methods for the Examination of Water and Wastewater, 1971. 13th Ed. Amer. Pub. Health Assn., New York.

Ward, H.B., and Whipple, G.C., 1959. Fresh Water Biology, John Wiley and Sons, New York. 2nd Ed., pp. 1248.

Welch, P.S., 1948. Limnological Methods. McGraw-Hill, Toronto. pp. 381.

EFFECTS OF LAND SEWAGE DISPOSAL ON
SUB-ARCTIC VEGETATION

by

RICHARD FAHLMAN
ROGER EDWARDS

Technology Programs Section

Technical Branch

Northwest Region

Environmental Protection Service

Environment Canada

MARCH, 1974

CONTENTS

LIST OF TABLES

1. SUMMARY

A study was initiated to ascertain the effects of land sewage disposal on vegetation in Canada's north, and also to determine if such disposal, through nutrient enrichment, may be beneficial for the renovation of disturbed areas. Sewage was applied to two cut-lines in the subarctic boreal forest region, one near Fort Simpson, the other near Norman Wells, N.W.T. The vegetation on the treated areas was monitored after one growth season to assess the impact of the applied effluent. No adverse effects or changes in overall productivity, in terms of current biomass production, were evident. In the Fort Simpson study, production of the herb *Epilobium angustifolium,* was significantly increased on treated areas. Thus, some indication of the growth enhancement of pioneer species was seen.

Although it is expected that no harmful effects, and possibly some beneficial ones, may be engendered on terrestrial vegetation through land disposal of domestic sewage, it is not recommended that such a practice be considered as a major means of disposal for construction camps in the N.W.T. Much of this area is situated in permafrost regions or in locations where the water table is close to the ground surface. Irrigation with effluent under such conditions would cause a rapid saturation of the soil and the possibility of contamination of ground water and surrounding water bodies could become a problem.

2. INTRODUCTION

2.1 Nature and Scope of Study

This study examines the effect of land sewage disposal on subarctic vegetation, and, in particular, the impact of such disposal on areas which have been subjected to surface disturbances through the activities of man.

2.2 Relation to Proposed Pipeline Development

If the development of a pipeline down the Mackenzie Valley is undertaken, a large labor force will be required during construction, requiring a number of large transient work camps along the proposed route. Each of these camps will be faced with the problem of disposing of its domestic sewage. The land application of effluent may provide an inexpensive and effective method of sewage disposal. Also, secondary benefits might be derived from land irrigation. Sewage effluents contain important plant nutrients, notably nitrogen and phosphorus compounds, the availability of which is often limited in northern areas. Thus the application of nutrient-rich effluents to disturbed sites, such as cut-lines, road sides and reclaimed borrow-pits, may assist in the revegetation and ultimate renovation of such areas.

3.   CURRENT STATE OF KNOWLEDGE

The concept of waste disposal on land is not new. Irrigation of crop-
land with sewage wastes is a centuries-old practice. In recent years
expected water shortages in many areas of the world have increased in-
terest in the use of land for wastewater disposal.

Studies of land irrigation in forested areas have been reported in the
literature, (Little et al., 1959; Sopper and Sagmuller, 1966; Sopper,
1971; Sopper and Kardos, 1973; and Urie, 1973). These studies, how-
ever, were conducted in temperate regions where severe climatic condi-
tions, as experienced in northern Canada, were not a factor. Virtual-
ly nothing is known regarding land sewage irrigation in boreal, or
arctic tundra communities.

4. STUDY AREAS

4.1 General Comments

Three areas were chosen for research purposes. Two are situated on disturbed sites within the boreal forest zone, one in a non-permafrost area near Fort Simpson, and the other in a location where underlying permafrost was present (Norman Wells). The third site is in a tundra dwarf shrub-heath community near Tuktoyaktuk. Only the two forest community sites will be discussed in this report, completion of the tundra irrigation study is scheduled for the fall of 1974 and will be reported at a later date.

4.2 Geographic Locations

4.2.1 Fort Simpson Site

The test area is situated on a seismic cut-line running in a northerly direction from the Mackenzie highway, between mile 304 and mile 305 (Figure 1).

4.2.2 Norman Wells Site

The study area is located on a cut-line approximately 0.8 of a mile northeast of the Gas Arctic test facilities at Norman Wells. Access is available from the road leading to the townsite quarry (Figure 1).

4.3 Climate

Both sites are included in Koppen's Dfc climatic classification or the subarctic classification of Brandon (1965). Such a climate is characterized by long, cold winter and short, cool summers, with some warm periods. Pertinent climatic data can be found in the Atmospheric Environment publication, Temperature and Precipitation. 1941-1970. The North - Y.T. and N.W.T.

4.4 Vegetation and Soils

4.4.1 Fort Simpson Site

Soil type was of the brunisolic order and the underlying parent material consisted of fine glacio-lacustrine sands. The site was imperfectly-drained and no permafrost was present.

Location of the area is within the Upper Mackenzie section of the boreal forest region (Rowe, 1972). The dominant forest cover was white spruce, *Picea glauca*, and aspen poplar, *Populus tremuloides,* with some intermixed black spruce, *Picea mariana,* and balsam poplar, *Populus balsamifera*. Composition of the shrub layer was wild rose, *Rosa acicularis,* willows *Salix* spp., and *Vaccinium* spp. Fireweed, *Epilobium angustifolium*, was the dominant species of the herb-grass layer. Sedges, *Cartex* spp., horsetails, *Equisetum* spp., wild strawberry, *Fragaria virginiana,* and bunchberry, *Cornus canadensis*, were also widespread.

Mosses and lichens were almost totally absent from the study area, although they formed an almost continuous mat on the undisturbed areas.

4.4.2 Norman Wells Site

Soils were poorly drained and consisted of a 30cm organic horizon underlain by a high-ice content, clayey till. At the time of vegetation sampling (mid-July), the active layer had an average thickness of approximately 35 cm.

The test site is situated in the transitional area between the Upper and Lower Mackenzie sections of the boreal forest zone (Rowe, 1972). The major aspect characterizing the separation of these two sections is the replacement of the *Populus* species, abundant in the Upper Mackenzie section, by white birch, *Betula papyrifera*, in the Lower section. Also, the prevalence of permafrost is more widespread in the Lower section and its impact upon the vegetation more pronounced.

Plots were established on a cut-line cleared through a mature black spruce community. Some scattered white spruce and tamarack, *Larix laricina*, were present. Alder, *Alnus crispa*, and white birch occurred in open areas. Dominant shrubs were willows, cinquefoil, *Potentilla fruticosa*, and wild rose. The dwarf shrub layer was composed of kinnickinnick, *Arctostaphylos rubra*; cowberry, *Vaccinium vitis-idaea*, and twinflower, *Linnaea borealis*. Major herbs were sedges, *Carex* spp.; horsetails, *Equisetum* spp.; and *Pyrola* spp. *Hylocomium splendens* and other feather mosses formed an almost continuous layer over the study area.

LIST OF TABLES

1.   SUMMARY

The intention of this investigation was to determine the
overall effectiveness of extended aeration treatment plants
operating at two Imperial Oil Limited drilling camps in the
Mackenzie Delta area on the artificial islands IMMERK and
ADGO-F28.

The observations and results of the investigation indicate
the following:

1.   There is a need for training programs for treatment
     plant operators in the North.

2.   Raw sewage having a BOD_5 of 1000 to greater than 2000 mg/1
     can be expected at drilling camps.

3.   More care is required in the sizing of treatment plants
     for camps in the North. Organic and hydraulic loadings
     require special consideration.

2. INTRODUCTION

The following report is supplementary to that prepared by
Grainge et al, 1973.

The advent of oil and gas exploratory work in the Northwest
Territories, accompanied by the possibility of large pipeline
construction camps operating in the Mackenzie Valley
necessitates a sound policy for domestic waste treatment in
the North. One possible method for obtaining high sewage
treatment efficiencies is by rapid biological decomposition
of the waste by an activated sludge treatment process, such
as an extended aeration treatment plant.

To date, the efficiency of extended aeration treatment plants
operating in the Northwest Territories has not been assessed.

Through the assistance and cooperation of Imperial Oil Limited,
extended aeration treatment plants on the IOL artificial islands,
IMMERK and ADGO-F28,were evaluated with regard to plant perform-
ance and operational difficulties.

The two islands were constructed for the purpose of off-shore
drilling, with the actual drilling operations in each location
lasting for approximately three months.

During the investigation period an Environmental Protection
Service employee was on site to assist in the operation of the
plants.

The specific objectives of the project were to determine:

1. The characteristics of the raw waste to be treated,

2. The operation and maintenance requirements of the
   plants, and

3. The operational parameters necessary to reach a high level
   of treatment efficiency.

3. CURRENT STATE OF KNOWLEDGE

The activated sludge process has been used for domestic
sewage treatment for several decades and its applications
have been well documented. The capabilities of this
process for obtaining high removals of BOD and suspended
solids in treating domestic sewage has been proven many times
over. However, the use of extended aeration treatment plants
at work camps in the Northwest Territories is relatively
new and their effectiveness as a means of treating camp
wastes has not been extensively evaluated.

4.   STUDY AREAS

The average treatment plants evaluated were manufactured by
CLOW corporation. They were AER-O-FLO model 250 package
plants of the type shown in Figure 1 having a design capacity
of 9,433 l. of sewage per day. The treatment plants on IMMERK
did not have effluent chlorination facilities.

4.1   IMMERK

The artificial island IMMERK was located east of Pelly Island
in Mackenzie Bay and was constructed during 1972-73. The
drilling camp was situated on a barge, owned by Northern
Construction Co. Ltd. This barge was also used during the
island construction phase.

During this investigation, the average population of IMMERK
was approximately 50, with a sewage flow of approximately
11,330 l. per day. Water for washing and cooking was taken
from the immediate vicinity of the camp and passed through
a desalinization unit prior to use. Flush water for the
toilets was taken directly from the surrounding area with no
treatment before use. During part of the drilling period,
the toilet flush water had a high silt and chloride content.
The salinity of the water varied from 0 to 2.8%.

Two AER-O-FLO treatment plants were located in the lower
portion of the barge at the aft end. One plant was on the
starboard side and the other was on the port side. Figure 2
is a schematic diagram of the treatment plants locations. The
two treatment plants were completely enclosed by the hull.
The only access for servicing was through 61 by 91.5 cm. bolt-
down hatches over the settling tanks. There was no shelter
over these hatches. Raw sewage flowed by gravity from the
washrooms and kitchen to the treatment plants and it was
comminuted prior to entering the aeration compartments.

The owner and operator of the sewage treatment facilities was
completely unfamiliar with the proper procedures for operating
these plants.

4.2   ADGO-F28

ADGO-F28 was located south of Garry Island in Mackenzie Bay.
Construction of the island during August 1973 and drilling
operations commenced during December, 1973. Water for domestic
purposes was taken from the immediate vicinity of the island and
it was chlorinated prior to use.

The AER-O-FLO treatment plant situated on the camp barge was
purchased during August, 1973. The treatment plant was housed
in a heated trailer and all parts of it were very accessible.
Figure 3 is a diagram of the plant and raw sewage holding
tank.

Sewage from the washroom and kitchen flowed by gravity to
the holding tank which had a holding capacity of 90-140
litres before it was pumped to the plant.

MODEL 250 C AER-O-FLO
PACKAGE SEWAGE TREATMENT
PLANT

SECTION B-B

SECTION A-A

FIGURE I

EXTENDED AERATION TREATMENT PLANTS
IN BOTTOM OF BARGE [IMMERK]

ACCESS PORTS FOR SERVICING

FIGURE 2

SEWAGE TREATMENT PLANT IN TRAILER HOUSING [ADGO F 28]

RAW SEWAGE

HOLDING TANK LIFT STATION (Holding Capacity)

90-135 Litres Before Pump Out

COMMINUTOR

MOTOR BLOWER & CONTROLS

BAFFLE

Effluent Pipe

HYPOCHLORINATOR

FIGURE 3

5. METHODS AND SOURCES OF DATA

A small number of samples were collected from the treatment plants at IMMERK because of inaccessibility to the various sections of the plants. A total of five "grab samples" were collected during the months of October and November, 1973.

At the beginning of January 1974, an extensive sampling program was started on the ADGO-F28 treatment plant. A number of 24-hour composite samples were collected of the raw sewage influent and treatment plant effluent. Daily routine tests and observations were also made on each stage of the plant with the overall objective of obtaining optimum treatment efficiency.

The samples for chemical analyses were frozen immediately after collection and forwarded to the Environmental Protection Service Laboratory in Edmonton for analyses. Most of the samples collected from the influent and effluent streams of the ADGO-F28 treatment plant were 24-hour composites. It is not known what effect freezing had on the various parameters.

The following analyses were carried out by the EPS Laboratory.

    BOD_5 (filtered & unfiltered)
    COD (filtered & unfiltered)
    Suspended Solids
    Volatile Suspended Solids
    Total Residue
    Fixed Residue
    pH
    Alkalinity
    Ammonia Nitrogen
    Nitrate Nitrogen
    Nitrite Nitrogen
    Total Phosphorus
    Organic Nitrogen
    Total Carbon (filtered & unfiltered)
    Organic Carbon (filtered & unfiltered)
    Inorganic Carbon (filtered & unfiltered)
    Hexane Extractables

All of the analyses were carried out in accordance with Standard Methods for the Examination of Water and Wastewater, 1971.

A series of bacteriological samples were also collected. The methods of analyses are given in Appendix B. Unfortunately, a number of the bacteriological samples froze before reaching the laboratory. The implications of this are discussed later in this report.

6.   OBSERVATION AND RESULTS

6.1   IMMERK

The IMMERK treatment plants were inspected for the first time by an Environmental Protection Service employee on October 19 and 20, 1973. Observations made of the starboard plant were as follows:

1.   Dissolved oxygen: 3-4 ppm (Hach kit).

2.   Thirty minute settleable solids using 1000 ml. graduated cylinder: 0% (trace on bottom of cylinder). Supernatant was slightly murky. Evidence of food waste (corn, mushrooms, etc.) present.

3.   Sludge return was translucent and rate appeared high.

4.   Skimmer was not operating due to list in barge. A thin layer of scum was present on settling tank surface.

5.   Color of aeration tank was light chocolate brown.

6.   Diffusers appeared to be working well.

7.   There was a large amount of rust build-up on the inside of the plant.

8.   Blowers were running continuously.

9.   A slight raw sewage odor was noticed.

When the port plant was inspected and sampled, the following observations were made:

1.   Aeration tank appeared similar to starboard plant - light chocolate brown and evidence of food waste. A greater amount of rust was observed.

2.   Diffusers were not working properly - bubbles and surface currents were not distributed evenly.

3.   Dissolved Oxygen: 1 ppm. (Hach kit).

4.   Settleable solids: 1 3/4 - 2% Supernatant was slightly murky.

5.   Sludge return appeared translucent.

6.   Skimmer was totally plugged.

7.   Initial odor was similar to starboard plant but slightly stronger.

8.   Blowers and sludge return were on continuous 24-hour
       operation.

In order to collect samples from the port plant, a black,
fibrous mat on the surface of the settling tank had to be
broken. This required about 5 kg. force. When the mat
was broken, a thick, black fluid filled the hole along with
clumps of black, spongy, floating material which was
originally under the mat. A strong, septic, hydrogen sulfide
and ammonia-like odor was noted.

One sample was taken from the settling tanks of the two plants.
In each case the surface layer was avoided as much as possible.
A third sample was collected, through the ice at the side of
the barge, near the discharge of the starboard plant, at a
depth of 2.5 m, which was 0.3 m above the sea bottom. A
fourth sample was taken through the ice on the port side of
the barge near the discharge of the port plant at a depth of
0.5 m. which was 15 cm. above the sea level.

No routine analyses were being carried out concerning operation
of the treatment plants.

On November 30, 1973, a second sample was taken from the
settling compartment of the starboard plant. The port plant
was not in operation at that time. Table 1 gives the results
of the analyses carried out on all the samples collected.

6.2   ADGO-F28

At the time of initial inspection, of the ADGO-F28 waste
treatment facilities, on October 3, 1973, there were approx-
imately 20 men in residence at the camp. A relatively strong
sewage odor was noted in the vicinity of the treatment plant.
The contents of the aeration and settling compartments were
a dark grey color and a number of grease balls were floating
in the aeration compartment. The air blowers were being
operated on a fifteen minute on-off cycle with what appeared
to be a very high sludge return rate. There was no equipment
available for doing routine tests concerning the operational
performance of the plant. The operator was unfamiliar with the
proper operational procedure for the plant.

A grab sample was collected from the settling compartments at a
15 cm. depth. The results of the analyses of this sample and a
sample taken of the chlorinated effluent on November 30, 1973
are given in Table 2.

The domestic water being used at the time of the October inspection
had been hauled from Imperial Oil Limited's Bar C Camp
in the Mackenzie Delta. When this supply was depleted, the
camp population was reduced to 3 men for a period of

approximately one month. The camp population was increased
to approximately 40 men during November. The domestic
water supply was then taken directly from the area around
the island. It was chlorinated before use.

Appendix A contains the results of the analyses carried
out on the influent and effluent composite samples taken
during the course of this investigation. Daily observations
are also included in Appendix A. Monthly averages of the
results are given in Table 3. Table 4 contains average
percent removals of a number of the parameters measured.

Tables 5, 6, 7 and 8 give the bacteriological determinations
of coliform bacteria, fecal coliform bacteria, fecal strep-
tococci, and standard plate counts at 35°C and 20°C. The
bacteriological samples were collected from the raw sewage
influent, the treatment plant settling compartment and the
chlorinated effluent.

TABLE 1

SEWAGE ANALYSES OF SAMPLES TAKEN FROM EXTENDED AERATION TREATMENT PLANT
I.O.L. - IMMERK

	Starboard Plant Settling Compt. (Oct. 23)	Starboard Plant Settling Compt. (Nov. 30)	Port Plant Settling Compt. (Oct. 23)	Starboard Plant Outfall (Oct. 23)	Port Plant Outfall (Oct. 23)
BOD5	675	5400	4050	225	166
BOD5 (filtered)	-	232	-	-	-
COD	716	1000	41700	368	119
COD (filtered)	-	955	-	-	-
Suspended Solids	267	6452	72850	215	22
Volatile Suspended Solids	164	6140	66000	96	3
Total Residue					
Fixed Residue					-
pH	7.6	6.9	6.5	7.6	8.0
Alkalinity as CaCO3	532	576	1000	212	98
Ammonia Nitrogen	24	235	36	29	3.0
Nitrate Nitrogen	0.15	0.33	0.17	<0.10	0.11
Nitrite Nitrogen	<0.01	<0.01	<0.01	<0.01	<0.01
Total Phosphorus	0.23	20.0	106	7.33	0.10
Organic Nitrogen	25.8	27.5	213	19.5	11.0
Total Carbon	313	788	830	170	28
Total Carbon (filtered)	-	285	-	-	-
Organic Carbon	200	670	781	131	6
Organic Carbon (filtered)	-	191	-	-	-
Inorganic Carbon	113	118	49	39	22
Inorganic Carbon (filtered)	-	94	-	-	-
Oils & Grease	-	-	-	-	-

NOTE: All constituents are in mg/l except pH which is in pH units.

TABLE 2

SEWAGE ANALYSES OF SAMPLES TAKEN FROM EXTENDED AERATION TREATMENT PLANT
I.O.L. - ADGO - F-28

	Settling Compt. (October 3/73)	Chlorinated Effluent (November 30/73)
BOD5	1100	652
BOD5 (filtered)	-	396
COD	2284	1337
COD (filtered)	-	655
Suspended Solids	644	438
Volatile Suspended Solids	540	318
Total Residue		
Fixed Residue		
pH	7.5	7.6
Alkalinity as CaCO3	626	661
Ammonia Nitrogen	100	95
Nitrate Nitrogen	0.19	0.33
Nitrite Nitrogen	0.01	0.05
Total Phosphorus	40	53.3
Organic Nitrogen	75	30
Total Carbon	847	530
Total Carbon (filtered)	681	310
Organic Carbon		417
Organic Carbon (filtered)		211
Inorganic Carbon	166	113
Inorganic Carbon (filtered)		99
Oils & Grease		

NOTE: All constituents are in mg/l except pH which is in pH units.

AVERAGES OF SEWAGE ANALYSES OF ADGO-F28 TREATMENT PLANT INFLUENT AND EFFLUENT

	INFLUENT JAN/74	INFLUENT FEB/74	EFFLUENT JAN/74	EFFLUENT FEB/74
BOD5	2080	1750	413	383
BOD5 (filtered)	670	543	265	223
COD	3154	2505	1164	978
COD (filtered)	1083	1363	592	523
Suspended Solids	1339	900	332	281
Volatile Suspended Solids	1083	720	219	210
Total Residue	2097	1921	1984	1658
Fixed Residue	954	863	1430	1130
pH	7.8	7.8	7.6	7.8
Alkalinity as CaCO3	642	595	715	710
Ammonia Nitrogen	173	105	178	96
Nitrate Nitrogen	0.10	0.15	0.10	0.1
Nitrite Nitrogen	0.10	0.01	0.10	0.01
Total Phosphorus	37	41	36	37
Organic Nitrogen	110	40	74	47
Total Carbon	936	973	447	456
Total Carbon (filtered)	399	347	326	289
Organic Carbon	827	887	306	325
Organic Carbon (filtered)	295	264	179	159
Inorganic Carbon	109	86	141	131
Inorganic Carbon (filtered)	104	83	147	130
Oils & Grease	419	414	42	27
Average Flow (gallons/day)	1435	1413		

NOTE: All constituents are in mg/l except pH which is in pH units. Influent Analyses of January 29/30 were not used in averaging values.

TABLE 4

AVERAGE REMOVALS IN ADGO-F28 TREATMENT PLANT

	JAN./74 (mg/l)	(%)	FEB./74 (mg/l)	(%)
BOD5	1667	80	1367	78
BOD5 (filtered)	405	60	320	59
COD	1990	60	1527	61
COD (filtered)	491	45	840	61
Suspended Solids	1007	75	619	69
Volatile Suspended Solids	864	80	510	71
Total Residue				
Fixed Residue				
pH				
Alkalinity as CaCO3				
Ammonia Nitrogen				
Nitrate Nitrogen				
Nitrite Nitrogen				
Total Phosphorus	36	33	0	0
Organic Nitrogen	489	53	517	53
Total Carbon	73	18	58	17
Total Carbon (filtered)	521	63	562	63
Organic Carbon (filtered)	116	39	105	40.
Inorganic Carbon				
Inorganic Carbon (filtered)	377	90	387	94
Oils & Grease				

TABLE 5

BACTERIOLOGICAL RESULTS
ADGO-F28 EXTENDED AERATION SEWAGE TREATMENT PLANT
6 FEB. - 18 FEB.

Sample	Date	Coliform MF per 100 ml	Fecal Coliform MF per 100 ml	Fecal Streptococci MF per 100 ml	Standard Plate Counts 35°C	Standard Plate Counts per ml 20°C
Incoming Sewage	6 February 74	4.8×10^6	3.9×10^5	3.0×10^3	1.2×10^5	1.7×10^5
	11 February 74	6.7×10^8	1.2×10^8	1.3×10^5	2.5×10^7	3.2×10^7
	15 February 74	3.5×10^9	3.4×10^7	4.2×10^3	6.5×10^7	5.7×10^7
	18 February 74	2.2×10^6	1.6×10^5	2.0×10^2	3.4×10^4	3.7×10^4
	Arithmetic Mean	1.0×10^9	3.9×10^7	3.4×10^4	2.2×10^7	2.2×10^7
Settling Tank	6 February 74	4.4×10^5	4.5×10^4	2.0×10^3	1.2×10^5	1.6×10^5
	11 February 74	1.5×10^8	1.4×10^7	2.2×10^4	7.4×10^7	1.4×10^8
	15 February 74	3.4×10^8	1.5×10^8	8.8×10^5	9.7×10^7	2.4×10^8
	18 February 74	1.2×10^7	6.1×10^5	1.5×10^5	5.9×10^7	7.8×10^7
	Arithmetic Mean	1.2×10^8	4.1×10^7	2.6×10^5	5.7×10^7	1.1×10^8
Final Effluent	6 February 74	1.7×10^6	1.2×10^5	4.3×10^3	5.2×10^5	7.0×10^5
	11 February 74	1.1×10^8	1.2×10^7	1.0×10^3	5.6×10^7	6.8×10^7
	15 February 74	8.7×10^6	1.4×10^5	3.2×10^3	2.5×10^6	9.3×10^6
	18 February 74	7.6×10^6	4.7×10^5	9.4×10^4	4.2×10^7	8.3×10^7
	Arithmetic Mean	3.2×10^7	3.2×10^6	2.6×10^6	2.5×10^7	4.0×10^7

Note: Samples received February 11, 1974 were the only unfrozen samples.

TABLE 6

COLIFORM % REDUCTIONS (ADGO-F28)

Date	Raw to Settling Tank	Settling Tank to Final Eff.	Raw to Final Eff.
Feb. 6/74	90.834	74.118*	65.584
11	77.612	26.267	83.582
15	90.286	97.442	97.514
18	81.667*	36.667	71.053*

* Increase in counts from location to location

TABLE 7

FECAL COLIFORM % REDUCTIONS (ADGO-F28)

Date	Raw to Settling Tank	Settling Tank to Final Eff.	Raw to Final Eff.
Feb. 6/74	88.462	62.500*	69.231
11	88.334	14.286	90.000
15	77.334*	99.907	99.588
18	73.771*	22.951	65.958*

* Increase in counts from location to location.

TABLE 8

STANDARD PLATE COUNTS AT 20^{o}C % REDUCTION (ADGO-F28)

Date	Raw to Settling Tank	Settling Tank to Final Eff.	Raw to Final Eff.
Feb. 6/74	5.882	77.143*	75.414*
11	77.143*	51.429	52.941*
15	76.250*	96.125	83.684
18	99.952*	6.025*	99.955*

* Increase in counts from location to location.

7.   DISCUSSION

7.1   IMMERK

The results show that the treatment plants were not operating
efficiently.   There were two reasons for this:

1.   The operator of the treatment plants had no previous
     experience or training in proper operation of an extended
     aeration treatment plant.

2.   The inaccessibility of the treatment plants on the barge
     made them virtually impossible to service to a degree
     where adequate treatment could be expected.

7.2   ADGO-F28

Most of the data collected for this report was obtained at
ADGO-F28.   The main reason for this was the accessibility
to the treatment plant and to all the components making up
the transporting systems to and from the plant.

The data collected show that the ADGO-F28 treatment plant
was organically overloaded.

During the month of January, the average camp population was
approximately 55 and during the sampling period in February
it was approximately 50.   The actual population could vary
considerably from this, especially during crew changes.

Using these populations and the average influent loadings
given in Table 3 the treatment plant would be required to
treat the following average daily loadings:

	Jan. 1974	Feb. 1974=
BOD_5 (influent)	13 kg. (240 gm./man)	11 kg. (222 gm./man)
Suspended Solids (influent)	9 kg.	6 kg.

The average number of pounds of BOD_5 and suspended solids
discharged in the effluent daily during January and February,
1974 were as follows:

	Jan. 1974	Feb. 1974
BOD_5 (effluent)	2.5 kg.	2.0 kg.
Suspended Solids (effluent)	1.8 kg.	1.5 kg.

The AER-O-FLO package treatment plant was actually designed for an average BOD_5 loading of approximately 3 kg. per day. Therefore, the treatment plant was originally overloaded by 3.6 to 4.4 times.

Martin and Schmidt, 1973, have suggested a BOD_5 design parameter of 1 kg/day per man for offshore drilling in the United States. This is approximately two-fifths of the loading experienced on ADGO-F28.

Table 9 gives some raw sewage characteristics experienced in Alaska (Clark et al, 1971). Although the number of samples is limited, the results do indicate that a wide range of values can be expected.

Table 4 shows that BOD_5 removals of 80% were being accomplished in the ADGO-F28 treatment plant. This percentage of removal is somewhat misleading because the effluent BOD_5 was still exceedingly high. These results indicate that a treatment plant serving a drilling camp should provide BOD_5 removals of greater than 98% if an acceptable effluent is to be discharged to the surrounding environment. It would be very difficult for a conventional extended aeration treatment plant to meet this critesion.

Table 4 shows that the per cent organic carbon conversion was only 63%, compared to an impressive 80% removal of BOD_5.

It may be possible, however, to reduce the loading on a treatment plant operating under these conditions. It should be noted that the ADGO-F28 raw sewage influent contained a large amount of hexane extractables (oils and greases). It is believed that this contributed substantially to the loading on the plant.

Figure 4 shows graphically the relationship between the oils and greases (hexane extractables) and COD, BOD_5, volatile suspended solids, and organic carbon of influent samples. The hexane extractables vary according to the other four parameters.

Figure 5 compares graphically the hexane extractables with the filtered-residue BOD_5, COD and organic carbon of the influent samples. The majority of the oils and greases would have been filtered out and therefore any loadings to the plant contributed by this fraction would be reflected in the results of the filtered samples. Figure 5 does in fact show a correlation between the oils and greases and the portion of the BOD_5, COD and organic carbon that was filtered out.

The removal of the hexane extractables from the influent raw sewage stream could reduce the organic loading on the plant substantially, and in turn result in a higher quality effluent being discharged.

In an attempt to reach as high a treatment efficiency as possible, under the existing conditions, the air blower was put on continuous operation at maximum capacity in order to reach a dissolved oxygen level of 1-3 mg/l in the aeration compartment. The organic loading was too great and no residual dissolved oxygen could be maintained. This is recorded in the routine testing results in Appendix A. An attempt was also made to add extra oxygen by the addition of hydrogen peroxide (H_2O_2). This proved to be of no value. The H_2O_2 was utilized almost immediately after addition, indicating a very high oxygen demand. The H_2O_2 additions and results are given in Appendix A, page 37.

Due to the inability to maintain an oxygen level in the aeration compartment an aerobic biological floc could not be supported. This is also recorded in the routine daily testing records in Appendix A. The return sludge from the settling compartment was continually anaerobic and had poor settling characteristics.

The deficiency of oxygen throughout the treatment plant is well reflected in the nitrogenous compounds in the samples analysed. There was virtually no conversion of organic and ammonia nitrogen to nitrite or nitrate nitrogen.

During January there was a decrease in organic nitrogen content in passing through the plant (see Table 3, page 15) accompanied by a slight increase in ammonia nitrogen. The organic carbon to organic nitrogen ratios of the influent and effluent were 7.5 and 4.1 respectively. Because of these variations it appears that the organic nitrogen was being converted to ammonia nitrogen, with ammonia nitrogen given off to the atmosphere.

The influent and effluent results for February, on the other hand, show an increase in organic nitrogen and a decrease in ammonia nitrogen. The organic carbon to organic nitrogen ratios for the influent and effluent were 22 and 6.8 respectively. The C:N ratio of 22 is at the approximate maximum limit for removal of organic nitrogen by the organisms. This would explain the increase in organic nitrogen through the plant. The organisms were actually utilizing the available nitrogen for cell syntheses thus resulting in the higher values in the effluent.

The average removals of BOD_5, COD and carbons (Table 4) show that the largest percentage of removals was in the filterable portion of the samples. At the same time there was a high reduction in oils and greases, indicating

once again that the oils and greases were probably contributing
substantially to the organic loading on the plant.

The reductions of total carbon were probably due to gaseous
carbon compounds given off to the atmosphere.

Graphical representation of effluent concentration of
BOD_5, COD and organic carbon are given in Figure 6. The
variation of these parameters in the effluent stream were
not as pronounced as those in the influent stream. The
effluent COD curve (Figure 4), however, does show the
general trend of influent COD. The BOD_5 and organic carbon
curves show relatively constant concentrations. One reason
for this buffering trend would be the dilution effect and
thorough mixing in the treatment plant.

As can be seen by the influent results the waste entering the
plant was not consistent in BOD, COD, organic carbon, volatile
suspended solids and oils and greases. These parameters vary
considerably from day to day as shown in Figure 4. This would
undoubtedly create problems in efficient treatment, even
if the plant was sized properly.

The anaerobic conditions combined with the varying organic
loading made it impossible to maintain any kind of a consistent
mixed liquor suspended solids concentration or sludge volume
index. This is shown in Appendix A. It is interesting to
note, however, that the SVI's were still in the acceptable
range for proper operation of extended aeration treatment plants,
during most of the time, even though the other operating para-
meters, such as dissolved oxygen, were not in the range re-
commended.

Conclusions from the bacteriological results cannot be made
as freely as one would wish. The results, although possibly
indicative, must be considered unreliable as all the samples
were frozen, except for those received on February 11.
Freezing of samples usually has the effect of partial steriliza-
tion and this sterilization effect is not consistent. Factors
affecting the population would be temperature of freezing,
speed of freezing, organic and particulate make up of the
sample and quantities and types of population within the sample.

All of the data are outlined in Table 5. Although the samples
were frozen, the results do reveal extremely high populations
of coliforms, fecal coliforms, fecal streptococci and total
heterotrophic bacteria. The numbers would indicate the likely
passage of pathogenic organisms into the environment showing
the inadequacy of the chlorination system. The high numbers
of heterotrophs throughout the system probably reflects a high
organic loading in the plant.

Tables 6, 7 and 8 show what was hoped would be the
bacterial reduction throughout the system. In fact, they
very often show increased numbers, particularly in the settling
tank and frequently between the raw and final effluent. This
indicates that the settling tank is in fact functioning very
well as a growth chamber. Chlorination of the effluent is
obviously having little or no effect on the bacteriological
population. This is probably due to the high organic content
in the effluent.

7.3   General

The observations and results to date show that if the treatment
plants investigated are to be used for future camps of a similar
nature, a number of changes will have to be made if a good
quality effluent is to be expected. Suggested changes for the
treatment plants at IMMERK are as follows:

1.   The hatch in the deck above the plants should be enlarged
      so that all diffuser valves and lines, the sludge return
      lines, and the effluent troughs are accessible by hand,
      and so that all sides and corners of the settling tank and
      aeration tank are accessible for cleaning.

2.   An insulated, heated, ventilated and lit shelter, large
      enough for an operator to stand in and have working access
      to the plants, should be constructed above the hatches.

These changes require major alterations to the present system,
but they are necessary if the treatment plants are to serve the
purpose for which they were designed.

It is recommended that additional work be carried out on the
treatment plant that was situated on ADGO-F28 to determine what
size of camp it is suited for.

Another very important point which must be kept in mind when
considering the use of extended aeration treatment plants at
northern camps is that these plants require a trained and
conscientious operator whose prime responsibility is to maintain
an efficient operating plant. Too often these plants are operated
by the camp maintenance man, who has had no training in the routine
tests which must be carried out and in the overall theory of
the operation of the plant. This appears to have been the case
at IMMERK. IMMERK, however, is not the only treatment plant
being operated by an untrained operator. Table 10 and Fig. 7 give
effluent results of extended aeration treatment plants operating
in Alaska and Manitoba, respectively. The operators of all the
plants discharging an acceptable effluent are conscientious
about their work. The operator of all of the plants in Manitoba,
meeting the Federal Facility BOD objectives, have attended an
operator training program.

Although it was virtually impossible, under the conditions, to treat the camp sewage at IMMERK and ADGO-F28 to an acceptable degree, valuable information was obtained concerning the chemical and bacteriological characteristics of raw sewage that could require treatment at northern camps.

The raw waste at ADGO-F28 appeared to be biologically treatable with respect to pH, alkalinity, nitrogen, phosphorus and organic carbon. However, many more data are required concerning the characterization of camp wastes before general recommendations can be made regarding a treatment plant size for a given installation.

INFLUENT CHARACTERISTICS DURING
INVESTIGATION (JAN. 5 to FEB. 14/74)
ADGO-F28

FIGURE 4

INFLUENT FILTER-RESIDUE COD, BOD$_5$ & ORGANIC CARBON
COMPARED TO INFLUENT OILS & GREASES   (JAN. 5 to FEB. 14/74)
ADGO F-28

FIGURE 5

EFFLUENT COD, BOD$_5$ and ORGANIC CARBON VARIATIONS
(JAN. 6 to FEB. 11/74) ADGO-F 28

FIGURE 6

TABLE 9

(after Clark et al, 1971)

NORTH SLOPE RAW SEWAGE CHARACTERISTICS

Location	Date	Population	BOD	COD	TS	SS
Toolik	7/16/70*	12	484	842	894	387
	8/20/70*	12	380	2440	2790	330
	9/30/70*	9	–	1605	1298	228
	3/17/71*	7	–	7610	–	–
	3/22/71*	7	–	3260	–	–
Deadhorse	8/20/70*	10	740	2000	2024	816
	9/16/70*	6	–	842	–	811
Mikkelson (All wastes except toilet)	4/13/71**	50	–	550	–	–
(Toilet Wastes)	4/21/71	50	–	460[1]	–	–
Galbraith	7/16/70*	15	500–1100	3600	3316	2788
	8/30/70*	10	–	232	582	256
Prudhoe	8/20/70*	85	7830	2510	3154	1547
(Average of 7 days of composites in March 1971)**		75	600	1150	–	1500

*   Grab samples from mixed surge tanks

** Composite samples taken with composite sampler on basis of frequency but not flow matching

1 Sampled by others

TABLE 10

(after Clark et al, 1971)

NORTH SLOPE SEWAGE TREATMENT
PLANT EFFLUENT CHARACTERISTICS

System	Date	BOD	COD	SS
Galbraith	9/16/70	–	696	291
	7/16/70	33	–	68
	9/01/70	28	–	15
	9/30/70	–	113	28
Happy Valley	9/30/70	0	324	147
Prudhoe	7/30/70	180	364	34
	8/20/70	153	371	106
	9/16/70	–	1167	1049
	3/12/71	40	170	68

8.   CONCLUSION

1.   The sewage treatment plants on IMMERK will not operate
      efficiently until alterations are made so that the
      plants can be serviced.

2.   The ADGO-F28 treatment plant was organically overloaded.

3.   The organic loading of the influent raw sewage to the
      ADGO-F28 treatment plant was approximately 4 times that
      for which the treatment plant was designed.

4.   The effluents of the IMMERK and ADGO-F28 sewage treatment
      plants were of very poor quality and pathogenic organisms
      and viruses were probably being passed to the receiving
      waters.

5.   The chlorinator on the ADGO-F28 treatment plant was having
      little or no effect on destroying pathogenic bacteria
      in the effluent.

9.   IMPLICATIONS AND RECOMMENDATIONS

9.1   Pipeline Construction Camps

The potential use of extended aeration treatment plants at
pipeline construction camps must be recognized and certain
precautions must be taken before allowing a camp site to
use this type of treatment. It is essential that conditions
and stipulations, as listed below, accompany the granting of
a permit to install an extended aeration treatment plant, or
for that matter, any type of treatment plant at a pipeline
construction camp.

1.   A best estimate of the chemical, physical and bacterio-
      logical characteristics of waste to be treated should
      be made. This estimate should be based upon analyses
      of raw sewage from existing camps of a similar nature.

2.   The treatment plant and all of its components including
      the influent and effluent lines must be very accessible
      to inspection and servicing.

3.   Each treatment plant must be accompanied by a small
      laboratory, able to carry out routine daily analyses.

4.   A trained and conscientious operator must be in charge
      of each plant. The prime responsibility of the operator
      should be the proper operation of the plant.

5.   Samples of the plant effluent should be collected on a
      regular basis of at least once every two weeks and sent
      to an independent laboratory for routine sewage analyses.

6.   An acceptable program for sludge wasting and a means of
      sludge disposal must be specified by the contractor.

9.2   General Recommendations Concerning Package Extended
          Aeration Treatment Plants

The extended aeration process is well known for its inability to
accept shock loadings (hydraulic and/or inorganic) while
maintaining a high treatment efficiency. These shock loadings
are even more critical in small extended aeration plants. It is
therefore recommended that a large holding tank, capable of
damping out peak flows and making up for low flows of incoming
raw sewage, be installed. A pump with a capacity approximately
the same as the average daily flow should then be used to pump
raw sewage from the holding tank to the treatment plant, at a
constant rate.

In addition the oils and greases should be separated and
incinerated from the raw sewage.

The following are recommendations for proper day to day
operation of extended aeration treatment plants at pipeline
construction camps:

1. The following maintenance equipment should be available.

    a. Scraper for tanks
    b. Surface skimming net
    c. Dissolved oxygen test kit or dissolved oxygen meter
    d. 1000 ml graduated cylinder for 30 minute settling test
    e. Spare parts for blowers and comminutor as recommended
        by manufacturers

2. A routine maintenance program should be carried out which
    would include the following.

    Daily

    a. Remove floating material in settling tank with skimmer.

    b. Ensure that all mechanical and electrical equipment
        are functioning properly.

    c. Measure dissolved oxygen and settleable solids in
        aeration tank ensuring a D.O. of 1.0 to 3.0 mg/1.

    d. Observe color of mixed liquor, color of sludge return,
        clarity in settling tank, and odor in plant.

    e. Adjust diffuser valves, sludge return rate, and timers
        according to results from above tests and observations.

    f. Calculate the sludge volume index according to:

        $$\frac{30 \text{ minute settling tank (\%) x 10,000}}{\text{suspended solids (mg/1)}}$$

        and maintain at approx. 100 by appropriate wasting.

    Weekly

    a. Scrape sides and sloping bottom of settling tank
        (daily until plant is mature).

    b. Clean out comminutor (more often if necessary).

    c. Clean sidewalls and troughs of all accumulation of
        grease, scum and solids.

    d. Check oil in blower gear box.

Other

    a.   Grease comminutor bearings every two weeks.

    b.   Change oil in comminutor gear housing once per month.

    c.   Change gear case oil of blowers every 2000 hours.

    d.   Lubricate blower shaft bearings periodically.

    e.   Sharpen or replace comminutor blades when dull.

3.   Sludge wasting should take place on a regular basis depending on the specific conditions the plant is operating under.

4.   The operator of the plants should be allowed an average of at least one hour each day to service the plant properly.

5.   A daily logbook should be kept indicating results of tests, observations and maintenance work done.

10.   NEED FOR FURTHER STUDIES

The high organic loadings observed in this investigation indicate that there is a need for further work in this area to determine the chemical, physical and bacteriological characteristics of raw sewage at northern work camps. A detailed examination should be made to determine the daily organic and hydraulic loadings and from where they originate, in a work camp. Characteristics of the wastes coming from the camp kitchen, the washroom and the laundry room should be determined. This investigation would have to be carried out at a number of different types of camps to compare sewage loading characteristics to the camp function.

11.   REFERENCES

Clark, S.E., A.J. Alter, J.W. Scribner, H.J. Coutts,
    C.D. Christianson and W.T. McFall; 1971. Alaskan
    Industry Experience in Arctic Sewage Treatment;
    Environ. Protect. Agency Water Quality Office,
    Northwest Reg.; Alaska Water Lab., College, Alaska;
    Presented at 26th Purdue Ind. Waste Conf., Purdue
    Univ., Lafayette, Indianna.

Grainge, J.W., J.W. Shaw, J. Greenwood; 1973. Factors
    Affecting the Design and Operation of Activated
    Sludge Plants for Wastewater Treatment for Northern
    Work Camps; in Management of Waste from Arctic and
    Sub-Arctic Work Camps by Grainge, J.W., R. Edwards,
    K. Heuchert, and J.W. Shaw; Rep. 73-19 Environ.-Soc.
    Comm., N. Pipeline, Task Force on N. Oil Develop.,
    Dep. Indian N. Aff. Ottawa.

Martin, J.C. and R.K. Schmidt; 1973. Domestic Waste
    Treatment in the Offshore Environment; U.S. Army
    Corps of Eng. and Ecodyne Corp.; Presented at Fifth
    Annu. Offshore Technol. Conf., Houston, Texas, Paper
    No. OTC 1737.

Standard Methods for the Examination of Water and Wastewater;
    1971. APHA, AWWA, WPCF, Publ. Amer. Public Health
    Ass., New York, NY, 13th Ed.

WASTE IMPOUNDING EMBANKMENTS IN PERMAFROST REGIONS:

THE OXIDATION POND EMBANKMENT, INUVIK, N.W.T.

by

D. E. THORNTON
TECHNOLOGY PROGRAMS
TECHNICAL BRANCH
ENVIRONMENTAL PROTECTION SERVICE
DEPARTMENT OF ENVIRONMENT
NORTHWEST REGION

MARCH, 1974

TABLE OF CONTENTS

TABLES IN APPENDIX 3

FIGURES IN APPENDIX 3

1.   SUMMARY

In permafrost regions, thaw bulbs exist beneath those masses
of water which maintain a mean annual temperature above the
freezing point of water. Because many permafrost soils are
unstable when thawed, the creation of such thaw bulbs may
create instability or seepage problems for embankments
impounding water. One possible solution to this problem,
constructing dykes utilizing non-cohesive, self-healing fill
materials, is not acceptable for the containment of waste
water because of the associated environmentally-damaging
high seepage rates. Simple time-independent, steady-state
calculations simulating the thermal regime in the vicinity
of an embankment impounding waste water indicate that, in
the higher latitudes at least, it should be possible to
maintain a frozen core within the embankment, thus minimizing
the problems related to instability and seepage.

A field site adjacent to the existing sewage lagoon at Inuvik,
N.W.T., has been set up to monitor the thermal regime within
and beneath the lagoon embankment. Preliminary data indicate
that, at the start of winter, an unfrozen zone exists within
the lower portions of the gravel embankment and extends a metre
or more into the underlying foundation silts. This zone may
be part of a deep active layer and/or be created by heat
transported by water seepage. To check these conjectures
it is necessary to continue monitoring the thermal regime
for at least one full temperature cycle, that is, one year, and,
concurrently, to use a time-dependent heat conduction model to
attempt to make a quantitative simulation of the processes
at work. Such a model may eventually be used as a design tool
for embankments in the North.

2.   INTRODUCTION

Accompanying the rapid development of the Canadian North
there is a need for sound waste management for both permanent
and transient communities. In the past, oxidation ponds
have provided satisfactory treatment for domestic wastes
at a number of communities in western and northern Canada.
Because of the low-cost, dependable treatment capabilities
and ease of operation, such systems are likely to be an
important method of waste treatment in the North for many
years in the future.

In permafrost regions, bodies of surface water create an
appreciable perturbation in the ground thermal regime. In
particular, thaw bulbs exist beneath those water masses
which maintain a mean annual temperature above the freezing
point. Since many permafrost soils are unstable when thawed,
the creation of thaw bulbs beneath and adjacent to impounded
water may create structural and seepage problems for the
containing embankments.

The structural problems are essentially twofold. Firstly,
the differential settlement created by uneven consolidation
of the underlying thawing soil tends to produce cracks
and fissures in the embankment above. Secondly, as the
thaw front advances within a high-ice-content soil,
relatively large volumes of water may be released which,
unless allowed to escape, could result in the generation
of excess pore-water pressures. Such a situation may lead
to a drastic reduction in soil shear-strength in the thawing
zone and contribute to the danger of catastrophic embankment
failures.

In addition to requirements of structural stability, waste
impounding embankments must be impermeable to ensure the
necessary protection of the environment.

Ideally, data relevant to the performance of a newly
constructed embankment is desirable, particularly in regard
to stability considerations. Unfortunately, no suitable
site is currently available, although a number of compre-
hensive lagoon systems are scheduled for construction in the
near future. With this in mind, the field work for the overall
project was separated into two stages: firstly, an examination
of an existing embankment to determine the long-term state
of such a structure; secondly, the monitoring of a site
immediately before, during and after construction of a lagoon.
Two possible locations for work on the latter stage are
Norman Wells and Inuvik, N.W.T., where lagoon systems are
scheduled for construction to begin in 1974 and 1975,
respectively. To implement the first stage of the project,
the embankment of the existing lagoon at Inuvik, N.W.T.,
was selected for study.

The object of this study is to observe the thermal regime within and adjacent to the lagoon embankment which, apparently, has performed adequately for almost twenty years. Theoretical heat flow calculations will be performed concurrently with the field studies to attempt to gain a quantitative understanding of the processes at work at this site.

3.   RESUME OF CURRENT STATE OF KNOWLEDGE

When considering construction practices in permafrost
regions, it is convenient to consider three general approaches
if the foundation conditions indicate that normal temperate
zone techniques are not applicable.

The first approach consists of appropriate modification to
the foundation conditions prior to construction to ensure
stability. The second approach allows, as part of the design,
the occurrence of thermal degradation and associated settlement.
Finally, the third approach encourages stability by the
maintenance of the existing thermal regime.

In the discontinuous permafrost zone one of the former two
approaches, or a combination of both, is generally favoured,
since relatively minor thermal disturbances are generally
sufficient to initiate the thawing processes in these regions.
In northern Manitoba, for example, reservoir dykes have been
constructed using non-cohesive, self-healing fill materials.
(Johnston, 1969; MacPherson et al., 1970). Such soils allow
limited differential movement and minor foundation failures
without severe fissuring. Further, since non-cohesive soils
typically exhibit high permeabilities, excess pore-water
pressures are rapidly dissipated, a process which is further
encouraged at the above-mentioned sites by the inclusion of
sand drains beneath the dykes. Naturally, the significant
seepage rate associated with such permeable embankments
contributes to the foundation thawing process through the
sensible heat transported by the water. Occasional remedial
work is usually necessary and entails the placement of extra
fill materials to maintain the design freeboard.

The final approach is generally reserved for those areas where
the mean soil temperatures are significantly below the freezing
point. In these cases the permafrost may be allowed to aggrade
within the core of the dam, or freezing may be actively
encouraged by the use of cooling pipes through which the cold
winter air, or even a refrigerant, is circulated. (Bogoslovskiy
et al., 1963). In particular, the thermal regime of a dam
of the more economical, passive design has recently been reported.
(Fulwider, 1973). This dam, the Crescent Lake Dam, is an
earthfill embankment constructed in 1952 near Thule Air Base,
Greenland, (mean annual air temperature approximately -12°C),
to impound a water supply for the base. Temperature readings
collected between 1952 and 1959 indicated that the central
part of the embankment remained frozen throughout the year,
creating an impervious core section. However, similar readings
from mine tailings pond dykes constructed of crushed rock,
in Yellowknife, N.W.T., (mean annual air temperature approximately
-5°C), showed the existence of a thawed zone through the dykes
for the majority of the year (Roy et al., 1973).

No detailed simulations of the thermal regime within a dyke
constructed over permafrost are available in the literature.
The only available theoretical work is a method developed
for estimating the rates of thaw and associated settlement
based on simple analytical approximations in heat conduction
theory and which is strictly applicable only when sensible
heat transported by seepage completely dominates the thawing
process (Brown and Johnston, 1970).

4.   STUDY AREA

The embankment studied in the field investigations impounds
the lagoon which services the town of Inuvik, N.W.T.
(68^o 18' N, 133^o 29' W). The town is located in the east-
central part of the Mackenzie Delta, the physical geography
of which has been described by Mackay (1963). The area
experiences a tempered arctic climate with a mean annual
temperature and precipitation of approximately -9^oC and 28 cm,
respectively.

The Inuvik lagoon consists of a strip of water approximately
910 m x 250 m, averaging a depth of 1.2 m, lying to the
north-west of the town-site and adjacent to the east channel
of the Mackenzie River (Figure 1).

5.   METHODS AND SOURCES OF DATA

5.1   The Field Site

Near the end of October 1973, thermal probes were emplaced
and representative soil samples obtained.

Three holes were drilled through the lagoon embankment to
a depth of 12 m for probes II, III and IV and one hole 61 m
deep was advanced 3.5 m from the downstream edge of the
embankment for probe V.

The cross-section of the embankment at the study-site and
the location of the bore-holes are shown in Figure 2. The
depths and relative positions of the temperature stations
are indicated in Figure 3. A further probe was also included,
labelled I in Figures 2 and 3, to obtain temperature data
from the upstream surface of the embankment and along the
bottom of the lagoon. In total, 44 temperature stations were
employed.

5.2   The Instruments

Probes II, III and IV consist of Atkins PR 99-3 thermistors
installed inside 2.54 cm diameter p.v.c. tubing filled with
zonolite. To facilitate transportation and ease of handling,
each probe was supplied in three sections with couplings
fitted so that the probes could be finally assembled on site
before insertion into the bore-holes. The two remaining
probes consist of similar thermistors attached to a flexible
p.v.c. cable reinforced by steel bracing wires.

Leads from the probes were channelled to termination boxes
on the sides of the embankment. A meter may be connected
to these boxes, each temperature station selected in turn,
and readings recorded weekly to the nearest 0.3°C.

5.3   The Samples

The holes were drilled using a Nodwell mounted Mayhew 100
drill-rig and variations of soil and groundwater conditions
were noted. Representative samples of the subsoils were
taken at intervals by pushing a 5 cm diameter split-spoon
or 7.5 cm diameter, thick-walled Shelby tubes into the perma-
frost. Densities and moisture contents of these samples
were determined in Inuvik. Samples of the 61 m deep test-
hole consisted primarily of disturbed air-returned material.

The soil samples recovered from the drilling operations were
subjected to standard laboratory classification procedures,
including particle size distribution by sieve analysis and
hydrometer tests, and Atterberg index property determinations.
Moisture contents were obtained for all samples. Wet density,
dry density and ice-content were obtained for the permafrost
samples.

5.4   Mathematical Modelling

Initial numerical and analytical calculations have been performed to simulate the average thermal conditions in the vicinity of the lagoon edge. These calculations are of the steady-state variety and, consequently, they do not include any transient behaviour. Further, because of insufficient data from the field at this stage, some of the thermal parameters are estimated using values representative of the Inuvik area.

The curve denoted by $0^{\circ}C$ in Figure 4 represents the extent of the thawing predicted near the lagoon edge using a simple explicit finite difference technique to solve numerically the partial differential equation which describes time-independent heat conduction (Laplace's equation). It was assumed that all cross-sections of the lagoon are identical, which reasonably implies there is negligable heat flow parallel to the lagoon edge, and reduces the problem to consideration of two-dimensions.

To facilitate the convergence to a steady-state solution, three consecutively finer grids simulating the embankment cross-section were utilised, culminating in a square lattice of 42x49 points, the geometry of which is shown in the insert to Figure 4.

The mean annual soil temperature was assumed to be $-4\,^{\circ}C$, a figure which was indicated from the preliminary readings from probe V and which is in general agreement with soil temperature data for the area (Brown, 1970).

The mean annual water bottom temperature in the lagoon was estimated to be $3.5^{\circ}C$, which is compatible with values for shallow water bodies in the region (Smith, 1972).

The ratio of the conductivities of the underlying silt and the gravel embankment, whose depth was approximated by the dotted lines in Figure 4, was assumed to be 0.67.

The bottom and left-side boundaries of the finite difference lattice were fixed as isothermals of $-4.0^{\circ}C$ at a distance equivalent to 36 m and 15 m, respectively, from the water-line on the embankment face, and the right-side boundary was set as an adiabatic. This latter boundary acted as a plane of symmetry and gave the lagoon an effective width of about 30 m. This is considerably smaller than the actual lagoon width, but this departure from reality, and also the imposition of the subsurface isothermal boundaries, produces negligible effects in the immediate vicinity of the embankment.

Simple analytical solutions to the steady-state heat flow equation, which approximate some configurations occurring in permafrost problems, are available in the literature.

(Gold and Lachenbruch, 1973). One such solution, the flow
of heat in a homogenous and semi-infinite solid with two
adjacent, straight-sided, semi-infinite isothermal surfaces
on the boundary, is included in Appendix 1. This simple
configuration is a crude approximation to the lagoon edge.

The straight line denoted by A in Figure 4 represents the
position of the thaw interface near the lagoon edge predicted
by the analytical solution. The boundary temperatures used
to obtain this line are the same as those utilized in the
numerical calculation described above, namely, $4.0^{o}C$ and
$3.5^{o}C$. In this case, these two isotherms are assumed to lie
along the horizontal line denoted as the X-axis in Figure 4,
and their point of separation is taken as 0, which is the
point on the X-axis vertically below the water-line at the
embankment.

Also included in Figure 4 is another line, B, which indicates
the predicted extent of the thaw utilizing the same boundary
conditions and analytical solution, but with the not unreasonable
assumption that the conductivities of the frozen and thawed
soils are in the ratio of 2 to 1. The necessary mathematical
details, verifying the generalization of the homogenous-
medium, steady-state solution to a medium of temperature
dependent conductivity, are included in Appendix 2.

The calculations described above are simple, preliminary
attempts intended to give some indication of the approximate
extent of the "average" thaw zone expected in the vicinity
of the lagoon embankment.

6.   RESULTS

6.1   Subsoil Conditions

The three holes drilled through the embankment indicated that
the gravel layer was 2.5 m deep beneath the higher upstream
section and approximately 1.25 m thick near the lower down-
stream toe. Below the gravel, a brown silt was present to
the bottom of each test hole. It was apparent that the
bottom portion of the gravel and approximately 0.6 m of the
silt deposit was unfrozen. In fact, sloughing from this
wet, unfrozen zone prevented sampling near the bottom of
the two holes closest to the lagoon. The hole adjacent
to the embankment indicated a 0.3 m topsoil cover above
the silt strata.

One of the recovered samples contained a 15 cm thick lens,
although most of the ice in the fine grain silt consisted
of visible horizontal layers varying from 1 - 13 mm in
thickness. Near the bottom of the test holes, the ground ice
was classified as non-visible, well bonded with excess ice.

6.2   Sample Classification and Soil Parameters

The major physical and thermal parameters for the recovered
soil samples are included in Table 2. Figures 5 and 6
also show curves summarizing the test hole logs for the
four holes and a plot of the variation of water content with
depth in the foundation soil.

The Inuvik silt deposit which comprises the majority of the
geologic sequence was classified as a low plastic silt
with a Unified Classification Symbol of ML. The Atterberg
liquid limit for the silt varied from 20.4% to 33.9% with
an average value of 25.6%. This average indicates that the
clay content is generally low and that the samples consisted
primarily of silts. Hydrometer analysis indicated that
the silt strata contained an average of 5% clay sizes with
a trace of sand and that the remainder consisted of silt.

Below the 30 m level the average liquid limit was 33.7% which
indicates that the strata contains a greater clay content.
A sample obtained from the 61 m level had a liquid limit of
42.4%, a clay content of 30% and was classified as an organic
clay of medium plasticity.

The range of dry densities and ice contents obtained, varying
from 0.64 g/cm^3 and 1.56 g/cm^3 and 42.0% to 78.6%, respectively,
are typical for the Inuvik area. In general, the sampling
indicated excess ice of approximately 70% near the original
ground surface and that the ice content decreased with depth.

6.3 Thermal Regime

At this time, the temperature readings have been collected for a period of four months.

The initial readings, as expected, indicated some transient effects created by the perturbation associated with drilling. In particular, those holes in which sloughing of wet material occurred from the unfrozen zone showed anomalous temperature variations for about two weeks after the probes were installed. A simple calculation indicates that this is approximately the time taken for the wet material to freeze at a lower level.

The temperature readings confirm the observation made during the drilling, that a thawed zone exists within and immediately beneath the embankment. The approximate extent of this zone during the early winter (November, 1973) is indicated by the cross-hatched region in Figure 4. Further readings collected to the middle of February, 1974, indicate that this thawed zone is still present, though it is diminishing in size.

Readings from probe V indicate that the rather shallow active layer on the downstream side of the berm was apparently completely frozen by the beginning of January, 1974. Temperatures from this deep probe for the last two months of 1973 and the first two months of 1974 are included in Figure 8, and the readings between 45 m and 60 m indicate that the permafrost table is approximately 75 m thick in this vicinity.

The long-term effect on the thermal regime beneath the oxidation pond embankment created by the nearby East Channel of the Mackenzie River has been estimated and the modifications to the temperature profile for probe V are shown in Figure 8. The contribution is negligible above a depth of 15 m, but in absence of the river channel the permafrost table in the vicinity of probe V would probably be 10 m thicker.

Extrapolation of the temperature readings between the depths of 20 m and 45 m indicates that the mean soil surface temperature is approximately $-4\,^{\circ}C$.

7.   DISCUSSION

Using the estimated surface and lagoon bottom mean temperatures
used previously, and averaging the thermal parameters in Table 1,
a one-dimensional thaw calculation (Nixon and McRoberts, 1973)
indicates that the depth of thaw beneath the centre of the
lagoon after almost two decades of operation will be approximate-
ly 6 m. The temperatures used in this calculation imply that
after centuries of operation the thaw bulb beneath the lagoon
would extend completely through the permafrost layer. Clearly,
the steady-state condition has not been reached in this region
beneath the lagoon. However, in the region of particular
interest, within the embankment and its immediate foundation
soils, the ground surface is relatively close and (periodic)
steady-state conditions should essentially prevail. This
implies that the thermal regime at the edge of the lagoon should
now be independent of initial transient effects, such as a
dependency on the particular time of the year when the
embankment construction took place. Of course, other time-
dependent effects are present because of random fluctuations
and periodic annual and diurnal ambient temperature variations.

The simple mathematical modelling described in section 5.4
ignores the important contributions from the periodic
temperature variations impressed on the boundary surfaces.
However, these calculations have been included to indicate
the "average" extent of the thaw zone in the vicinity of the
embankment and they imply that the majority of the soil within
and beneath the embankment should remain frozen.

In contrast, the temperature readings from the field show that
an unfrozen zone exists in the gravel of the embankment core
and extends into the underlying silts, at least, during the
first half of the winter of 1973-74. It is likely that this
thawed zone is caused by the periodic annual ambient temperature
variations which create a particularly deep active layer through
the gravel berm, by sensible heat transported via water seepage,
or by a combination of both these mechanisms. Although evidence
of excessive seepage through the embankment is not visibly ap-
parent in the immediate vicinity of the field site, seepage
icings of a considerable size were evident at the downstream
toe of the embankment in an area about 150 m west of the sewer
outfall during the early winter months of 1973 (Fig. 11).

8.   CONCLUSION

Initial temperature data indicate that during the first half
of the 1973-74 winter, at least, a thawed zone was present in
the core and the immediate foundation soils of the lagoon
embankment at Inuvik. Such a thawed zone is not predicted
by preliminary steady-state calculations. These calculations
indicate that a thawed zone should be limited to a small region
near the upstream toe of the embankment.

Clearly, to make a quantitative simulation of the thermal
regime within the embankment and foundation, it is necessary
to consider time-dependent boundary conditions and also,
possibly, the contribution to heat flow by seepage water.

The shallow thawed zone presently existing beneath the Inuvik
lagoon embankment is apparently created by the exclusive use
of gravel as a fill material in this case. Such a material
exhibits a high permeability in the thawed state, creating
the environmentally-damaging possibility of effluent leakage
and also the occurrence of further thawing caused by heat
transported by water movement. Further, the high thermal
conductivity of such a coarse fill material encourages the
undesirable development of a particularly deep active layer.

It seems likely that by an appropriate choice of fill materials,
and possibly the suitable use of heat insulating layers, it
may be possible to avoid the creation of similar undesirable,
unfrozen zones in the future construction of wastewater
impounding embankments in certain permafrost areas.

It remains necessary to continue temperature data collection
from the present site for a full cycle - one year. The
existing soil parameter data will be used in conjunction
with the surface temperature data from the site for input into
a model which will be used to simulate the time-dependent thermal
regime in the vicinity of the berm. This model will then be
used to interpret the processes at work in the present Inuvik
lagoon embankment.

9. IMPLICATIONS AND RECOMMENDATIONS

These preliminary findings indicate that the exclusive use
of coarse fill materials for the construction of waste water
impounding embankments for workcamps or permanent communities
in the North should not be encouraged because of the
environmentally-damaging high seepage rates associated with
such permeable materials. Further, coarse materials have
relatively high thermal conductivities, thereby increasing
the undesirable possibility of thawing the foundation soils;
a feature which is probably compounded by the sensible heat
supplied by seepage water.

It seems likely that the use of impermeable lining or grouting
materials may prove necessary to ensure containment of waste
water impounded by embankments of coarse fill materials.

Embankments constructed largely of fine-grained materials,
which generally have relatively low permeabilities and
conductivities, present an alternative approach. Seepage rates
may be minimized using such materials and the possibility of
maintaining a frozen foundation and embankment core are
increased. However, in the North, such borrow materials are
often obtained in the frozen state with a high ice content,
and any thawing may result in low shear strengths and in slope
stability problems. In such cases, it may be desirable to
thaw and partially consolidate the material prior to placement.
This will ensure that the water content of the embankment fill
approaches reasonable engineering standards.

REFERENCES

Bogoslovskiy, P.A., Veselov, V.A., Ukhov, S.B., Stotsenko, A.V. and Tsvid, A.A. (1963). "Dams in Permafrost Regions". Proceedings of the First International Conference on Permafrost, pp. 450-455.

Brown, R.J.E. (1970). "Permafrost in Canada". University of Toronto Press.

Brown, W.G. and Johnston, G.H. (1970). "Dikes on Permafrost: Predicting Thaw and Settlement". Canadian Geotechnical Journal, Vol. 7, No. 4, pp. 365-371.

Carslaw, H.S. and Jaeger, J.C. (1959). "Conduction of Heat in Solids". Oxford University Press, Second Edition.

Fulwider, C.W. (1973). "Thermal Regime in an Arctic Earthfill Dam". Proceedings of the Second International Conference on Permafrost, North American Contribution, pp. 622-628.

Gold, L.W. and Lachenbruch, A.H. (1973). "Thermal Conditions in Permafrost - A Review of North American Literature". Proceedings of the Second International Conference on Permafrost, North American Contribution, pp. 3-25.

Johnston, G.H. (1969) "Dykes on Permafrost, Kelsey Generating Station, Manitoba". Canadian Geotechnical Journal, Vol. 6, No. 6, pp. 139-157.

Kersten ,M.S. (1949). "Thermal Properties of Soils". University of Minnesota, Engineering Experiment Station Bulletin 28.

Mackay, J.R. (1963). "The Mackenzie Delta Area, N.W.T.". Geography Branch, Mines and Technical Survey, Ottawa, Memoir 8.

MacPherson, J.G.,Watson, G.H. and Koropatnick, A. (1970). "Dikes on Permafrost Foundations in Northern Manitoba". Canadian Geotechnical Journal, Vol. 7, No. 4, pp. 356-364.

Nixon, J.F. and McRoberts, E.C. (1973). "A Study of Some Factors Affecting the Thawing of Frozen Soils". Canadian Geotechnical Journal, Vol. 10, No. 3, pp. 439-452.

Roy, M., LaRochelle, P. and Anctil, C. (1973). "Stability of Dykes: Embankments at Mining Sites in the Yellowknife Area". North of 60, IAND Publication No. QS-3037-000-EE-A1.

Smith, M.W. (1972). "Observed and Predicted Ground Temperatures, Mackenzie Delta, N.W.T.". Mackenzie Delta Area Monograph, 22nd. International Geographical Congress, pp. 95-106.

APPENDIX 1

The steady-state temperature within a semi-infinite solid with
two isothermal regions separated by a straight line on the boundary
surface

Figure 7 presents a section which is perpendicular to the line
separating two isothermal surfaces at temperatures T_1 and T_2
imposed on the boundary of a semi-infinite solid of uniform
conductivity. The boundary is denoted by the continuation of
the line OX, with the point O representing the separation point
of the two isothermal regions and which is taken as the origin
of a set of cartesian coordinates as shown.

The set of steady-state isotherms on this diagram are represented
by straight lines passing through the point O. The equation
defining the temperature distribution is given by (Carslaw & Jaeger,
1959)

$$T(X,Y) = T_2 + (T_1 - T_2) \frac{\arctan (Y/X)}{\pi} \tag{A1.1}$$

$$= T_2 + (T_1 - T_2)(\theta/\pi), \tag{A1.2}$$

where θ is the angle between the line OX and the isotherm of
temperature T.

If the region within which $T < T_f (T \leqslant T_f \leqslant T_2)$, say, has conductivity
K_F and the remaining region where $T > T_f$ has conductivity K_T, then
in the solution (A1.1) or (A1.2) replace T and T_2 by T' and T'_2,
respectively. Here,

$$T' = \begin{cases} (K_T/K_F)(T-T_f) + T_f; & T > T_f \\ T & ; & T < T_f \end{cases} \tag{A1.3}$$

and

$$T'_2 = (K_T/K_F)(T_2-T_f) + T_f \tag{A1.4}$$

The verification of this transformation is included in Appendix 2.

APPENDIX 2

The solution to the steady-state heat flow between two isotherms in a medium when the conductivity is purely a function of the temperature

The diffusion equation which describes heat-conduction, in a three-dimensional medium of varying conductivity with no heat sources, may be written in cartesian co-ordinates as (Carslaw and Jaeger, 1959)

$$\frac{\partial}{\partial x}\left(K\frac{\partial T}{\partial x}\right) + \frac{\partial}{\partial y}\left(K\frac{\partial T}{\partial y}\right) + \frac{\partial}{\partial z}\left(K\frac{\partial T}{\partial z}\right) = \rho c \frac{\partial T}{\partial t} \quad . \quad (A2.1)$$

Here, ρ and c, respectively, represent the density and specific heat of the medium, K denotes thermal conductivity, and the partial derivative on the right-hand-side gives the variation of temperature with time. Specializing to the steady flow of heat in a region with time-independent boundary conditions, the partial derivative with respect to time makes no contribution and the equation becomes in more compact notation,

$$\text{div K grad T} = 0 \quad . \qquad (A2.2)$$

Here, div and grad denote, respectively, the divergence and gradient operations of vector analysis.

When the thermal conductivity is purely a function of temperature (A2.2) may be rewritten as

$$\text{div.grad } T' = \nabla^2 T' = 0 \quad , \qquad (A2.3)$$

which is of the form for describing time-independent, steady-state heat flow in a medium of constant conductivity (Laplace's equation). In (A2.3), we have

$$T' = T_1 + \frac{1}{K_1} \int_{T_1}^{T} K \, dT, \qquad (A2.4)$$

where K_1 is the conductivity when $T = T_1$, the lowest boundary temperature. In appendix 1, the temperature variation assumed for K is

$$K = K_F + (K_T - K_F) H(T - T_f) \qquad (A2.5)$$

where, in this case, K_T and K_F represent the thermal conduct-
ivities of thawed and frozen soil, respectively, and T_f denotes
the freezing temperature. In (A2.5), $H(T-T_f)$ is the Heaviside
step-function, given by:

$$H(T-T_f) = \begin{cases} 0 & T < T_f \\ \\ 1 & T > T_f \end{cases}$$

$$(A2.6)$$

Solving (A2.3) with the boundary conditions prescribed in
Appendix 1 recovers (A2.1) or (A2.2) and substituting (A2.5)
into (A2.4) generates the transformation given by (A1.3) and
(A1.4).

APPENDIX 3

TABLES & FIGURES

Table 1: PHYSICAL AND THERMAL SOIL PARAMETERS

Test Hole Probe No.	Hole Depth (m)	Effective Depth (m)	ρ_w (g/cm^3)	ρ_d (g/cm^3)	w (%)	V_I/V (%)	K_T (mcal/ s cm 6C)	c_F (cal/ cm3 oC)	c_T (cal/ cm3 oC)	L (cal/cm^3)
IV	1.5	0.3	1.39	0.64	115.5	75.9	0.15	0.50	0.87	53.6
III	2.7	0.6	1.68	1.16	44.5	56.8	0.25	0.49	0.75	37.2
III	3.0	0.9	1.94	0.76	153.5	71.4	0.15	0.74	1.33	84.4
V	1.2	1.2	1.36	0.57	139.4	78.6	0.15	0.51	0.91	57.2
IV	3.6	2.4	1.76	1.20	47.2	55.1	0.25	0.52	0.81	40.8
II	5.2	2.7	1.76	1.27	38.3	52.4	0.29	0.50	0.74	35.1
V	2.7	2.7	1.82	1.28	43.1	52.2	0.27	0.53	0.80	39.6
V	4.9	4.9	1.79	1.22	45.9	54.1	0.25	0.53	0.81	40.4
II	7.9	5.5	2.00	1.49	34.3	44.3	0.31	0.55	0.81	36.8
IV	9.1	7.9	1.97	1.53	28.5	42.6	0.34	0.52	0.74	31.4
IV	10.7	9.4	1.98	1.56	26.6	42.0	0.36	0.52	0.73	29.9

LEGEND FOR TABLE 1

The effective depth shown in Column 3 represents the depth below the top of the foundation soil.

ρ_w = wet density

ρ_d = dry density

w = water content as a percent of dry unit weight

V_I/V = volumetric ice content as a percent of total volume

K_F = conductivity of frozen soil

K_T = conductivity of thawed soil

C_F = volumetric heat capacity of frozen soil

C_T = volumetric heat capacity of thawed soil

L = volumetric latent heat of soil

The conductivities given in table 2 are evaluated using the data of Kersten (1949). The frozen soil conductivity for all the samples collected is 0.52 mcal/s cm °C (Nixon and McRoberts, 1973).

The volumetric heat capacities and latent heats were evaluated using the relations given by Nixon and McRoberts (1973) and, for the latter parameters, assuming that 10% by mass of the total water content was unfrozen.

LEGENDS FOR FIGURES

Figure 1   Plan of the sewage lagoon at Inuvik, N.W.T.,
              indicating the location of the field study.

Figure 2   Plan of the study site at the lagoon embankment
              at Inuvik, N.W.T., indicating the positions of
              the thermal probes.

Figure 3   Cross-section of the embankment at the study
              site indicating the positions of the temperature
              stations.

Figure 4   Cross-section of the embankment at the field site
              indicating various thaw boundaries. The cross-
              hatched region indicates the approximate extent
              of the thawed zone within the gravel embankment,
              whose extent is represented by the dotted lines,
              and foundation soils during the early winter
              (November) of 1973. The curve denoted by 0^{o}C
              represents the extent of the thawing predicted
              by an explicit finite-difference numerical solution
              to the steady-state heat flow problem. The line
              A indicates the position of the thaw interface
              predicted using the analytical solution for the
              steady-state heat flow in a homogenous, semi-
              infinite solid beneath a straight boundary between
              two isothermal surfaces. The line B is derived
              in the same manner as line A, but assuming the
              ratio of the frozen to thawed soil conductivities
              is 2. The insert indicates the finite difference
              grid utilized in the numerical simulation.

Figure 5   Soil Gradation Curves. The cross-hatched area
              denoted by A represents the range of gradation
              curves for seven samples collected from the four
              bore holes at various depths between 8 and 26 feet.
              Curve B is the gradation curve for an air-returned
              sample recovered from hole V from a depth of 200 feet.

Figure 6   The variations of water content with depth in the
              four bore holes. The effective depth represents
              the depth in the foundation soil i.e. the actual
              depth minus the embankment thickness.

Figure 7   Schematic representation of the lagoon edge used
              for the steady-state, analytical heat flow
              calculation in Appendix 1.

Figure 8   Temperature readings from probe V. The mean
              monthly temperature variation with depth for
              November, December, 1973 and January, February,
              1974. The geothermal gradient between 20 m and
              45 m indicates a mean annual surface temperature of

approximately -4°C.   The contribution to the
temperature profile from the East Channel of
the Mackenzie River is indicated.

Figure 9   The Nodwell mounted Mayhew rig drilling through
the Inuvik embankment. Probe I was lowered
through the cut in the ice in the foreground.

Figure 10   The Inuvik lagoon embankment, looking NW, showing
the completed termination boxes on both sides of
the embankment.

Figure 11   An extensive seepage icing at the end of October
1973, near the downstream toe of the Inuvik lagoon
embankment in an area about 500 ft. NW of the sewer
outfall.

FIGURE 1 PLAN OF INUVIK LAGOON

Scale: 1 cm. = 48 m.

LAGOON

AIRSTRIP

EAST

CHANNEL

MACKENZIE

RIVER

A — A' INSTRUMENT LINE

SEWER OUTFALL

FIGURE 2 PLAN OF STUDY SITE

FIGURE 3. LOCATIONS OF THE TEMPERATURE STATIONS

FIGURE 4 THAW BOUNDARIES IN THE INUVIK LAGOON EMBANKMENT

INSERT: THE BOUNDARIES FOR THE FINITE DIFFERENCE NUMERICAL CALCULATION

FIGURE 5   GRADATION CURVES

FIGURE 6   WATER CONTENT Vs. EFFECTIVE DEPTH

FIGURE 7 SCHEMATIC REPRESENTATION OF THE LAGOON EDGE

# FIGURE 8 TEMPERATURE READINGS FROM PROBE V

Fig. 9 The Nodwell mounted Mayhew rig drilling
        through the Inuvik embankment. Probe I
        was lowered through the cut in the ice in
        the foreground.

Fig.10 The termination box on the upstream side of the
        embankment.

Fig. 11   An extensive seepage icing at the end
          of October 1973, near the downstream
          toe of the Inuvik lagoon embankment
          in an area about 150 m NW of the sewer
          outfall.

TABLE OF CONTENTS

LIST OF TABLES

LIST OF FIGURES

TERMS OF REFERENCE

A contract was signed on October 15, 1973, between the Environmental Protection Service and the University of Toronto to carry out the following work:

1. To prepare a preliminary report on alternatives for disposal of concentrated human wastes collected in 'honeybags', from future collection systems, such as vacuum sewers or pressure sewers, and sludge from treatment plants. Proposals for detailed work on possible solutions are to be included. The solids handling problem as well as final disposal problem is to be investigated.

2. To carry out a laboratory investigation on disposal of human waste in permafrost. Several physical-chemical and microbiological parameters will be monitored on the decomposition taking place in laboratory reactors designed to simulate a sludge pit - anaerobic digestor under low temperature conditions. Waste will be selected to simulate contents of 'honey-bags'.

Reports were to be submitted by April 15, 1974. It was the clear understanding of both parties involved that this investigation will extend over several years, and that only preliminary results can be expected after a few months of work. I was assisted in the study by Mr. Durga Prasad, M.Sc., Technologist, and Mr. Mohammed Elamin, B.A.Sc., Graduate Student, whose conscientious work is acknowledged.

The report is arranged to briefly state the nature of the problem and to summarize the findings to date. Where possible at this time recommendations are made. Item 1 is reported on in Part I Collection and Disposal Systems for Concentrated Wastes and item 2 in Part II Laboratory Investigation of Decomposition of Human Wastes in Permafrost.

STATEMENT OF THE PROBLEM

Many communities in the Northwest Territories and the Yukon Territories rely on trucked supply of water and pick-up of human waste. The high capital cost of conventional water and gravity sewer systems and limited funds necessitate the continued use of trucked systems for many years, particularly in the smaller settlements in permafrost regions. Bucket toilets, with or without the use of chemicals, are widely used. Their contents, in plastic bags ('honey-bags'), are picked up several times a week and trucked to dumps, sludge pits, or dumped into lagoons, the previous practice of disposal to the sea or on ice being no longer permitted. Water flush toilets are also in wide use. They include the conventional 3-5 gallon flush toilet and also low water usage toilets, of which the 'Flush-O-Matic' unit, using one quart of water per flush, is an example. These require connection to a storage tank in the home which is generally pumped out once a week. Normally, other household liquid wastes from kitchen sinks, bathtubs and laundry are not connected to the holding tank. Therefore, sewage from holding tanks is more dilute than contents of 'honey-bags', but still generally more concentrated than sewage in a gravity sewer system. There are several installations of self-contained toilets, such as incinerating toilets and chemical recirculating toilets, but they are not in widespread use.

The elimination of the use of 'honey-bags' would be a very important improvement in the living conditions of northern communities by contributing to a reduction in waste-borne diseases. Proper treatment and disposal methods for contents of 'honey-bags' are therefore probably only required for the next ten to twenty years. However, promising methods of piped collection of concentrated wastes are now being tested for use in northern communities. They include vacuum sewer and pressure sewer systems. Both require only small quantities of water for transport of solids. In addition, trucking of sewage from holding tanks will continue to be used. There is, therefore, a long-term need for treatment and disposal processes for wastes which are much more concentrated than domestic sewage transported by gravity. Since much of the process and cost of conventional sewage treatment lies in concentrating solids from dilute sewage, the advantage of receiving relatively undiluted waste for treatment is obvious. In addition, treatment and disposal of sludges from conventional sewage treatment plants, which will be built in communities served by gravity sewers, will require methods applicable for northern conditions. Finally, joint treatment of refuse, human waste and sludge is a possibility. The task, therefore, is to search out and test promising methods of collection and treatment for concentrated wastes to ensure their safe disposal to the environment.

SUMMARY AND RECOMMENDATIONS

It must be emphasized that the scope and resources for this report were very limited and that the recommendations are only preliminary. They are expected to be revised and enlarged upon in subsequent work. Because of the closeness of topics of Part I and II, necessitating some overlap, the summary and recommendations are presented together at the beginning of the report.

1. Concentrated Human Wastes include ' honey-bag' wastes, holding tank wastes, black water from vacuum sewers and pressure sewer wastes, and sludges from sewage treatment plants. There is limited information available in the North American literature on quantities and strength of these wastes. A preliminary search of Japanese literature on night soil and Swedish literature on black water and grey water from vacuum sewers has provided limited data on quantity and strength of these wastes. Studies on human waste quantities and strengths carried out under this contract agree reasonably well with the literature values.

    Recommendation 1: It is recommended that a thorough search of Japanese, Indian and other Asian literature be carried out regarding concentrated human wastes and their disposal. Work should be carried out to provide Canadian comparison. On pilot projects for vacuum and pressure sewers monitoring of quantity and strength of waste should be done.

2. Collection Systems

    The presently-used collection systems for concentrated wastes are mainly the trucked 'honey-bag' system and a trucked system for holding tank wastes. The elimination of the 'honey-bag' system in most communities would be a large step forward in improving living conditions in northern communities. Trucking of large quantities of holding tank wastes is expensive. Both systems will, however, continue to be used for many years in the smaller settlements, due to a lack of capital funds and local conditions. The vacuum sewer and pressure sewer systems are attractive alternatives to collect concentrated wastes. They avoid the need of excessive dilution of wastes required for transport in gravity sewers. Very recently, pilot tests on vacuum sewer and pressure sewer systems, adapted to northern conditions, have been started. There are many advantages in using the new systems. Their ability

to operate satisfactorily in northern communities
has to be proven, but I am confident of their
success, where local conditions make their use
sensible.

*Recommendation 2: It is recommended that pilot
plant work under way on vacuum sewers and pressure
sewers be increased substantially to obtain proof
of their ability to function under northern climates
and operating conditions. Close contact with similar
work under way in Alaska is recommended to avoid
unnecessary duplication of efforts.*

3.   Treatment and Disposal Systems

Present methods of disposal of 'honey-bag' wastes
include the open dump, together or separate from
garbage and refuse, sludge pits and lagoons. They
leave much to be desired from many points of view.
Adequate treatment methods for these concentrated
human wastes are required for those communities
that will continue to use the 'honey-bag' system for
many years. The use of vacuum sewers and pressure
sewers brings about the need for adequate treatment
methods for these wastes, which will be more dilute
than 'honey-bag' wastes, but much more concentrated
than normal domestic sewage. Treatment and disposal
processes include long-term storage, anaerobic
digestion, lime precipitation, incineration and aerobic
digestion.

*Recommendation 3: It is recommended that a pilot
project on 'honey-bag' disposal station similar to
the Greenland type be started immediately in at least
one northern community. It is further recommended
that research efforts on adequate treatment methods
for concentrated wastes from 'honey-bag' and vacuum
and pressure sewer systems be increased substantially.
Funds should be set aside as soon as possible to
permit construction of several pilot projects as soon
as laboratory research has advanced sufficiently.*

4.   Disposal of Human Wastes in Permafrost

One common method of disposal of 'honey-bag' wastes
is to store them in pits, excavated in permafrost,
which are covered with soil when full. Little or no
information is available on any long-term decomposi-
tion of wastes and on the acceptability of this method
for health and ecological safety. A simulated sludge

pit has been set up in the laboratory (see Part II).
It is operated at -5°C. Measurements of physical,
chemical and bacteriological parameters have been
made weekly for the past three months. Data to
date are too sparse and taken over far too short
a time to draw any conclusions. They indicate so
far that no measurable decomposition takes place in
the pit, and that bacterial counts are drastically
reduced from feed values due to freezing. Data on
survival rates of pathogenic organisms are incon-
clusive so far.

*Recommendation 4: It is recommended that the sludge
pit be continued to operate for at least one year, if
not longer, and that measurements now taken be continued.
The frequency of sampling can be decreased to once per
month. Temperature should be raised to about +5°C.
for about three months to simulate summer conditions.*

5.   Anaerobic Digestion

Anaerobic digestion, a process widely occurring in
nature, is a biological process in which complex
organic matter is converted to methane and carbon
dioxide in the absence of oxygen, thus decomposing
organic waste. It will come about naturally in the
storage of concentrated human waste. Heat is produced
in the process. It can be made to work much more
efficiently in an engineered reactor, where environmental
conditions such as temperature, pH, mixing, etc., are
controlled. The liquid effluent from such a reactor
will require further treatment, most likely of a
physical-chemical form, before discharge to the environ-
ment. Some further treatment and ultimate disposal of
sludge is also a necessity.

*Recommendation 5: It is recommended that current labora-
tory studies (see Part II) on anaerobic digestion under
low temperature conditions be continued with the objective
of establishing design criteria and operating conditions
for future installations. Pilot plant studies in a
northern community will be required once laboratory
studies are completed. This should be carried out for
concentrated wastes, such as 'honey-bag' wastes, as well
as for more dilute wastes from vacuum and pressure sewer
systems. Work on possible treatment methods for the
supernatant and sludges are to be included. The possible
effect of the use of chemical inhibitors in the 'honey-
bag' system on anaerobic digestion should be studied.*

I-1   CONCENTRATED HUMAN WASTES

1.1   DEFINITION:

For the purpose of this report the term 'concentrated wastes' shall include the following:

- Human waste, faeces and urine, from bucket toilets normally collected in plastic bags, called 'honey bags'. These wastes will be referred to from now on as *'honey bag' wastes.*

- Human waste, faeces and urine, from low water usage toilets connected to holding tanks in the house. These wastes will be referred to from now on as *holding tank wastes.*

- Human waste, faeces and urine, from vacuum toilets normally connected to a vacuum holding tank at the house or to a vacuum sewer system. These wastes will be referred to from now on as *black water.*

- Human waste, faeces and urine, from toilets used in conjunction with a pressure sewer system. These wastes will be referred to from now on as *pressure sewer wastes.*

- Sludge from sewage treatment plants.

In addition to these toilet wastes, household liquid wastes are generated from kitchen, bathroom tub and sink, laundry, etc. They are not included in concentrated wastes, but will require discussion in the report. They are referred to as *liquid wastes* or as *grey water wastes* (for vacuum sewers only). Garbage, refuse and other solid wastes are referred to as *solid wastes.*

1.2   QUANTITIES AND CHARACTERISTICS OF HUMAN WASTES:

Human body wastes (faeces and urine) are excreted in quantities varying with age, sex, and the diet. Fecal matter contains food residues, the remains of bile and intestinal secretions, cellular substances from the alimentary tract, and microbial flora (Fair *et al*, 1968). Various authorities claim that, on an ordinary mixed diet, the daily fecal excretion by an adult male will aggregate 110-170 g. with a solid content ranging between 25 and 45 g.; the fecal discharge of such an individual upon a vegetable diet will be much greater and may even be as great as 350 g. and possess a solid content of 75 g. (Hawk *et al*, 1937).

The volume of urine excreted by normal individuals during any definite period fluctuates within very wide limits. The average normal excretions of urine fall within the range of 1000 to 2000 ml. The volume excreted is influenced greatly by the diet, particularly by the ingestion of fluids, and by the ambient temperature which affects not only fluid intake but also loss of water through perspiration (Hawk *et al*, 1937; Spector, 1956).

The moisture content of fresh excrement changes with the type of diet and environmental temperature. Evaporation of water may occur under certain conditions. Little information is available on the characteristics of human body waste in the North American Sanitary Engineering literature. However, medical literature contains considerable information, but unfortunately the information is reported in different units suited to medical fields and comparable parameters are not collected in all studies. Physical and chemical characteristics of human body waste taken mainly from medical literature, calculated and converted to units used in sanitary engineering field are listed in Table I.

Some information is available on the characteristics of human body waste (night soil) from Japan, where night soil collection is the most common domestic waste disposal system. In Japan, night soil accumulates at a rate of 1.0 - 1.1 litres per day per person, compared to values of about 1.3 - 1.5 litres per day per person in Canada and U.S.A. It is a mixture of faeces and urine which, during storage in the privy vault, has undergone putrefaction to some extent (Ikeda, 1972, and Iwai *et al*, 1962). Table II shows some characteristics of Japanese night soil. Comparing the strength of the human waste reported and indicated in Table I and II, the strength of the waste reported from Japan, appears to be less than half of that of North American waste. This can perhaps be attributed to the diets, body size and other factors mentioned earlier. Further literature search in Asian journals during the next year may provide additional information.

1.3 HOLDING TANK WASTES AND BLACK WATER WASTES:

Low water usage type toilets and vacuum toilets require about 1 quart (or litre) of water for rinsing purposes. With the assumption of an average of 7-8 flushings per person per day the total volume of holding tank wastes or black water wastes generated can be estimated as 1.3 litres of faeces and urine and 7.5 litres of rinsing water, or approximately 9 litres

TABLE I

VOLUME AND CHARACTERISTICS OF HUMAN BODY WASTE

(Values are expressed in units shown/adult/day except for pH)

	Volume in Litres	Total Solids gm.	BOD gm.	Total Nitrogen Load gm.	Total Phosphorus Load gm.	pH
Urine	1.16	56.0	--	12.2	1.1	(4 to 8) 6.0
Faeces	0.14	26.0	--	1.5	0.4	(7.0 to 7.5)
Total	1.3	82.0	64.0	13.7	1.5	
Reference	Spector, 1937	Spector, 1937	Spector, 1937	Painter & Viney, 1959	Fair et al, 1968, and Hawk, 1937	Hawk et al, 1937

TABLE II

CHARACTERISTICS OF HUMAN BODY WASTE (NIGHT SOIL) FROM JAPAN

Reference	pH	Total-N mg/l	NH4-N mg/l	Total Solids gm/l	Sus-pended Solids gm/l	Volatile Solids gm/l	COD gm/l	BOD gm/l	Calorific Value Kcal/l.
Ikeda 1972	8.5	--	3,471	30.1	12.0	17.6	--	10.19	--
Iwai et al, 1962	8.5	--	--	31.5	--	20.4	37.8	12.8	107.5

(or 2 gal.) per person per day, with a maximum of
about 50% more.* This assumes that household liquid
wastes are not connected to the holding tank or a
vacuum sewer system. They could account for 20-120
litres (5 to 30 gal.) per person per day, depending
on the sophistication of the water supply system.

As a comparison Olsson, Karlgren and Tullander
(1968) have estimated volumes of black water of 8.5
litres/person/day and grey water of 120 litres/person/
day for Swedish practice.

Waste production with conventional 3-5 gal. water
closets and all liquid wastes discharged to the
gravity sewer system average about 40-60 gal./person/
day, of which about half is contributed by toilet
flushing. A comparison indicates that the use of low
water usage toilets or vacuum toilets results in a
volume of highly polluted wastes of about 5% of wastes
produced in a conventional system, and in relatively
unpolluted liquid wastes of about 50% volume compared
to that of a conventional system.

Olsson, Karlgren and Tullander (1968) provide
extensive information on physical-chemical and bacter-
iological parameters on black water and grey water in
Sweden. A few selected parameters are given in Table
III. As a comparison data are presented from work
done in this contract on concentrated wastes (from
Table V) and to literature averages on concentrated
wastes (from Table I).

---

*   Cadario and Heinke (1972) reported water consumptions
      varying from 1 to 5 gallons (4 to 20 litres) per
      person per day for communities in the Northwest
      Territories on holding tank systems with the lower
      figures predominating.

TABLE III

CHARACTERISTICS OF BLACK WATER AND GREY WATER

Parameter	Units	BLACK WATER			GREY WATER	
		Olsson *et al*	Calc.* from this Report (Table V)	Calc. from* Literature (Table I)	Olsson *et al*	This Report
Volume	l/person/day	8.5	8.8	7.8	120	--
	gal/ " / "	1.9	2	1.7	27	--
BOD_5	mg/l	2317	-	-	203	--
COD	mg/l	8500	20,000	11,900	408	--
Solids-Total	mg/l	6250	13,600	9,300	666	--
Phosphorus	mg/l P	190	190	170	19	--
Nitrogen	mg/l N	1280	1,360	1,590	9	--

*   On assumption of a dilution of 1.3 litres of faeces and urine by 7.5 litres of water.

Agreement of most parameters is quite reasonable. Higher solids and COD values of results of this report compared to literature are noted.

Pressure sewer wastes are expected to produce volumes and strength of about the same quantities as for vacuum sewer systems. No accurate information on solid waste quantities in northern communities is available. Quali- tative statements are given in several reports that, in native homes, very small quantities of garbage and refuse are accumulated, with very few combustible materials, that in white homes quantities are larger and contain more combustible material, particularly in construction camps and military installations, where quantities may be higher per person than in southern communities. All report higher accumulations of scrap, machine parts, abandoned equipment and the ever-present oil drum than in comparable southern communities. There is a need for quantitative information on amounts and character of gar- bage and refuse in northern communities and camps.

I-2   COLLECTION SYSTEMS

2.1   GENERAL:

Hanks (1967) has conducted an exhaustive literature study on the relationship of solid wastes (including human wastes) and disease. While the literature failed to permit a quantitative estimate of any solid waste/ disease relationship, he had this to say in summary:

"The communicable diseases most incriminated are those whose agents are found in fecal wastes - particularly human fecal wastes. Where these wastes are not disposed of in a sanitary manner, the morbidity and mortality rates from fecal-borne diseases in the popu- lation are high. Despite the fact that other factors are known to contribute to some reduc- tion of these rates, the inescapable conclusion is that the continued presence in the environ- ment of the wastes themselves is the basic causative factor. Therefore transmission -- whether by direct contact vector transfer, or indirect contact -- is due to environmental contamination by these wastes."

I cannot think of any place in North America where this statement applies more than in most of our northern communities. There is a lack of conclusive data of solid waste/disease relationship in our northern commun- ities, but the problem is there.

2.2   TRUCKED 'HONEY-BAG' SYSTEM:

Health officials recommend that 'honey-bags' be collected from all households daily; in addition, this assists the collection procedure since a half-full bag is less likely to break. Daily collection, however, is the exception rather than the rule.

There are three methods of 'honey-bag' collection:

1.   collection from 45-gallon drums in front of each household, with or without the garbage;

2.   collection from the bathroom of each household;

3.   collection from the service porch of each household ("2-bucket" system).

1.   The householder is supposed to remove the 'honey-bag' from the bucket toilet and place the sealed bag in a 45-gallon drum (used especially for this purpose) in front of his home. Often, the bag is left on the ground, where it is broken by birds, dogs, or children, or where it can freeze to the ground in winter. The presence of 'honey-bags' lying around the settlement is aesthetically unpleasant. If broken, they constitute a danger to health. Removal of 'honey-bag' debris is unpleasant, inconvenient, and difficult. Handling, first by the householder, and then again by the collector, increases the possibility of breakage.

2.   A system of in-house collection of 'honey-bags' from the bathroom has been implemented in Cambridge Bay, Arctic Bay, and Frobisher Bay. The 'honey-bag' collector enters the house and removes the 'honey-bag' and pail to the truck. After dumping, a new bag is placed in the pail and the pail is returned to the bathroom. The system is advantageous in that handling of the 'honey-bag' only once by the collector minimizes the chance of breakage. It is convenient to the householder, requiring no conscious actions on his part. 'Honey-bags' are not left around the roads of the settlement where they may be broken. Residents in Cambridge Bay have objected strongly that collection from the bathroom is a serious inconvenience, dirties up the house, and invades their privacy, and about their not having been consulted before the system was placed in operation. The in-house system is somewhat expensive; charges are $2.00 per bag in Cambridge Bay and $1.60 per bag in Frobisher Bay, compared to 40¢ per pickup from drums on the street in Rae.

3.   A variant of the in-house from the bathroom collection system is the service porch or "2-bucket" system. Each household has two plastic pails for its toilet. Each morning, the householder ties the top of the bag and places the plastic pail and full bag in the service porch for collection. The second pail, with an empty unused plastic bag inside, is placed in the toilet for use. The collector removes the used bag from the pail and replaces it with a fresh bag. The pail is left on the service porch for use the next day, and the "full" honey-bag is taken to the collection vehicle for disposal. The "2-bucket" system is advantageous in that it minimizes handling of the bag, is clean, and does not leave 'honey-bags' lying around the settlement. The major objection to the in-house system - the invasion of privacy - is not present. The "2-bucket" system requires that all homes have two plastic toilet pails.

There are two methods of 'honey-bag' transport
systems. The first system consists of a large flat
holding tank with a dumping "ripper chute" with spikes
on the interior connected by a chute, and gravity
ejection door. The full 'honey-bag' is placed in the
ripper chute by the driver and broken on the spikes by
an upward hand motion. The contents flow or are sucked
into the holding tank, and the ripped bag is placed in
a 45-gallon drum especially for this purpose for stor-
age before disposal. In the second system, 'honey-bags'
are placed in 45-gallon drums on the back of a tractor-
driven cart or pickup truck. The drums with their
contents are dumped at the disposal area and re-used.
If the necessary equipment can be made available, the
use of a ripper chute is recommended.

2.3 TRUCKED SYSTEM FOR HOLDING TANK WASTES:

An alternative to the 'honey-bag' system without
going to the expensive piped sewer system is as follows:

Each house has a flat, 250-gallon sewage holding
tank installed under an insulated, raised floor in the
bathroom. The toilet is mounted directly above. A small
amount of water is added for flushing and cleaning by
hand ladling. The kitchen sink may also be connected by
a pipe to the holding tank. An exterior connection would
permit weekly emptying by a vacuum pump collection system
similar to that already used on a Nodwell RN75 oil-sewage
tanker. A flapper valve between the toilets and the tank
reduces odour. The tank must be well insulated to prevent
freezing, since, in cold weather, the contents of an
insulated tank may freeze and with vacuum extraction,
the thin-wall discharge piping may collapse during pump-
out.

The capacity provided by a 250-gallon tank is more
than adequate for the present weekly output of liquid
sewage from an "average household", and adequate for a
great increase in water-use habits from the present 1-5
gallon/person/day. In settlements with heavy snow which
may block roads and prevent reliable pumpout in winter,
this extra capacity is especially important.

Cost data on such an alternative are scarce.
Associated Engineering Services Limited (1973) have
estimated for Fort McPherson that the capital cost re-
quired to install sewage holding tanks and econoflush
toilets would be $600 per household. Extensions of
gravel pads, where necessary, to permit truck access was
estimated at $500 per household. Amortization of $1,100
per household over 20 years at 7-1/2% interest would be
about $100 per year, or $20 per person per year, based
on an occupancy of 5 people per household. The unit cost

of sewage pumpout (excluding cost of water supplied)
was assumed at 2¢ per gallon. At their assumed water
consumption of 14 gallons per person per day, the
annual operating cost per person per year was $91.00.

On the other hand, Fred Ross and Associates of
Cambridge Bay, proposed (Cadario and Heinke (1972))
that the implementation of such a system in Cambridge
Bay, with the weekly pumpout of toilet wastes from
60-gallon tanks, would result in a large saving on a
long-term contract for labour costs, which would off-
set the required investment in equipment and facilities.
They were apparently prepared to assume all capital
costs of such a proposal if they could obtain a long-
term contract (5 years) at the same cost now charged
for the 'honey-bag' disposal system. However, winter
conditions (1971-72) made pumpout unreliable and many
of the small capacity tanks overflowed.

The advantages of a system of sewage holding tanks
and econoflush toilets are their greater convenience
and better hygiene to householders and collectors, and
the possible elimination of spillage of other liquid
wastes on the ground. The disadvantage is that capital
investment is required, which is mostly lost, if in
the future utilidors are installed. Serious considera-
tion should be given to such a system as a means to
eliminate the 'honey-bag' system in those communities,
where for whatever reason it is not likely that a
utilidor system will be installed for many years.

In most settlements using 'honey-bags' for toilet
wastes, kitchen and laundry wastewater is disposed of
by pipe to the ground surrounding the house. With
proper drainage and ground conditions, this is adequate
as a short-term measure. However, in the long run,
another more sanitary means of disposal must be found.
Some public health officials feel that this contributes
to the occurrence of skin diseases, particularly in
children. In addition, it often creates serious
inconvenience to householders in the spring when houses
often sit "in the middle of a lake".

As soon as tanks are used for toilet wastes, it is
recommended that the kitchen sink be connected to the
tank for disposal of at least kitchen sink wastes. The
tank should be of adequate size for this purpose, and
pumpout should be frequent enough to prevent overflow.

2.4 VACUUM SEWERS:

A vacuum sewer uses air pressure instead of gravity
as the driving force for wastewater transport. Waste-
water is moved in plugs, separated by air gaps, at
high velocities through small diameter pipes. The

pressure differential of about one-half atmosphere
is created by a central vacuum pump. Specially
designed vacuum toilets, valves and a central col-
lection tank complete the system. The advantages
of a vacuum sewer system over a conventional gravity
system are its ability to transport wastewater
horizontally and to a certain extent upgrade, its
much lower water useage and, therefore, its more
concentrated characteristic, and its lower capital
cost. However, length, capacity and lift potential
of vacuum sewers are limited by the available pressure
differential, which precludes their use in many cases.
Averill and Heinke (1973) have provided an extensive
review of the system. Pilot installations in arctic
regions are now being tested in Alaska (Ryan *et al*,
1972) and may soon be tested in Canada through the
Department of the Environment.

In my opinion, vacuum sewer systems will find a
sizeable market in northern communities and construc-
tion camps. Blackwater (toilet waste only) systems,
possibly with connections to include kitchen wastes,
are most likely to be constructed where discharge of
liquid wastes from bathtubs, laundry, and sinks directly
to open ditches, can be tolerated. In other areas
these liquid wastes may also need to be conveyed to a
treatment facility, either by a greywater vacuum system
or by a one-pipe vacuum system. There is, therefore,
a need for treatment methods for concentrated wastes
(blackwater) as well as more dilute wastes from vacuum
sewers.

2.5 PRESSURE SEWERS:

In pressure sewer systems wastes are pumped from
the buildings into a pressure main, which continually
circulates the wastewater to prevent freezing. Pressure
piping can follow the contours of the terrain, and re-
quires smaller diameter piping than gravity sewers.
Ahead of the pump at the household a grinding device or
a settling tank may be used to prevent blockage of
pipes and pumps. An experimental pressure sewer system
is installed in a utilidor to serve ten houses at
Frobisher Bay, N.W.T. (Heinke (1974), Cooper (1968)).
The sewage from the houses is pumped into the circulat-
ing sewer line from settling tanks installed under-
ground behind each house. This system was installed in
1967, and although still operating, has required consider-
able maintenance. I am aware of proposals to install
pressure sewers in several northern communities, among
them Tuktoyaktuk, but do not know if any have been con-
structed recently.

2.6   REFUSE COLLECTION SYSTEMS:

Heinke (1973b) reports on refuse collection and disposal methods in the Northwest Territories:

Storage of garbage and refuse at the house is most commonly achieved in the readily available 45-gallon drums. They are, however, difficult to lift by hand. In some communities special raised wooden platforms have been constructed. This has generally been a failure since they are often not used and if used, become an eyesore since they are often not cleaned and covered with much spillage. On the other hand, the 15-gallon metal garbage pails are lighter, but are more easily blown over by wind and do not have the capacity to hold large animal carcasses and other larger types of refuse. Burning of paper and other combustible material at the home garbage drum is usually practised for bulk reduc- tion. Plastic containers are used in some communities, but break in cold weather. In cold weather, garbage will also freeze to the container, making it difficult for the collecting crew to empty them. Paper or plastic garbage sacks have been used recently with somewhat better success. However, if they are put on the ground they will freeze to the ground, with resulting breakage during collection. In some communities special holders fitted with a cover and the sacks hanging free have been used successfully. In spite of organized storage and collection facilities, the appearance of many northern communities suffer from the indiscriminate disposal of garbage, refuse, vehicles, scrap and items of all sorts in yards, roads, beaches, etc. This becomes progressive- ly worse as the winter goes on, though mercifully covered by snow for much of the year.

In most communities there is some organized collec- tion of garbage and refuse, once or in a few cases twice weekly. Vehicles vary in sophistication from tractor- drawn open cart to special garbage packer trucks. En- closed vehicles prevent garbage from blowing around during collection and are aesthetically more satisfactory. Overall, the collection of garbage is better organized than the storage facilities or the disposal grounds. Garbage crews are responsible in some communities for general street maintenance and cleanup; however, this appears to be done only infrequently. Massive spring cleanups occur in most communities.

Charges for scheduled collection of garbage and its disposal are usually made on the basis of *number* of drums emptied, as for *gallons* of water delivered and sewage picked up, and *number* of 'honey-bags' delivered.

This method of payment places the emphasis on quantity
rather than quality of service provided. Since the
contract should specify the required frequency and
level of service for a settlement's municipal services,
which will determine the equipment and labour require-
ments, the actual quantity under these conditions is
not a variable affecting cost of service, and, thereby.
payment. Existing charges for drums (normally 45-gallon
drums) emptied vary from about 40¢ to $1.00.

I-3   TREATMENT AND DISPOSAL SYSTEMS

3.1   PRESENT METHODS:

With the exception of a few larger communities most
do not practise sewage treatment. Those that do generally
use lagoons. Dawson and Grainge (1969) and Heinke *et al*
(1972) have carried out studies on the Inuvik lagoon and
have concluded that lagoons can work in arctic areas
if properly designed and operated. Lagoons, however, are
generally designed to receive dilute wastes from gravity
sewer system. Concentrated wastes should not be dumped
into such a lagoon.

Disposal of 'honey-bags' or their contents is now
made at a sludge pit-lagoon together with holding tank
wastes, or at the garbage dump or at a separate disposal
site. With the ripper-chute method of 'honey-bag'
collection, when the tank truck is full its contents are
dumped by gravity or by ejection pump into the sludge
pit. The pit is covered with earth when it becomes full
and a new one dug. Liquid effluent may flow from the
sludge pit into an adjacent lagoon, if there is one.
Ripped, used bags are disposed of separately at the
garbage dump. The sludge pit-lagoon disposal method is
preferred over other disposal methods. If no sludge
pit-lagoon exists 'honey-bags' are dumped separately
from dry garbage and in a location where pollution of
the water source will not result. The site should be
downwind from and out of the settlement. Burning of the
contents of 'honey-bags' is extremely unpleasant and is
not recommended. The dumping of 'honey-bags' into the
sea should be strictly forbidden.

Disposal of collected garbage and refuse in many
communities is at an open dump. The dump area should
be located far from the water supply to eliminate any
possible source of pollution. To remove any aesthetic
objections it should be located out of view of the settle-
ment, and downwind, so that unpleasant odours or smoke,
from burning at the dump, do not blow over the settlement.
It should not be located on the road to the airstrip, to
avoid giving visitors an unpleasant first impression of
the settlement. A sloping site facilitates dumping
operations, and a nearby supply of gravel or sand helps
in periodic covering of the garbage. In many communities

this is not possible because of lack of equipment,
shortage of gravel or the severe climate. The dump
should be fenced, which is mostly not the case now.
In some settlements several dump sites are used
because of different road access in summer and
winter. From an economic point of view, the distances
travelled between the settlement and the dump should
be as small as possible. However, it cannot be over-
emphasized that the dump area should be located far
enough from the water source to ensure that water is
not polluted by runoff from the dump. The local resi-
dents, government officials and health workers should
agree that the chosen site is suitable in this regard.
The other aspects of dump location are desirable; that
the location does not pollute the water supply is
essential.

Dumping on ice or in water (ocean) has been practised
in the past, but now only in a few small communities
where local circumstances may make it tolerable. In
general, this method is now prohibited. Sanitary land-
fill is practised in a few of the more southern communi-
ties. The cold climate makes biological degradation so
slow, that the value of covering is really only in prevent-
ing garbage from blowing around and reducing the danger
of disease transmissions through insects and animals. In
most cases where sanitary landfill is claimed to be
practised, it really is a modified open dump. The most
common form of incineration is through open dump burning.
Incinerators are used at some industrial camps, but not
in communities.

3.2   ALTERNATIVE METHODS:

The alternative methods considered fall into two
categories:

    - solids handling methods prior to treatment

    - treatment and disposal methods.

Solids handling methods are required for 'honey-bags'
prior to any possible treatment methods. One improve-
ment in this was seen recently in Greenland (Heinke
(1973a)) and is described below. Treatment and disposal
methods include anaerobic digestion, chemical precipi-
tation and incineration.

1.   'Honey-bag' Disposal Station:

Disposal stations were inspected at Godthab, which
has a bucket collection system, and at Holsteinsborg
and Egedesminde, which have bag collection. In all three
towns, collection of human waste is carried out daily.

Final discharge of wastes is to the sea, which is
considered acceptable in Greenland. All towns larger
than 1500 people must have a disposal station built
in the next few years. It is a two-storey building,
30' x 20'. It contains a room for unloading and
emptying of bags, provisions for thawing frozen bags,
oil-fired incinerator for burning empty bags, a winter
storage, washroom and changing room for the operator,
and a workshop and storage room. The disposal station
in Egedesminde, built at a cost of 750,000 Danish Kroner
(approx. $125,000), was put into operation in 1972. The
populationof Egedesminde is about 3200, but parts of
the town are serviced by utilidor. Bags are delivered to
the station by a private contractor, who is paid 2.50 Kr/bag
($0.42/bag). One man is employed for the day to day
operation of the station. His monthly salary is 1800 Kr.
($300) plus a bonus of 2 Kr. (0.3 cents) per bag in recogni-
tion of good effort. He works 64 hours per week from
8 A.M. to 6 P.M. handling approximately 98,000 bags annual-
ly, or an average of 270 bags per day. Pickup in Egedesminde
takes place directly from the washroom of the houses
and consequently only a few of the bags are brought
frozen to the station. There are facilities for steaming
them (about 8% were frozen last year). Bags are made of
strong paper, with a plastic liner. A special clip is
used to close them. Empty bags are burned in an oil-
fired incinerator. It can only handle 25 bags per hour,
and less when bags are very wet. In Holsteinsborg,
plastic bags are used and are difficult to burn. The
contents of bags are emptied into a collecting tank and
discharged through a gravity pipe to the sea below low
water level.

Construction of a pilot 'honey-bag' disposal
station in one or several communities of the N.W.T. is
recommended. It will improve present methods of
disposal of 'honey-bags' even without further changes
in treatment, occurring at the same time. In addition,
Canadian experience with it can be gained prior to
implementation of treatment methods for concentrated
wastes.

2.   Anaerobic Digestion

Application of the anaerobic digestion process for
treatment of concentrated wastes is discussed in more
detail in Part II of this report. A review of the
literature reveals that anaerobic digestion of sewage
sludges can function at lower temperatures; however,
with reduced rates of digestion so that longer detention
times are required. Anaerobic digestion is undoubtedly
taking place in sludge pits, however under uncontrolled
conditions. The research carried out in the present

Final discharge of wastes is to the sea, which is
considered acceptable in Greenland. All towns larger
than 1500 people must have a disposal station built
in the next few years. It is a two-storey building,
30' x 20'. It contains a room for unloading and
emptying of bags, provisions for thawing frozen bags,
oil-fired incinerator for burning empty bags, a winter
storage, washroom and changing room for the operator,
and a workshop and storage room. The disposal station
in Egedesminde, built at a cost of 750,000 Danish Kroner
(approx. $125,000), was put into operation in 1972.
The population of Egedesminde is about 3200, but parts of
the town are serviced by utilidor. Bags are delivered
to the station by a private contractor,who is paid 2.50 Kr/bag).
One man is employed for the day to day operation of the
station. His monthly salary is 1800 Kr. ($300) plus a
bonus of 2 Kr. (0.3 cents) per bag in recognition of
good effort. He works 64 hours per week from 8 A.M.
to 6 P.M. handling approximately 98,000 bags annually,
or an average of 270 bags per day. Pickup in Egedesminde
takes place directly from the washroom of the houses
and consequently only a few of the bags are brought
frozen to the station. There are facilities for steaming
them (about 8% were frozen last year). Bags are made of
strong paper, with a plastic liner. A special clip is
used to close them. Empty bags are burned in an oil-
fired incinerator. It can only handle 25 bags per hour,
and less when bags are very wet. In Holsteinsborg
plastic bags are used and are difficult to burn. The
contents of bags are emptied into a collecting tank and
discharged through a gravity pipe to the sea below low
water level.

Construction of a pilot 'honey-bag' disposal
station in one or several communities of the N.W.T. is
recommended. It will improve present methods of
disposal of 'honey-bags' even without further changes
in treatment, occurring at the same time. In addition,
Canadian experience with it can be gained prior to
implementation of treatment methods for cocentrated
wastes.

2. Anaerobic Digestion:

Application of the anaerobic digestion process for
treatment of concentrated wastes is discussed in more
detail in Part II of this report. A review of the
literature reveals that anaerobic digestion of sewage
sludges can function at lower temperatures; however,
with reduced rates of digestion so that longer detention
times are required. Anaerobic digestion is undoubtedly
taking place in sludge pits, however under uncontrolled
conditions. The research carried out in the present

laboratory study has, as one of its objectives, the
optimum environmental conditions which must be obtained
to treat concentrated wastes satisfactorily and economic-
ally. This will include ultimate disposal of anaerobic
sludges and further treatment required of the supernat-
ant. For further discussions on this topic see Part II.

3.   Aerobic Digestion:

There are substantial possibilities of application
of aerobic digestion for treatment of concentrated
sewage and sewage sludges in arctic climatic conditions.

Theoretically, the involved reactions are exother-
mic and may produce more heat than heat losses during
the respective treatment. Therefore, the temperatures
of liquors under digestion may rise above the tempera-
tures of the inflow material. In turn, these elevated
temperatures increase the rate of reaction.

Although there are some examples in Sweden of a
successful application of this approach, very little is
known about its design parameters and limitations. Even
the aeration equipment used for this purpose should be
accordingly modified.

4.   Physical-Chemical Treatment:

Some experience in physical-chemical treatment of
concentrated wastes has been gained in treatment of black
water from vacuum sewers by lime precipitation, Jespersen
(1973) outlines the system as follows (Fig. 1):

"The black water is collected in the collecting
tank (1) (see Figure 1) by the vacuum sewer system.
From this tank it is automatically discharged into the
lime reactor (3) in fixed batches. In the lime reactor
the waste is mixed intensively with lime, $Ca(OH)_2$ from
the lime storage tank (8) at a rate of six pounds per
100 gallons (400 flushes). The circulating pump (9)
starts immediately sucking the lime mixed sewage from
the bottom of the lime reactor and throws it at a high
velocity against the upper walls of the reactor. In
larger installations air is blown in at the bottom of
the lime reactor.

During the circulation time (approximately 30
minutes) the pH value increases to above 12. With this
high pH value the urea compound (NH_2CONH_2) in the liquid
reacts with water to form ammonia (NH_3) and carbon
dioxide (CO_2). After the liquid waste has been mixed with
lime the batch is allowed to settle for 30 to 40 minutes,
during which period phosphorus is precipitated and at
the same time strong flocculation of suspended and colloid-
al particles occurs in the liquid which forms a sediment

FIGURE 1   BLACK WATER TREATMENT PLANT

(after Jespersen 1973)

1. Collecting Tank
2. De-watering Tank
3. Lime Reactor
4. Ammonia Expellor
5. Sludge Pump
6. Sewage Transport Pump
8. Lime Dosing Tank
9. Circulation Pump
16. Treated Black Water

on the bottom of the lime reactor. If no grey water
has to be treated the black water effluent goes to
the receiving water body through an ammonia expeller
(4) and a pH reducer. The sludge which has settled in
the lime reactor is either pumped to a sludge bed or
taken back to the collecting tank by vacuum. Sludge
from the dewatering tank (2) is fluffy, has a high lime
content and is odour-free. It is periodically removed
by scavenger truck and can be used as fertilizer.

In the treated black water effluent the original
quantity of phosphorus is reduced by approximately 99%,
nitrogen by 75% and BOD by 70%. At the same time,
nearly all pathogenic bacteria and viruses have been
killed due to the high pH value. In some areas re-
carbonation to decrease the high pH value of the effluent
must be done."

Experience with lime precipitation of black water
has been gained in several European countries, notably
in Denmark. Canadian application, at the research
pilot plant and finally full scale installation should
be carried out in conjunction with vacuum sewer install-
ations. Lime treatment of 'honey-bag' wastes, with or
without prior digestion, by anaerobic or aerobic processes,
should be investigated.

Deans and Heinke (1972) report on another chemical
treatment method, the Elsan Yarrow System (Fig. 2).

"It was originally designed to treat shipboard
wastes; however, three land installations are now in
operation, two in Great Britain and one at the supplier's
plant at Port Colborne, Ontario. These are compact,
factory assembled treatment units designed to service the
kitchen and personal wastes of 25 to 120 people. The
largest unit is about 10 feet long, 6 feet wide and 6 feet
high. Additional space would be required for the control
panel and pressurized supply tank. The unit employs
chemicals with the trade names E.C. 1, a chlorine com-
pound, and E.C. 2, which contains sodium hydroxide, to
reduce all sewage, paper, and vegetable matter from the
water closets or drains, to a completely sterile liquid
of acceptable odour and colour. This liquid is claimed
to be acceptable for recirculation as flushing water.

The Elsan Yarrow Unit may be charged with either
salt or fresh water. The operation of this unit is as
shown in the line diagram (Fig. 2). The E.C. 1 chemical,
in tablet form, releases chlorine in the pressure break-
down tank which improves the colour and odour of the
wastes. The wastes then pass through a comminutor where
they are further broken down, and then to the chemical
treatment tank. The chemical E.C. 2, in flake form, is
added in this tank. These flakes which contain sodium

FIGURE 2   FLOW DIAGRAM - ELSAN YARROW CHEMICAL TREATMENT
(after Deans and Heinke (1972))

hydroxide, further break down the solids and ensure
stability of the effluent.

This type of unit may have application in recreation-
al or industrial camp sites, for military field use or
for specific buildings or institutions within a community.
The compact size of this unit permits adaptation for
installation in transportable or mobile units. Technical
supervision of the plant operation would have to be
available."

5.   Incineration:

Incineration is a process where either all liquid and
solid wastes are burned when mixed with a combustible
fluid or where concentrated wastes or sludges are reduced
to an inert ash by burning with a fuel, or by an electrical
element. Alter (1969) reported that the first method has
yet to be perfected for general use. A survey by Deans
and Heinke (1972) of manufacturers and suppliers indicated
that no commercial models were available in 1971. However,
developments were being worked on and may have resulted
in commercial units by now. Further investigation follow-
ing this preliminary report needs to be done.

The latter method has been applied to concentrated
sewage, concentrated black water wastes and sludges.
Baumgartner (1960) reports on the use of an oil-carriage
sewage incineration system at remote air force sites in
Alaska. Jespersen (1973) reports on incineration of black
water. If oil or gas is readily available, incineration
of the black water is often both technically and economic-
ally feasible for small communities. Most incinerators
in Scandinavia (Paccanora-hammer, Atlas Denmark, etc.) use
0.5 to 0.7 litres of heavy fuel oil per litre of waste.
The advantages are:

1.   Low installation cost.

2.   No sludge handling problems.

3.   Extra heat for numerous purposes available.

4.   Possibility of pyrolyzing or burning
     garbage from the household.

Deans and Heinke (1972) report on the possible appli-
cation of a commercial unit for toilet waste, sludges or
refuse:

"A representative unit which is commercially available
for the burning of concentrated human wastes is manufactured
by Garret Industries, Rexdale, Ontario. This unit was
originally developed for the incineration of chemically
treated human wastes from portable military field install-
ations. Units for commercial use would be modifications
of this military unit.

The Garret incinerator has the capacity to burn the toilet and solid wastes (garbage) generated by 250 people per day, using either diesel oil, gasoline, natural gas or manufactured gases. The wastes are burned in batches, equivalent to that generated by 80 people, in 6 to 7 hours at a temperature of 1600°F. Fuel consumption would be 1.1 U.S. gallons of diesel fuel per hour. The electrical power required for the blower and controls is 350 watts. Cost for this unit would be about $15,000.

The incineration of waste sludges would have the advantage of complete destruction of the wastes. Both sludges and general garbage could be burned in the unit. Small units, like the one described, can be operated and maintained with a limited amount of technical knowledge and skills.

Disadvantages of the incineration process include high capital cost, requirements for fuel and electrical power, and odours if the unit is improperly operated or maintained. Local incinerator requirements may also be a problem in the operation of the particular unit described. For example, the Ontario Air Management Branch of the Department of Energy Mines and Resources, require that an incinerator which burns Type 4 wastes have minimum combustion chamber temperatures of 1800°F and stack temperatures of 1600°F. Type 4 wastes include materials in which pathogenic bacteria might be present (Air Management Branch Department of Energy and Resources Management, 1970)."

Substantial information is available on a small incinerator for refuse disposal at the Murphy Dome Air Force Station in Alaska (Smith and Straughn (1971)).

The recent large increases in costs of energy and in particular of oil, require re-evaluation of the possible economics of incineration for destruction of toilet wastes and refuse. Insufficient work has been done as part of this report to come to any firm conclusions.

REFERENCES

Alter, J. (1969)
    Sewerage and Sewage Disposal in Cold Regions.
    Monogr. III-C5b, Cold Reg. Sci. & Eng., Hanover, N.H.

Associated Engineering Services Ltd. (1973)
    Solid Waste Management in the Canadian North,
    Rep. Environ. Prot. Serv., Environ. Canada, Ottawa.

Averill, D.W. and Heinke, G.W. (1973)
    Vacuum Sewer Systems for Northern Applications,
    Proc. Symp. Wastewater Treat. in Cold Clim., Saskatoon.

Baumgartner, D.J. (1960)
    Water Supply and Waste Disposal Problems at Remote Air
    Force Sites in Alaska, Proc. 11th Alaska Sci. Conf. 91

Cadario, P.M., and Heinke, G.W. (1972)
    Manual for Trucking Operations for Municipal Services in
    Communities of the Northwest Territories, Publ. Dept.
    Civ. Eng., Univ. Toronto.

Cooper, P.F. (1968)
    Engineering Notes on Two Utilidors, Technical Notes -1,
    North. Sci. Res. Group, Dept. Indian Affairs and North.
    Dev., Ottawa.

Dawson, R.N. and Grainge, J.W. (1969)
    Proposed Design Criteria for Wastewater Lagoons
    in Arctic and Sub-Arctic Regions, J. Water Pollut.
    Control Fed., 41, 237.

Deans, B. and Heinke, G.W. (1972)
    Household and Community Waste Disposal Systems for
    Northern Communities, Publ. Dept. Civ. Eng., Univ.
    Toronto.

Fair, G.M., Geyer, T.C., and Okun, D.A. (1968)
    Water and Wastewater Engineering, Vol. 2, John Wiley and
    Sons Inc., New York.

Hawk, P.B., Oser, B.L., and Summerson, W.H. (1937)
    Practical Physiological Chemistry, 12th ed.,
    The Balkinston Co., Toronto

Hanks, T.G. (1967)
    Solid Waste/Disease Relationships - A Literature Survey
    Publ. Public Health Serv., U.S. Dept. of Health, Educa-
    tion and Welfare, Cincinnati.

REFERENCES (CONT'D)

Heinke, G.W. (1974)
    Report on Municipal Services in Communities of the
    Northwest Territories, Dept. Indian Affairs &
    North Dev., Publ. No. QS-1323-000-EE-A1, Ottawa.

Heinke, G.W. (1973a)
    Report on Environmental Engineering in Greenland and
    Northern Scandinavia, Dept. Civ. Eng., Publ. No. 73-05,
    Univ. Toronto.

Heinke, G.W. (1973b)
    Solid Waste Disposal in Communities of the Northwest
    Territories, Rep. Environ. Prot. Serv., Dept. Environ.,
    Ottawa.

Heinke, G.W., Miyamoto, H., and Jacobsen, N. (1972)
    Evaluation of a Sewage Lagoon at Inuvik, N.W.T., Publ.
    Dept. Civ. Eng., Univ. Toronto.

Ikeda, I. (1972)
    Experimental Study on Treatment of Night Soil by the
    Wet Air Oxidation Process, Water Res., 6, 967-979.

Iwai, S., Honda, A., and Chong, C.Y. (1962)
    Experimental Studies on High Rate Digestion of Night
    Soil. Mem. Fac. Eng., Kyoto Univ., Vol. XXIV, Part 3.

Jespersen, F. (1973)
    Vacuum Sewage Transport and Treatment in Rural Areas in
    Denmark, Proc. Symp. Wastewater Treat. Cold Clim.,
    Saskatoon.

Olsson, E., Karlgren, L. and Tullander, V. (1968)
    Household Waste Water, Rep. Natl. Swedish Inst. Build.
    Res., Stockholm.

Painter, H.A. and Viney, M. (1959)
    Composition of Domestic Sewage, J. Biochem. & Microbiol.
    Tech. Engg., 1: 143-162

Ryan, W.L., Crum, J.A., and Rogness, D.R. (1972)
    Sanitation Facilities Construction Branch, Alaska Area
    Native Health Service, Depart. Health, Educ. & Welfare,
    U.S.A. (Personal Communication) 1972-1973.

Smith, D.W. and Straughn, R.O. (1971)
    Refuse Incineration at Murphy Dome Air Force Station,
    Arctic Health, Educ. & Welfare, Fairbanks, Alaska.

Spector, W.S. (1956)
    Handbook of Biological Data, W.B. Saunders & Co.,
    Philadelphia - London

II-1   THE ANAEROBIC DIGESTION PROCESS

1.1   A BRIEF REVIEW:

Anaerobic digestion, as a biological process in waste treatment, has been practised since the beginning of the twentieth century. Imhoff (1906) was one of the first to use plants which separated solids from mixed sewage. The settled sewage was then digested in the lower compartment of the Imhoff tank. Since those early days, anaerobic digestion has gained importance primarily as a means for treating the solid organic matter contained in sewage, but also for industrial wastes carrying high concentrations of dissolved organic matter.

Anaerobic digestion, a process also occurring widely in nature, can be defined as a biological process, in which complex organic matter is converted to methane and CO_2 in the absence of oxygen. The stabilization of organic matter in waste is mainly brought about by bacterial metabolism which converts the complex organic molecules into stable end products. A portion of the organic matter is synthesized into new cell protoplasm, while a further portion is oxidized as a source of energy. Unlike aerobic oxidation, the anaerobic conversion yields relatively little energy to the micro-organisms. Thus, their rate of growth is slow and only a small portion of the waste is converted to new microbial cells, the major portion of the degradable waste being converted to methane gas. Such conversion to methane gas represents waste stabilization since methane gas is insoluble in water and escapes from the waste stream. It can be collected and burned to CO_2 and water for heat. As much as 80 to 90% of the degradable organic matter of the waste can be stabilized in anaerobic digestion by conversion to methane gas, even in a highly loaded system. This is in contrast to aerobic systems, where only about 50% of the waste is actually stabilized even at conventional loading (McCarty (1964)).

Anaerobic digestion is usually considered to be a two-stage process consisting of acid-formation (liquefaction) and gas-formation (gasification). At least two large, physiologically different, bacterial populations must be present for the overall conversion of organic matter to methane and CO_2 to occur. In the first stage, a heterogeneous group of micro-organisms convert proteins, carbohydrates and lipids mainly into fatty acids by hydrolysis and fermentation (McCarty *et al*, (1963)). In the second stage, the end products of the metabolism

of the micro-organisms of the first stage are converted
to methane and CO_2 by strict obligate anaerobic bacteria
called methanogenic (methane-formers) bacteria.

Several investigators in the past suggested that
the bacteria involved in the "acid-formation" stage are
predominantly facultative, with a few obligate anaerobes
(McKinney (1962), McKinney et al (1958), McCarty et al,
(1962)). This concept was more recently questioned by
Toerien et al (1967) who were of the opinion that
aerobic and facultative anaerobic bacteria account for
only a small proportion of the total bacterial popula-
tion of anaerobic digesters. These investigators
(Toerien & Siebert (1967)) developed a method based on
the cultivation methods used in rumen microbiology
and used this new method to enumerate obligate anaerobic
acid-forming bacteria in digesters. The anaerobic counts
were usually 100 or more times greater than the aerobic
counts (Toerien et al, (1967)). The suggestion of
McKinney (1962) that acid-formation is mainly carried
out by facultative bacteria seems to be incorrect in
the light of these results.

The methane bacteria and their characteristics
which are responsible for the majority of the stabiliza-
tion in the second phase in anaerobic digestion, are
poorly defined, although studies on methane bacteria
have been carried out for many years. Until recently
the techniques for the enumeration of methane bacteria
were very poor. However, good methods based on those
of Hungate (1950) which have been used in rumen micro-
biology, are now available. These methods formed an
interesting approach to the study of methane bacteria
in sludge digestion (Mylroie & Hungate, 1954). It is
unfortunate that further work does not appear to have
been carried out along these lines except that of
Siebert & Hatting (1967).

1.2 ANALYTICAL TECHNIQUES FOR CONTROL AND CHARACTERIZATION
OF ANAEROBIC DIGESTION:

The major factors determining the nature of a
specific digester are the substrate composition and
loading, the temperature of operation, the design of
the digester tank, the mode of operation and the source
of the inoculum of micro-organisms required to digest
the substrate (Kotze et al, 1969).

Before it is possible to control anaerobic diges-
tion efficiently it is necessary to characterize a
well-operating digester. No single factor (parameter)
can be used as a control measure of the process of

anaerobic digestion as the degradation of organic matter to methane and CO_2 is brought about by a heterogeneous microbial population. Various factors affect digestion and a number of "general" parameters such as pH, alkalinity, volatile acid content, solids and volatile solids content, COD of feed and effluent and rate and composition of gases produced are normally used to control anaerobic digestion (Pohland (1962), Hatting *et al* (1967)). These investigators indicated that the above named "general" parameters were not sufficient to describe anaerobic digestions and thus biological parameters were developed by them to assess the state of biological activity.

1.3   LOW TEMPERATURE ANAEROBIC DIGESTION:

The reactions taking place in an anaerobic digester result from the activity of the heterogeneous bacterial population. The effect of temperature on the process as a whole is therefore a reflection of the behaviour of the bacteria at different temperatures. Buswell (1957) reported that production of methane could be achieved from $0^{o}C$ to $55^{o}C$. However, generally, anaerobic digestion in the mesophilic temperature range ($20-45^{o}C$) with an optimum at about $37^{o}C$ is practised. This is in large part due to the high energy requirements for temperature maintenance. Thermophilic temperatures often bring about more efficient digestions but control of temperature seems to be the greater problem. Sudden temperature changes are detrimental to anaerobic digestion (Buswell, 1957).

Little information is available concerning low temperature anaerobic digestions. Rudolfs (1927) reported studies on unseeded sewage sludge at temperatures of 10, 18, 24, 29.5 and $35^{o}C$. About 360 days retention time was required at $10^{o}C$ compared to 61 days at $27^{o}C$ to $28^{o}C$. Fair and Moore (1934, 1937) report digestion times at $10^{o}C$ of 4 to 5 times that required at $25^{o}C$, and digestion times of nearly 8 times that required at $25^{o}C$ when operating at $5^{o}C$. Interestingly, these longer required digestion times at lower temperatures do not agree with those predicted by thermodynamic considerations. However, micro-organisms do not always follow thermodynamic laws. Zeller (1928) reported that freezing was not disruptive to the anaerobic process if the reactor is later returned to its original temperature, in that case $20^{o}C$. Recently, there has been little investigation of the anaerobic process at low temperature. O'Rourke and McCarty (1967) reported on studies at 25 and $15^{o}C$ on the digestion of sewage solids. McGhee (1968) conducted studies on digestion of sewage solids at a temperature of $25^{o}C$ with continued methane production and destruction of total and volatile solids.

From these studies it appears that anaerobic
digestion can function at lower temperature; however,
with slower rate of digestion requiring longer deten-
tion times. McGhee (1968) concluded from his studies
that the anaerobic process at low temperature is
equivalent to that at high temperature and is not
dependent upon the generation of a specialized popula-
tion of psychrophilic bacteria. The normal sewage
bacteria continue to function at low temperature,
though at a much reduced rate. Since his studies were
not extended to determine the psychrophilic population,
the statement should be accepted with reservation.

II-2   EXPERIMENTAL SETUP AND ANALYTICAL METHODS

2.1   EXPERIMENTAL SETUP:

To simulate the present practice of dumping of
'honey bags' into a sludge pit constructed in permafrost,
an anaerobic laboratory sludge pit, described below,
was constructed. It is being operated so far at a temper-
ature of -5°C (21°F) which is the approximate soil temper-
ature at a depth of about 3-5 m. (10-15 ft.) underneath
undisturbed tundra under winter conditions. (Edwards,
(1974) Private Communication). In order to be able to
compare results at such low temperatures to those achieved
at higher temperatures a conventional anaerobic batch
reactor is operated at 10°C concurrently.

1.   Anaerobic Pit

The laboratory anaerobic pit consists of a wooden
box 122 x 92 x 92 cm. (4 x 3 x 3 ft.). In the centre,
a 61.0 cm. (2 ft.) long plastic container (dia. 38.0 cm.)
having a volume of 68ℓ (15 gal.) was placed. In order to
simulate the permafrost conditions, the box was filled
with loam soil in such a way that the plastic container
was surrounded by a minimum of 30.5 cm. loam soil. To
facilitate the introduction of the waste and collection
of the mixed liquor from the pit, a 30.5 x 30.5 x 30.5
cm. (1 x 1 x 1 ft.) lid box was prepared and fitted at
the top of the plastic container. (Figs. 3 and 4).
The anaerobic pit is operated at -5°C temperature in a
walk-in incubator.

The concentrated waste is introduced at the rate of
5-7 litres per week.

2.   Anaerobic Batch Reactor

A 20-litre glass bottle is used for the laboratory
anaerobic batch reactor. This unit is operated at +10°C
in an incubator. The bottle was filled with 17 litres
of concentrated waste, and was closed with a rubber
stopper and sealed. Gas was removed through glass tubes

FIGURE 3   DIAGRAM OF THE LABORATORY ANAEROBIC PIT AT -5°C

FIGURE 4   PLAN VIEW OF THE LABORATORY ANAEROBIC PIT

inserted in the stopper. Mixed liquor was withdrawn
through a tube with the help of a pump. Gas was
delivered into one litre graduated bottles containing
an acidified solution saturated with common table salt.
The acidification and saturation with NaCl insures the
insolubility of the gases produced (Fig. 5).

3. Collection and Handling of Human Waste

The study ran into several difficulties in the
early stages, especially because of the difficulty in
obtaining human body waste free of inhibitors, in a
metropolitan area. These difficulties delayed the
start of laboratory investigations for several weeks.
Local sanitation firms were contacted for the supply of
the inhibitors-free human waste, but they were reluct-
ant to do so. However, one firm agreed to cooperate,
but their efforts had to be abandoned after only one
collection, because only 5.0 litres of waste free of
chemical inhibitors was thus procured in two weeks'
time. Finally, one firm agreed to lend us a portable
toilet. It was brought to the university laboratory
in the month of January, 1974, and is being operated
since then. About 2-5 persons were expected to use the
portable toilet every day. This number, however, dropped
to one person per day on several occasions.

Both faeces and urine were collected and the amount
measured. This ranged from 0.5 to 3 litres per day,
depending upon the number of persons using the toilet.
The waste was stored in a bottle for a week at $-5^{o}C$.
Before being transferred to the pit, the waste was thawed
at room temperature overnight. Waste characteristics,
such as pH, alkalinity, COD, total and volatile solids,
total nitrogen, NH_4-N, total PO_4 and calorific values
were determined on the contents of the bottle, before
transfer to the pit.

2.2. ANALYTICAL METHODS:

1. Sampling and Replication

An estimate of the precision of the procedures
involved in sampling, analysis and replication of analyses
was needed, since the waste is of very high strength.
Parameters which could affect replicate samples were
tested: volume of sampled waste, homogenization of the
waste, dilution of the waste. The following procedure,
which is considered adequate for the work, was evolved:

All samples of wastes are collected weekly, homo-
genized by Waring Blender. The analyses of samples for
both physico-chemical and bacteriological tests were
commenced within a few minutes of sampling except for the

FIGURE 5   DIAGRAM OF THE LABORATORY ANAEROBIC

BATCH REACTOR AT $10^{o}C$

samples collected from the anaerobic pit, where the delay extended 1-2 hours due to the need for thawing of the samples. The medium delay between sampling and plating for bacteriological analyses was 60 minutes.

2. Physical and Chemical Methods

pH:-

pH was measured on all samples withdrawn from the units as well as the waste collected from the toilet. It was measured as rapidly as possible to minimize the change due to loss of CO_2.

Alkalinity:-

Total alkalinity was measured regularly by titration with 0.1 NH_2SO_4 to a pH of 4.5. The samples were diluted to 100 times and 25 ml. of the diluted sample was normally used for titration.

Chemical Oxygen Demand (COD):-

COD, together with volatile and total solids, was used as an operational parameter. COD measurements were made on 10 ml. of diluted samples according to Standard Methods (1971).

Solids:-

Solids, both total and volatile, were measured for both anaerobic pit and anaerobic batch reactor mixed liquors. Later on, dissolved solids and dissolved volatile solids were also measured on centrifuged super-natant.

Nitrogen:-

Both NH_4-N and organic nitrogen were determined by Kjeldahl procedure as described in Standard Methods (1971).

Phosphorus:-

Total phosphorus in samples was determined accord-ing to the method described by Heinke (1969), using aminonaphtholsulfonic acid and an auto analyzer.

Calorific Values:-

An oxygen bomb calorimeter manufactured by Parr Instrument Co. Inc. was used for determining calorific values. The determinations were made on 1.0 gm. of

oven dried (105°C) waste material. The results are
reported in terms of cal/g. of oven dried weight and
ash free oven dried weight.

3. Bacteriological Methods

The total number of viable aerobic and anaerobic
bacteria and fecal streptococci were determined by the
dilution plate method. Ten-fold dilutions were prepared
in physiological saline, and 1.0 ml. aliquots of the
desired dilutions were plated with 10 ml. aliquots of
appropriate fluid agar (50°C). For each medium, 3-4
dilutions of each sample were plated in duplicate. The
plates thus prepared were incubated in the dark for 7
days for mesophilic bacteria at 20°C, for 4 weeks for
psychophilic bacteria at 0°C, and for 48 hours for fecal
streptococci. For anaerobic bacteria plates were incu-
bated at 20°C and 10°C in anaerobic jars.

Total Bacterial Count:-

The bacterial medium used for total bacterial count
was the nutrient agar described by the Society of Ameri-
can Bacteriologists (1957) supplemented with 0.1%
glucose at pH 7.4. Actidione was added to the fluid agar
(50°C) just before plating to give a final concentration
of 0.1%. The actidione stock solution (1.0%) had been
previously sterilized by autoclaving for 10 min. at
121°C and 20 lb. pressure. Preliminary investigations
had shown that all waste supplies contained large
numbers of fungi, which suppressed the growth of bacteria
on the plates. Since the wastes were stored at -5°C
prior to transferring to the units, and fungal spores
are more resistant to freezing than most bacteria, the
large number of fungi observed is not surprising. Because
of the large numbers of fungi, the incorporation of
actidione, a fungicide, was considered essential.

Obligate Anaerobic Bacterial Count:-

We are attempting to count obligate anaerobic bac-
teria using the new method developed by Toerien &
Siebert (1967) in the present study. This method includes
the use of the roll-tube technique. A small portion of
the material under test is introduced into melted nutrient
agar contained in a small, specially designed, bottle
which is held in a horizontal position in an electric-
ally driven spinner. The spinner is constructed of
heavy gauge mild steel and holds seven bottles in stain-
less steel spinner heads driven by a 1/2 h.p. motor.
As the bottles rotate in the spinner they are bathed in
cold water contained in a cooling trough. This causes
the melted and inoculated agar to set within one minute
in the form of a thin film. The bottles are then incu-
bated at a suitable temperature. After incubation the
colonies which develop on the thin agar film are counted.

Unfortunately, the roll-tube spinner is not available
in Canada, so we had to get it made in our workshop.
This equipment is ready for use now and will be used
from now on.

Methane-Forming Bacterial Count:-

In the present study an attempt will be made to
enumerate the methane bacteria by MPN method developed
by Siebert & Hatting (1967). This work will be started
when the reactors reach the methane-formation phase.

Test for Indicator Organisms:-

Tests for coliforms and fecal streptococci (entero-
cocci) were conducted regularly to determine the bacter-
iological safety of the treated waste. Although the
validity of these indicators is questioned for various
reasons, especially in cold regions, these are the best
ones we have at hand. Some data is available from cold
regions on coliforms and other fecal indicators in
sewage lagoons (Miyamoto 1972), rivers and lakes (Boyd
and Boyd 1967); little is available on toilet waste
disposed of in 'honey bags'. The literature contains
several references to the use of other indicator organ-
isms such as *Clostridium perfringenes, Pseudomonas
aeruginosa*; due to lack of time, these were not included
in this study. However, we are planning to use these
indicators in the future.

Coliforms:-

In the preliminary experiments McConkey Agar was
tried for total coliform plate counts, but found to be
unsuitable, because the number of coliform bacteria
reduces tremendously due to freezing of the wastes at
$-5^{\circ}C$. Furthermore the unusual nature of the sample
made it difficult to identify bacterial colonies on the
plates. Therefore, coliforms were estimated by MPN
method in accordance with Standard Methods (1971).

Fecal Streptococci (Enterococci):-

Fecal streptococci were determined by the pour-
plate technique using M-Enterococcus agar according to
Standard Methods (1971).

II-3   RESULTS AND DISCUSSIONS

The results and discussion relate to:

1. Waste (Feed) put in the anaerobic pit and the batch anaerobic reactor.

2. Pit mixed liquor.

3. Batch reactor mixed liquor.

The results for both anaerobic pit and batch anaerobic reactor are discussed with respect to the following in the order indicated:

3.1 Physical-Chemical Results:

1. Volume and the composition of the Human Waste

2. Temperatures

3. pH and alkalinity

4. Solids -- total, volatile, dissolved and suspended

5. COD

6. Nitrogen

7. Calorific value

Bacteriological Results.

1. Volumes and the Composition of the Human Waste:-

The volume of human waste was dependent on the number of persons who used the toilets, their diet, the frequency of excretion, and the purpose. Sometimes the toilet was used only for urine excretions. The volumes of the waste transferred to the anaerobic pit during the different weeks are shown in Table IV.

TABLE IV

VOLUME OF WASTE INPUT INTO THE ANAEROBIC PIT

MONTH/WEEK	No. of Days	Waste-Input Litres	Average Waste Produced litres/day
Feb. - 2nd week	5	7.5	1.5
Feb. - 3rd week	5	5.0	1.0
Feb. - 4th week	5	6.5	1.3
Mar. - 1st week	5	5.0	1.0
Mar. - 2nd week	5	6.0	1.2
Mar. - 3rd Week	5	7.0	1.4
TOTAL & AVERAGE:	30	37.0	1.23

Daily rate of waste input to the batch anaerobic reactor was not determined. However, since there was little change in the number of persons using the toilet, the rate of waste input to the batch anaerobic reactor was not much different from the rate of waste input to the anaerobic pit.

Only few samples (six) have been analyzed to date and the results are shown in Table V. In order to compare the results obtained in this study, data taken from the literature (Table I) and converted to comparable units (mg/l) are shown in Table VI. By comparing Tables V & VI, it can be seen that Total solids (75,850-85,030 mg/l) and COD values (11,220-134,820 mg/l) in this study (Table V) are considerably higher than those reported (Total Solids - 63,077 mg/l, COD - 81,538 mg/l) in the literature (Table VI).

TABLE V

COMPOSITION OF HUMAN WASTE - RESULTS OF ANALYSIS

Date	pH	Alk. mg/l CaCo₃	Mixed Waste COD mg/l	Total Solids mg/l	Total Volatile Solids mg/l	Dissolved Solids mg/l	Dissolved Volatile Solids mg/l	TKN mg/l	NH₄-N mg/l	Organic-N mg/l	Phosphorus as PO₄ mg/l	Calorific Value Cal/g	Centrifuged Supernatant COD mg/l.
								Mixed Waste: Nitrogen					
12-2-74	8.80	-	110,880	79,980	63,415	53,620	44,760	7,580	3,700	3,880	3,500	4,340	44,880
19-2-74	8.85	16,400	134,820	83,250	66,410	38,720	27,120	8,230	3,530	4,700	3,400	4,260	-
26-2-74	8.90	17,800	110,220	75,850	59,170	37,650	25,450	8,180	3,920	4,260	4,000	-	46,990
5-3-74	8.76	15,000	125,630	83,440	67,740	41,070	29,660	8,620	4,370	4,260	4,250	4,380	54,910
12-3-74	8.85	17,000	121,700	85,030	67,220	43,310	30,340	8,400	4,370	4,030	3,500	4,330	61,280
19-3-74	8.85	13,600	102,080	75,560	56,680	36,600	21,980	9,520	4,060	5,520	-	-	42,240
Mean	8.84	15,960	120,650	81,510	64,790	42,870	31,470	8,150	3,980	3,790	3,730	4,330	52,010
Std. Deviation ±	± 0.04	± 1,550	± 10,380	± 1,160	± 3,560	± 6,390	± 7,690	± 430	± 380	± 120	± 320	± 40	± 7,530

TABLE VI

COMPOSITION OF HUMAN WASTE - LITERATURE VALUES

(Taken from Table I)

Total Solids	=	63,077 mg/l
COD	=	81,538 mg/l
Total Nitrogen	=	10,538 mg/l
Total Phosphorus	=	1,154 mg/l

These higher values are probably due to the addition of tissue paper in the waste collected from the laboratory toilet. Addition of tissue paper was considered essential in order to represent the actual waste collected in 'honey bags'. Total nitrogen values (7,580 mg/l - 9,520 mg/l) obtained in this study (Table V) are slightly lower than the literature values (10,538 mg/l). This difference may be attributed to the fact that the waste collected was contributed during working hours (from 9 a.m. to 5 p.m.). Since most of the nitrogen in human body waste comes from urine (Table 1), the low values may be due to the absence of the urine excreted by the persons using the toilets in the early morning. To check on this hypothesis, total nitrogen was determined in the urine excretions of one person starting from early morning (8:00 a.m.) until 5:00 p.m. The results are shown in Table VII. Considering the nitrogen values (14,000 mg/l) in the urine sample excreted early morning, the explanation for low nitrogen values obtained in the waste appears to be correct. The values of total phosphorus in our waste are in agreement with that of literature values.

TABLE VII

VOLUME & TOTAL NITROGEN IN URINE EXCRETED
BY ONE PERSON DURING WORKING HOURS
(8:00 a.m. to 5:00 p.m.)

Time	Total-N mg/l.	Volume Urine Excreted ml.
8:00 a.m.	14,000	130
10:00 a.m.	6,100	150
1:00 p.m.	4,088	125
2:30 p.m.	5,986	110
4:00 p.m.	6,412	150
4:45 p.m.	1,260	200
Average & Total	6,307	865

2.   Temperature:

The temperatures of the contents of the anaerobic reactor, the anaerobic pit and the soil surrounding the pit, were determined regularly.

(a)   Anaerobic Pit (-5^{o}C):

The temperature in the pit mixed liquor, especially below the surface, rose 1 degree higher than the ambient temperature after every addition of the feed, probably from the heat supplied by the feed waste. However, by next day this levelled off and there was no variation in temperature in the pit, soil and ambient temperatures.

(b)   Anaerobic Batch Reactor (+10^{o}C):

The temperature in the anaerobic reactor was the same as ambient temperature in the early part of the experiment. However, later on the temperature in the reactor was 1^{o}C higher than the ambient temperature.

3.   pH and Alkalinity:

(a)   Anaerobic Pit:

The pH and alkalinity values observed in this

study are shown in Table VIII and IX. No significant
fluctuations in both the parameters is evident in the
pit.

(b) Anaerobic Batch Reactor:

pH in the anaerobic reactor (10°C) dropped
by 0.3 units in the first week of operation; this
trend is continuing. In six weeks operation, the pH
has dropped from 8.98 to 7.6. Alkalinity increased in
the first three weeks. From 14.8 g/l it has increased
up to 17.6 g/l in the third week. From the third week
onward it started decreasing and reached its original
value of about 13/0 g/l.

4. Solids:-

(a) Anaerobic Pit:

Total, volatile, dissolved and suspended solids
were determined and the results are shown in Table VIII.
There appears to be considerable fluctuation in all the
solid values of the pit mixed liquor. The difficulty
of obtaining uniformly representative samples of the pit
contents, owing to its partly frozen condition, is
possibly responsible for the fluctuation in results.
Also, the variability of the feed samples may be respon-
sible to some extent. No trend of changes in solids
concentrations is evident, which indicates no activity
in the pit.

(b) Anaerobic Batch Reactor:

Total solids as well as volatile solids have
decreased during the six weeks of operation in the
anaerobic batch reactor (Table IX). Dissolved solids
as well as dissolved volatile solids are also decreasing.

5. Chemical Oxygen Demand (COD):-

(a) Anaerobic Pit:-

Only the centrifuged supernatant of the pit
contents was used for COD determinations to avoid the
errors introduced by the non-homogeniety of the mixed
liquor samples. The results are shown in Table VIII.
The COD values are still fluctuating and this may be
attributed to the wide variations in the COD contents
of the feed waste (Table V). These results also
indicate that there is no activity taking place in the
pit under the experimental conditions.

TABLE VIII

OPERATIONAL PARAMETERS FOR ANAEROBIC PIT – OPERATED AT -5°C.

Date	pH	Alk. mg/l as CaCo$_3$	Centrifuged Supernatant COD mg/l	Total Solids mg/l	Total Vol. Sol. mg/l	Dissolved Solids mg/l	Dissolved Vol. Sol. mg/l	Nitrogen – Supernatant			Calorific Value Cal/g.
								TKN mg/l	NH$_4$-N mg/l	Organic-N mg/l	
20-12-73	8.9	–	43,150	–	–	–	–	10,000	5,320	–	–
12- 2-74	8.7	–	42,240	–	–	55,570	25,220	9,600	6,700	2,800	–
19- 2-74	8.6	21,800	66,000	81,590	57,930	51,080	32,680	9,180	6,220	2,970	3,720
26- 2-74	8.8	17,600	59,810	84,790	66,210	45,160	31,220	7,000	4,260	2,740	–
5- 3-74	8.8	21,200	59,070	86,790	67,720	43,500	30,230	6,830	4,480	2,350	4,180
12- 3-74	8.8	17,000	66,380	86,940	70,070	43,070	31,410	7,930	4,700	3,220	4,370
19- 3-74	8.9	16,600	62,480	81,580	63,650	38,340	25,910	7,620	4,650	2,970	–
Mean	8.8	18,840	56,110	84,160	65,480	47,680	30,150	8,150	5,280	2,720	4,090
Std. Deviation	± 0.05	± 330	± 3,420	± 790	± 1,670	± 1,720	± 2,890	± 2,500	± 2,210	± 260	± 27

TABLE IX

OPERATIONAL PARAMETERS FOR ANAEROBIC REACTOR OPERATED AT 10°C.

Date	pH	Alkal. mg/l CaCo$_3$	Mixed Liquor COD mg/l.	Total Solids mg/l.	Total Volatile Solids mg/l.	Dissolved Solids mg/l.	Dissolved Volatile Solids mg/l.	Nitrogen – Supernatant TKN mg/l.	NH$_4$-N mg/l.	Org.-N mg/l.	Calorific Value Cal/gm.	Centrifuged Supernatant COD mg/l
5-2-74	8.98	14,800	105,000	68,180	54,300	-	-	7,730	3,470	4,260	4,580	-
12-2-74	8.65	-	107,400	67,520	52,750	43,810	36,740	5,910	3,700	2,210	4,110	42,240
19-2-74	8.45	17,200	117,600	62,900	49,570	25,040	16,330	5,600	4,370	1,030	4,330	45,240
26-2-74	7.9	17,600	117,440	57,300	44,470	25,100	14,980	6,370	5,210	1,160	-	45,720
5-3-74	7.85	14,800	-	60,790	47,630	27,620	17,740	6,050	4,590	1,460	4,340	49,090
12-3-74	7.6	14,200	-	60,400	47,480	25,890	16,500	6,030	4,700	1,330	4,480	52,770
19-3-74	7.8	13,200	-	36,380	25,300	19,910	10,520	5,520	4,540	1,000	-	42,240
Mean	8.2	15,720	111,800	62,850	49,370	29,490	20,460	6,330	4,340	2,020	4,370	46,410
Std. Deviation	± 0.5	± 1560	± 6,400	± 4,270	± 3640	± 8070	± 9150	± 830	± 650	± 1330	± 25	± 1410

(b)   Anaerobic Batch Reactor:

COD determinations were made on both mixed liquor and centrifuged supernatant, and the results are shown in Table IX. As expected, COD values of the mixed liquor are erratic probably due to the difficulty of collecting a representative sample. However, the COD values of the centrifuged supernatant are more consistent. These values do not show any COD reductions. It must be remembered that the COD test is somewhat lacking in precision for an individual determination, especially while analyzing waste of very high strength. However, at this initial stage of operation, the reactor probably is in the "acid-forma-tion" phase where complex organic substances are converted to organic acids. COD reductions can be expected when the reactor reaches the methane-formation phase, when these organic acids will be converted to methane gas, which will escape.

6.   Nitrogen:-

A knowledge of nitrogen transformations in waste treatment system is important for several reasons. Nitrogen is one of the major nutrients of concern in the eutrophication of water bodies. An efficient means of eliminating nitrogen from wastes can prevent or reduce pollutions of both surface and ground waters.

(a)   Anaerobic Pit:

Total Kjeldahl nitrogen (TKN) and NH_4-N were regularly determined for the pit mixed liquor centrifuged supernatant and the results are shown in Table VIII. The nitrogen values in the early weeks of operation are higher than the nitrogen values of the feed waste (about 8,000 mg/l). This may be attributed to the fact that the first sample transferred to the pit was obtained from the "Johnny-on-the-Spot" toilets. This waste sample had significantly higher total nitrogen (10,000 mg/l) compared to 8,000 mg/l in the feed waste collected from the toilet operating in the laboratory. Generally, about two-thirds of the total nitrogen in the pit con-tent is in the NH_4-N form. This is in contrast to only 1/2 of the total nitrogen in the feed waste being in the NH_4-N from Table V. These relative values have stayed approximately constant throughout.

Other parameters measured in this study indi-cate no bacteriological activity of any kind in the pit. Therefore this change in nitrogen form may be due to some sort of physical phenomenon or the effect of freez-ing and thawing of the wastes. This will be examined in our future study.

2.0 million/ml. Coliforms ranged from 24 x 10^3/ml
to 15 x 10^4/ml, while fecal streptococci occurred in
the range of 0.4 million/ml to 2.5 million/ml.

These bacterial counts are far lower than
literature values of 10^8 to 10^{10} per gm. of wet
faeces, for aerobes, of 10^6 to 10^8/gm for coliforms
and 10^4 to 10^8 for enterococci (Mata *et al* 1969)
These differences are mainly due to the effect of
freezing of the waste. The literature is enormous
on the effect of freezing and thawing on bacteria,
especially in food technology. However, little work
has been done on the effect of low temperature and
freezing on bacteria in waste waters. Fournelle
(1952) reported that freezing of sewage (-13 to -21^{0}C)
brought reductions in total bacterial counts and coli-
form counts to 95.2% and 99.6% in the first 24 hours.
However, fecal streptococci (enterococci) showed re-
ductions in counts ranging from 56% to 72% the first
24 hours of freezing.

(b) Anaerobic Pit:

In general, the microflora (Table XI) in
the anaerobic pit exists in the same range as was
found in the feed waste, except the coliforms, which
have reduced from about 10^4/ml to less than 1/ml.
According to Fournelle, the first 24 hours freezing is
more detrimental to micro-organisms, and coliforms are
more susceptible to freezing than other bacteria.
Our results are in agreement with Fournelle in this
respect.

Bacterial counts confirm the physical-
chemical results which indicated that the anaerobic pit
is serving just as a holding tank and no biological
activity is taking place.

(c) Anaerobic Reactor:

The results for bacterial counts are shown in
Table XII. Total aerobic counts appear to decrease
during the first week of operation; however, from the
second week onward the bacterial numbers are increasing.
The drop in bacterial numbers in the first week seems
to be due to the temperature effect. An increase in
coliforms also seems to occur. However, fecal strep-
tococci decreased from 1.5 million/ml to 0.055 million/
ml after four weeks. It is too early to conclude from
this limited data, but the results do indicate that
biological activity is going on in the anaerobic reactor
under the experimental conditions.

(b)   Anaerobic Reactor:

The results for nitrogen determinations
are shown in Table IX. It can be seen from the table
that about 2,000 mg/l total nitrogen is unaccounted
for. The TKN loss continued up to 4 weeks of opera-
tion of the reactor. This period corresponds to the
high pH values measured in the reactor mixed liquor
(8.98 - 7.9). Perhaps the observed nitrogen loss
must have occurred by volatilization of NH_3. Chemical
equilibrium conditions dictate that free ammonia can
exist in solution in appreciable quantities at high
pH values.

Organic-nitrogen dropped from 4,000 mg/l to
1,000 mg/l in 5 weeks operation indicating microbial
activity in the reactor.

7.   Calorific Value:-

Calorific values were determined in order to use
these values as another operational parameter as well
as to measure the amount of energy produced as a
result of the decomposition of the waste. The calor-
ific values of the human waste range from 4,260 to
4,380 cal/g dry wt.

(a)   Anaerobic Pit:

The calorific values of the waste content
in the anaerobic pit range from 3,720 to 4,370 cal/g
dry weight of waste. This indicates no activity in the
pit. The fluctuations in the results may be due to
the difficulty in collecting the homogeneous sample.

(b)   Anaerobic Reactor:

The calorific values of the contents in the
anaerobic reactor range from 4,110 - 4,590 cal/g dry
weight of waste. It seems this parameter is similar
to COD measurement so far as precision is concerned.
Probably, it may become of use when the activity is
higher in the reactor.

3.2   BACTERIOLOGICAL RESULTS:

Bacteriological tests were conducted regularly on
feed waste, anaerobic pit and anaerobic reactor con-
tents, and the results are shown in Table X, XI and XII.

(a)   Feed Waste:-

Total aerobic plate count in the feed waste
(Table X) ranged from 4 million/ml to 7.0 million/ml.
Total anaerobic count ranged from 1.0 million/ml to

In all the samples, irrespective of their source, the total anaerobic bacterial counts were lower than total aerobic counts. This is in agreement with other investigators (Rudolfs *et al* 1926; McKinney *et al*, 1958; McCarty *et al*, 1962); however, these results may be considered as doubtful since incidence of large numbers of obligate anaerobic bacteria in faeces, sewage and sewage treatment processes has been demonstrated by modern culture techniques (Zubrycki and Spaulding, 1962; Post *et al*, 1967, and Toerien *et al*, 1967). Due to the difficulty in obtaining the necessary materials for these modern techniques, we were unable to use them in the present study. However, we are planning to use these modern techniques from now on.

Psychrophilic aerobic bacterial counts were found in the range of 100-300/ml in the feed waste as well as in anaerobic pit contents. No increase in numbers occurred in psychrophilic bacteria in the anaerobic pit during the 6 weeks operation of the pit. The low numbers of psychrophilic bacteria may be attributed to the effect of freezing and thawing. Fournelle (1952) observed a reduction of 99.5-99.9% in psychrophilics after freezing the raw sludge.

TABLE X

MICROFLORA IN HUMAN WASTE

Date	Aerobic Total Count 10^6/ml 20^0C	Anaerobic Total Count 10^6/ml 20^0C	Aerobic Total Count No./ml 0^0C	Entero-cocci 10^6/ml 37^0C	Coliform MPN/ml 37^0C
19-2-74	4.6	-	20×10^3	2.5	24×10^3
26-2-74	7.1	1.91	37×10^4	0.56	11×10^4
5-3-74	5.4	-	44×10^4	0.34	15×10^4
12-3-74	7.5	2.0		0.75	8×10^4
19-3-74	6.3	1.85		1.0	10×10^4

TABLE XI

QUANTITATION OF MICROFLORA IN ANAEROBIC PIT OPERATION AT -5^{o}C

Date	Aerobic Total Count 10^6/ml 20^{o}C	Anaerobic Total Count 10^6/ml 20^{o}C	Aerobic Total Count 10^6/ml 0^{o}C	Entero- cocci 10^6/ml 37^{o}C	Coliform MPN/ml 37^{o}C
12-2-74	7.5	2.4	Nil	0.42	43
19-2-74	7.1	1.7	Nil	0.66	110
26-2-74	-	-	-	-	-
5-3-74	8.9	2.0	Nil	0.85	43
12-3-74	2.83	1.79		0.57	46
19-3-74	0.91	-		1.52	2.4

TABLE XII

QUANTITATION OF MICROFLORA IN ANAEROBIC REACTOR

OPERATED AT 10^{o}C

Date	Aerobic Total Count 10^6/ml 20^{o}C	Anaerobic Total Count 10^6/ml 20^{o}C	Aerobic Total Count No./ml 0^{o}C	Fecal Strepto- cocci Count 10^6/ml 37^{o}C	Coliform MPN/ml 37^{o}C
5-2-74	3.38	1.9	200	1.44	
12-2-74	0.75	-	17,000	0.19	0.43
19-2-74	17.5	-	-	0.071	2.40
26-2-74	41.0	1.75	36×10^3	0.069	2400
5-3-74	3,000	150.0	60×10^6	0.055	930
12-3-74	3,200	-		0.027	12
19-3-74	33.5	1.05		0.019	2.4

However, in the anaerobic batch reactor the physchrophilic bacteria increased from 200/ml to 60×10^6/ml. This increase corresponds to the increase in mesophilic aerobic bacteria.

In no case were anaerobic psychrophilic bacteria found in this study.

II-4   FUTURE EXPERIMENTAL WORK

1. Effect of Change in Temperature on the Performance of the Anaerobic Pit:-

In order to study the effect of change in temperature on the performance of the anaerobic pit, the temperatures of the unit will be changed every day by 1^oC for 10 days and will be held for about 12 weeks at $+5^o$C. After this the reverse procedure will be used to return to -5^oC. Usual analyses will be conducted. It is hoped that these changes in temperature will simulate the natural seasonal summer fluctuations in temperature in the field.

2. Anaerobic Digestion of Human Waste:-

Anaerobic digestion studies of concentrated human wastes will be continued at 10^oC and for comparison purposes will also be operated at 20^oC. This should provide information on the minimum temperature at which an anaerobic reactor would have to operate in a plant. If found necessary, dilution of the waste will be carried out to decrease the effect of toxic materials, such as high ammonia concentrations. If funds permit, anaerobic digestion studies on more dilute wastes, such as holding tank wastes and black water wastes will be carried out. This may also include further treatment methods of the supernatant through physical-chemical processes such as lime treatment. The extent and range of these future studies will primarily depend on funding available.

3. Effect of Chemical Inhibitors on Anaerobic Digestion:-

A variety of chemicals are added in some communities for the purpose of odor control and as a bacterial killing agent. The potential effect of such practices on the anaerobic treatment process will be investigated.

REFERENCES

Boyd, W.L., and Boyd, J.W. (1967)
    Microbiological Studies of Aquatic Habitants of
    the Area of Inuvik, Northwest Territories, Arctic
    20: 27-41

Buswell, A.M. (1957)
    Fundamentals of Anaerobic Treatment of Organic Wastes,
    Sewage Ind. Wastes, 29: 717-721.

Edwards R.
    Private Communication. Env. Protection Service,
    Dept. of Environment, Edmonton.

Fair, G.M., and Moore, E.W. (1934)
    Time and Rate of Sludge Digestion and Their Variations
    with Temperature, Sewage Works J., 6: 1.

Fair, G.M., and Moore, E.W. (1937)
    Observations on the Digestion of a Sewage Sludge Over
    a Wide Range of Temperature, Sewage Wastes J., 9: 1.

Fournelle, H.J. (1952)
    Studies of Changes in Sewage Held at Low Temperatures,
    Alaskan Sci. Conf., 3:74.

Hatting, W.H.J., Kotze, J.P., Thiel, P.G., Toerien, D.F.,
and Siebert, M.L. (1967)
    Biological Changes During Adaptation in an Anaerobic
    Digester to a Synthetic Substrate, Water Res. 1: 225-277

Heinke, G.W. (1969)
    Hydrolysis of Condensed Phosphate in Lake Water and
    Waste Water, Ph.D. Thesis, McMaster Univ., Hamilton,
    Ontario.

Hungate, R.E. (1950)
    The Anaerobic Mesophilic Cellulolytic Bacteria,
    Bact. Rev. 14: 1

Imhoff, K. (1906)
    Emscherbrunnen, German Patent No. 187723 of 12th May,
    1906.

Kotze, J.P., Thiel, P.G., and Hatting, W.H.J. (1969)
    Anaerobic Digestion II, Characteristics and Control
    of Anaerobic Digestion, Water Res. 3: 459-494.

Mata, L.J., Carrillo, C., and Villatore, E. (1969)
    Fecal Microflora in Healthy Persons in a Pre-Industrial
    Region, Appl. Microbiol. 17: 596.

McCarty, P.L., Jeris, J.S., McKinney, R.E., Reed, K., and
Vath, C.A. (1962)
    Microbiology of Anaerobic Digestion, Report No. R62-29
    Sedgewick Lab. Sanit. Sci., Massachusetts, Inst.
    Technol., Cambridge, Mass.

McCarty, P.L., Jeris, J.S., and Murdoch, W. (1963)
    Individual Volatile Acids in Anaerobic Treatment,
    J. Water Pollut. Control Fed. 35: 1501.

McCarty, P.L. (1964)
    Anaerobic Waste Treatment Fundamentals, Part I -
    Chemistry and Microbiology, Public Works, September,
    1964, 107-112.

McGhee, T.J. (1968)
    Low-Temperature Anaerobic Digestion, Ph.D. Thesis,
    Univ. Kansas, Lawrence, Kansas.

McKinney, R.E., Liangley, H.E., and Tomilson, H.D. (1958)
    Survival of Salmonella Typhosa During Anaerobic
    Digestion I, Experimental Methods and High Rate
    Digestion Studies, Sewage Ind. Wastes, 30: 1469.

McKinney, R.E. (1962)
    Microbiology for Sanitary Engineers,
    McGraw-Hill, New York.

Miyamoto, H. (1972)
    Performance Study of the Lagoon at Inuvik, N.W.T.,
    Under Winter Operation, M.A.Sc. Thesis, Dept. Civ.
    Eng., Univ. Toronto, Toronto.

Mylroie, R.L., and Hungate, R.E. (1954)
    Experiments on the Methane Bacteria in Sludge,
    Can. J. Microbiol. 1: 55

O'Rourke, J.T., and McCarty, P.L. (1967)
    Anaerobic Treatment at Reduced Temperature, 4th Ann.
    Water Pollut. Control Fed. Conf., New York, N.Y.

Pohland, F.G. (1962)
    Laboratory Investigations on the Thermological Aspects
    and Volatile Acids-Alkalinity Behaviour During
    Anaerobic Sludge Digestion, Ph.D. Thesis, Purdue Univ.

Post, F.J., Allen A.D., and Reid, T.C. (1967)
    Simple Medium for the Selective Isolation of
    Bacteroides and Related Organisms in Sewage,
    Appl. Microbiol. 15: 213.

Rudolfs, W., Hotchkiss, M., Fisher, A.J. and Lackey, J.B.
(1926)
    Studies on Fresh Solids Digestion, New Jers. Agric.
    Expt. Sta. Bull. 427, 50.

Rudolfs, W. (1927)
    Effect of Temperature on Sewage Sludge Digestion,
    Ind. & Eng. Chem. 19.

Siebert, M.L. and Hatting, W.H.J. (1967)
    Estimation of Methane-Producing Bacterial Numbers
    by the Most Probable Number (MPN) Technique,
    Water Res. 1, 13.

Society of American Bacteriologists (1957)
    Manual of Microbiological Methods, p. 112,
    McGraw-Hill Book Co., New York.

Standard Methods for the Examination of Water and Waste
    Water (1971), APHA, AWWA, WPCF, 13th Ed., New York,
    N.Y.

Toerien, D.F., and Siebert, M.L. (1967)
    A Method for the Enumeration and Cultivation of
    Anaerobic "Acid-Forming" Bacteria Present in
    Digesting Sludge, Water Res. 1, 397.

Toerien, D.F., Siebert, M.L. and Hatting, W.H.J. (1967)
    The Bacterial Nature of the Acid-Forming Phase
    of Anaerobic Digestion, Water Res. 1, 497.

Zeller, A.P.J. (1928)
    Effect of Freezing on Sludge Digestion, New Jers.
    Agric. Expt. Sta. Bull. No. 486 (1928).

Zubrycki, L., and Spaulding, E.H. (1962)
    Studies on the Stability of the Normal Faecal Flora.
    J. Bact. 83: 968.